

PREMISES SECTION, CIRCLE OFFICE, LAV KUSH TOWER, EXHIBITION ROAD, PATNA
PHONE: 0612 - 2323405, 2321787 (EMAIL: premisescopat@canarabank.com)

CORRIGENDUM FOR TENDER TOWARDS FURNISHING
WORK AT SONAILI BRANCH DIST- KATIHAR, BIHAR

Sealed tender are invited for Furnishing work at SONAILI BRANCH. DIST-KATIHAR. Revised BOQ of furnishing works is attached herewith. Eligible empaneled furnishing vendors may collect tenders from above mentioned office or from www.canarabank.com/tenders and the date for submission has been extended till 10.09.2025, 03:00 pm.

-sd-
ASSISTANT GENERAL MANAGER

GENERAL ADMINISTRATION SECTION Internal
3RD FLOOR, LUV KUSH TOWER
EXHIBITION ROAD
PATNA, BIHAR – 800 001
Ph. 0612 – 25000214/8102916784
Email: premisescopat@canarabank.com

BOQ OF INTERIOR DESIGN AND FURNITURE WORKS FOR CANARA BANK SONAILI BRANCH , DIST:-KATIHAR, BIHAR.					
BRANCH					
Sl. No	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
1	<p>(FULL HEIGHT PARTITION)- STATIONARY ROOM & OTHERS- Providing and fixing full height double skin partitions in cabins etc, with frames of 50mmx50 mmx1.5mm thick Aluminium section framework at 600 mm c/c. (intervals of 2'-0" x 2'-0" c/c with provision of bigger members at skirting, fixing to door frames), etc, and covered with 6 mm thick BWP Plywood of approved make covered with various finishing layers as per design and details including 1 mm thick High Gloss laminate. The Aluminum section shall be painted with Premium 1st quality paint / polished. High Gloss Laminates shall have a number of horizontl / vertical grooves and the ply under such grooves shall be painted with approved colours.</p>				
	<p>Opening for communication / conversation shall be provided as required as per detailed design and nothing extra shall be paid / deducted for the same.</p>				
	<p>All doors including sliding doors / openable doors, with all fittings including ISI Marked Floor Springs, Hinges, Bolts, etc., shall be included in the same price. Doors shall be of heavy sections matching the partition, and shall have 8.0 mm thick etched glass as per design.</p>				

GENERAL ADMINISTRATION SECTION
3RD FLOOR, LUV KUSH TOWER
EXHIBITION ROAD
PATNA, BIHAR – 800 001
Ph. 0612 – 25000214/8102916784
Email: premisesopat@canarabank.com

सिंडिकेट Syndicate

	All items necessary for completing the above mentioned work are deemed to be included in the scope of work, whether or not they are specifically mentioned in the B.O.Q / tender documents / drawings.	S.Ft.	366		
2	FULL HEIGHT PARTITION (UPS ROOM, 10'-9" height) :- Providing and fixing half height double skin partitions in UPS room with frames of 50mmx50 mmx1.5mm thick Aluminium section framework at 600 mm c/c. (intervals of 2'-0" x 2'-0" c/c with provision of bigger members at skirting, fixing to door frames), etc, and covered with 6 mm thick BWP Plywood of approved make covered with various finishing layers as per design and details including outer side with 1 mm thick High Gloss laminate & inner side with 8mm Calcium Silicate Board /FRC . The boards are to be fixed to the frame work with joints staggered to avoid through cracks to be provided at the horizontal joints of two boards, fixed to the studs using metal to metal flat head screws, including jointing and finishing to a flush finish with recommended jointing compound, jointing tape, angle beads at corners (25 mm x 25 mm x 0.5 mm), joint finisher and one coats putty, two coats of primer and two coats of lustre paint suitable for board as per manufacture's specification and direction of engineer in charge all complete, suitable anchor fastener or metal screws with nylon plugs . All doors including sliding doors / openable doors, with all fittings including ISI Marked Floor Springs, Hinges, Bolts, etc., shall be included in the same price.All items necessary for completing the above mentioned work are deemed to be included in the scope of work, whether or not they are	sft	192		

GENERAL ADMINISTRATION SECTION
3RD FLOOR, LUV KUSH TOWER
EXHIBITION ROAD
PATNA, BIHAR – 800 001
Ph. 0612 – 25000214/8102916784
Email: premisesopat@canarabank.com

सिंडिकेट Syndicate

	specifically mentioned in the B.O.Q / tender documents / drawings.				
3	<p>FULL HEIGHT FULL GLAZED PARTITION (BM cabin, 8'-6" height) :- Providing and fixing 12 mm thk. full ht. Toughened Glass partitions with etched horizontal liner of 1"ht. and 1/2"clear space in between as per design ,Rate should be inclusive of additional Alluminium profile fixed in the flooring and above finished false ceiling level with necessary patch fittings as required to hold the glass partition. All exposed edges surfaces should be machine polished edges. The Rate shall be also inclusive of floor spring ,necessary hardware 3'-0"ht. Matt steel door handles with floor locking arrangement of Enox co. etc. Complete as per desigens and details from the Architects.The rate shall be Inclusive of Horizontal Etched Lining in between 3' to 6' ht. horizontal etched lining of 1"frost and 1/2" clear as per design etc. complete. Supplying and fixing banks logo – sticker as per drawing and design. The door size to be 3ft width & 7ft height. center Door lock to be provided at 3ft height/ bottom of the door. Glass wall ,all complete as per directions for the Architect /Bank (MAKE:- Floor springs-Hyper/ Dorma/Hardwyn,Glass-MODIGUARD / AIS / SAINT)</p>	S.Ft.	216		

GENERAL ADMINISTRATION SECTION
3RD FLOOR, LUV KUSH TOWER
EXHIBITION ROAD
PATNA, BIHAR – 800 001
Ph. 0612 – 25000214/8102916784
Email: premisesopat@canarabank.com

सिंडिकेट Syndicate

4	<p>(HALF HEIGHT PARTITIONS-FULLY PANELLED) (4'-6" Height) Providing and fixing half height double skin partitions in cabins etc, with frames of 50mmx50 mmx1.5 thick Aluminium section framework at 450 mm c/c. (intervals of 1'-6" x 1'-6" c/c with provision of bigger members at skirting), fixing to door frames, etc, The partition shall be provided with 10mm plain glass panel in front and sides (Wherever required) with engraved etching fixed with teak/beech beading. 6 mm thick BWP Plywood of approved make covered with various finishing layers as per design and details including 1 mm thick High Gloss laminate. (All visible beading to be of 1st quality "gamhar") and shall be painted with Premium 1st quality paint / polished as per instructions of Bank. All necessary hardware such as hinges, bolts, etc, and any other hardware required for the wicket door, shall be included in the price. Laminates shall have a number of horizontal / vertical grooves and the ply under such grooves shall be painted with approved colours. Openings for communication / conversation shall be provided as required as per detailed design and nothing extra shall be paid / deducted for the same.</p>				
	<p>All items necessary for completing the above mentioned work are deemed to be included in the scope of work, whether or not they are specifically mentioned in the B.O.Q / tender documents / drawings. All exposed wooden surfaces are to be painted with Premium quality paint as per Specifications.</p>	S.Ft.	56		

सिंडिकेट Syndicate

5	(COMPUTER CASH AND CASH CAGE PARTITIONS - FRONT) Providing and fixing cash cage glazed partition on top of cash counter above 5'0" UPTO 7'0" facing the customer with 12 mm thick clear toughened glass (Modiguard) fixed in a frame of 50mmx50 mmx1.5mm thick Aluminium section, bwp ply, High Gloss laminate /polished teakwood members framework on all three sides, duly polished, all beading etc. as required, all cutting, polishing of glass at two positions -one at 4ft of 4inch width,6inch height & other at 5ft of 6inch dia as required, all complete. Bank Logo to be provided on Glass	S.Ft.	16		
6	(COMPUTER CASH AND CASH CAGE PARTITIONS - SIDES & REAR- HEIGHT UPTO 7'0" HT) Providing and fixing cash cage partition, as per specifications given in Item No. 2 mentioned above, modified in height and the openings required to suit the requirements of cash cages, etc, 10 mm glass from 4'-0" to 7'-0", along with supporting members all doors, as per specifications given in Item No. 1 above, all hardware for doors excluding door closers, godrej night latches which shall be paid for separately, all complete. The front of the cash cage shall be done in a decorative design, as shown in the attached drawings and details. Proper cut tray to be providing for passing documents between tables. Film to be provided on Glass.	S.Ft.	68		
7	(HYDRAULIC DOOR CLOSER) Providing and fixing Hydraulic door closers of specified brand, all complete as per instructions of Architect / Employer. (Makes -EFFICIENT GADGETS / Everite / Hardwyn. / GODREJ)	Each	4		

GENERAL ADMINISTRATION SECTION
3RD FLOOR, LUV KUSH TOWER
EXHIBITION ROAD
PATNA, BIHAR – 800 001
Ph. 0612 – 25000214/8102916784
Email: premisesopat@canarabank.com

सिंडिकेट Syndicate

8	(LOCKS) Providing and fixing "Godrej Night Latch" / "Godrej Mortice Lock" in required places, all complete with fixing, fitting, etc. Cash Cabin should be provided with Godrej Night Latch	Each	1		
9	(TABLES) Providing and Placing new executives tables alongwith matching credenza of plan size (basic) as given below, table top to be made of 19 mm thick BWP plywood of approved make, edged with beading of 2" x 1-12" approx), cut to required shape, top of table to have 1.0 mm thick laminte, and teakwood beading to be polished to required colour and finish. Table to have a vertical modesty panel of 19 mm thick plywood of approved make laminated/Plain with High Gloss laminate (1.0 mm thick) from the outer side and Laminate 0.8 mm thick on the inner side. Modesty partition to have 1st quality beading on top as per design and specification the internal surface.				
	High Gloss Laminate to have a no. of grooves as per design and drawings. A chest of drawers shall support the table on 1 side (except in the case of staff tables of 4'-0" width, where the table shall be supported on one side by the credenza unit) integrally connected to the modesty partition, made of 19 mm thick plywood of approved make, drawers to slide on drawer slides (EBCO / Godrej/Link), and made of 19 mm thick grade bwp board for all sides and bottom cabine shutters of 19 mm thick plywood of approved make, cabinet hinges to be t-type, self closing, EBCO / Godrej/Link, all edges of all blockboard / plywood to be sealed with 1st quality teakwood edging, including blockboard members touching the ground.				

GENERAL ADMINISTRATION SECTION
3RD FLOOR, LUV KUSH TOWER
EXHIBITION ROAD
PATNA, BIHAR – 800 001
Ph. 0612 – 25000214/8102916784
Email: premisesopat@canarabank.com

सिंडिकेट Syndicate

	Drawers and cabinet shutters to be laminated on all external surfaces with 1.0 mm thick High Gloss laminate, and all internal surfaces with with 0.8 mm thick laminate as Specified above. All drawers and cabinets (both in tables and credenza) to provided with high quality 'Gogrej/Link' locks, and high quality handles .				
	The other end of the table to be supported / integrated with a credenza unit of basic 2'-6" height, or as required, top, back and sides made out of 19 mm thick BWP plywood of approved make laminated/Plain , top to be finished with 1.0 mm thick High Gloss laminate and teakwood beading o/o 1" x 1", carved as per design, and finished as per table Specifications above.				
	Drawers and cabinets, cabinet shutters, etc.Shutters will be hung by hinges, locks, magnetic door catcher and satin finished S. S. handles etc. of approved make to be as described in table specifications above, including all finishing details, and one glazed cabinet shutter in 1st Quality Teakwood frame, finished with laminate also to be laminated with 1.0 mm thick High Gloss laminate grooves as / design				
	Keyboard unit as per design and specification to be included in the rate.				
	High Gloss Lamianate pasting pattern /design as per banks design guideline/detail/reference.				
a)	Manager Table (6'-6" x 3'-0")	Each	1		
b)	Officer Table (4'6"x2'6")/(5'0"X2'6")	Each	4		
c)	Daftari Table/MAY I HELP U (4'0"x2'0")	Each	1		
d)	Credenza (1'6"x3'6")/(1'6"x3'0")	Each	5		

GENERAL ADMINISTRATION SECTION
3RD FLOOR, LUV KUSH TOWER
EXHIBITION ROAD
PATNA, BIHAR – 800 001
Ph. 0612 – 25000214/8102916784
Email: premisescopat@canarabank.com

सिंडिकेट Syndicate

e)	Full Ht cabinet;-(elevation area calculation))Providing & fixing STORAGE CABINETS of 8'-0" ht and 1'-6" deep as per layout plan made up of 19mm BWP plywood of approved Make and finished with 1mm thick High Gloss laminate of Make, shade as approved and per detailed drawing. With 2-3 shelves made up of 19mm BWP plywood, all unexposed portion shall be finished with 0.8mm thk laminate from make mentione above. The work includes supplying, fixing of hinges, magnetic catchers, handles, locks, teak lipping etc complete in all respects to the complete satisfaction of the Architect.	SFT	274		
f)	Sill Ht cabinet;-(elevation area calculation))Providing & fixing STORAGE CABINETS of 2'-6" ht and 1'-6" deep as per layout plan made up of 19mm BWP plywood of CENTURY/ GREEN Make and finished with 1mm thick High Gloss laminate of CENTURY/GREENLAM Make, shade as approved and per detailed drawing. With 2-3 shelves made up of 19mm BWP plywood, all unexposed portion shall be finished with 0.8mm thk laminate from make mentione above. The work includes supplying, fixing of hinges, magnetic catchers, handles, locks, etc complete in all respects to the complete satisfaction of the Architect.	SFT	92		
g)	Center Table (3'-0"x1'-9") 12 mm glass top with glass shelf below	Each	1		

सिंडिकेट Syndicate

10	(COUNTERS) Providing and fixing COMPUTER COUNTERS (formerly from as LEDGER COUNTERS) made out of 19 mm thick BWP plywood of approved make and as per the attached drawing with the working top of 2'-6" width at 2'-6" level,, all complete with 1.0 mm thick High Gloss laminate on all visible surface, tabletops, customer top, etc, and all drawers etc. to be with 0.8 mm thick laminated. 12mm thick glass as a screen shall be provided in front, with a 3" gap from the counter top where required. Height of Glass: 24". Glass to be inserted in polished teakwood members, size 2" x 2", appropriately finished. Keyboard Tray to be provided on Special Keyboard Slides, and wristrest to be given. Drawer Slides to be used for all drawers. All locks to be of Godrej / Link. All drawers, cabinets, Keyboard, etc. to be lockable. Footrest to be provided. (See Detailed drawing attached). The Front of the Computer Counter shall have decorative finishing in ply and laminate as shown in the drawing attached.	R.Ft.	0.00		
11	(CASH COUNTERS) Providing and fixing Cash Counters, to be made entirely of 19 mm thick BWP plywood for all surfaces, with the working top of 3'-0" width at 2'-6" level, and the customer top of 1'-6" width at 4' level. Chest of drawers (lockable) with Godrej / Links to be provided and on cabinet just below drawer. The working top to be 3'-0" wide, fully detailed out with overhangs and supports as per detail drawings, all edges to be sealed with 1 mm thick High Gloss laminate as per directions, all internal laminate of modesty table should be 0.8 mm thick laminate all complete with footrest of ghambhar wood of section 4" x 2", all complete with all hardware, supporting	R.Ft.	5.00		

GENERAL ADMINISTRATION SECTION
3RD FLOOR, LUV KUSH TOWER
EXHIBITION ROAD
PATNA, BIHAR – 800 001
Ph. 0612 – 25000214/8102916784
Email: premisesopat@canarabank.com

सिंडिकेट Syndicate

	clips, etc. The front of the Counter shall have decorative features, all complete, as per the designs and drawings attached..The counter should have front, both sides modesty panel/ legs.)				
12	COULUM PANELING WITH LAMINATE FINISH/wall paneling - Providing & Fixing laminate finish paneling for columns, etc. made out offrames of 50mmx50 mmx1.5 thik Aluminium section framework at 600 mm c/c (vertical/horizontal) both ways, covered with 12mm thick BWP ply upto false ceiling height. All exposed surfaces of the paneling shall be finish with approved color 1.00 mm thk High Gloss laminate complete as per detail drawing & instructions of Architect.	SFT	228		
13	Main Entrance Door: Full.ht.Glass Partitions (WITH DOOR) Entrance side Providing and fixing 12 mm thk. full ht. Toughened Glass partitions with etched horizontal liner of 1"ht. and 1/2"clear space in between as per design ,Rate should be inclusive of additional Alluminium profile fixed in the flooring and above finished false ceiling level with necessary patch fittings as required to hold the glass partition. All exposed edges surfaces should be machine polished edges. The Rate shall be also inclusive of floor spring ,necessary hardware 3'-0"ht. Matt steel door handles with floor locking arrangement of Enox co. etc. Complete as per desigens and details from the Architects.The rate shall be Inclusive of Horizontal Etched Lining in between 3' to 6' ht. horizontal etched lining of 1"frost and 1/2" clear as per design etc. complete. Supplying and fixing banks logo – sticker as per drawing and design. The door size to be 3ft width & 7ft height. center Door lock to	S.Ft.	94.00		

GENERAL ADMINISTRATION SECTION
3RD FLOOR, LUV KUSH TOWER
EXHIBITION ROAD
PATNA, BIHAR – 800 001
Ph. 0612 – 25000214/8102916784
Email: premisesopat@canarabank.com

सिंडिकेट Syndicate

	be provided at 3ft height/ bottom of the door. Glass wall ,all complete as per directions for the Architect /Bank (MAKE:- Floor springs-Hyper/ Dorma/Hardwyn,Glass-MODIGUARD / AIS / SAINT)				
14	(NOTICE BOARD) Providing and fixing a notice board near the Waiting area, frame to be made of 1st quality hardwood, and infill of 12 mm thick 'Celotex, board, duly covered with "Matte" quality cloth of approved colour and make. Visible surfaces of Frame to be painted with "Premium 1st Quality Paint" in approved colour and shade, and internal frames and internal surface of celotex board to be painted with priming coat. The frame is to be securely fixed to the wall, all complete as per directions for the Architect / Employer. Size: 2'-6" x 3'-0".	Each	1		
15	(SUGGESTION BOX) Providing and fixing one suggestion box, made with 12 mm bwp ply as per standard design and specifications of the Bank, fully complete, with 0.8 mm thick High Gloss laminated inside and outside, lock, glass, lettering on top, etc.	Each	1		
16	Providing and fixing Cheque writing/slip rack projected/supported from wall 6'0" x1'-3" and a C.T. as per design with suggestion box,first aid box,suggestion box.	Each	1		
17	(CHEQUE DROP BOX) Providing and fixing one Cheque drop box, made with 12 mm bwp ply as per standard design and specifications of the Bank, fully complete, with 0.8 mm thick High Gloss laminated inside and outside, lock, glass, lettering on top, etc.	Each	1		
18	FALSE CEILING				
i)	Gypsum board false ceiling				

GENERAL ADMINISTRATION SECTION
3RD FLOOR, LUV KUSH TOWER
EXHIBITION ROAD
PATNA, BIHAR – 800 001
Ph. 0612 – 25000214/8102916784
Email: premisesopat@canarabank.com

सिंडिकेट Syndicate

	Gypsum board false ceiling with 4"Vertical band /drop of per detail drawing & instructions of Architect				
	Providing and fixing in position Gypsum Board False Ceiling including Two coats of Plastic emulsion Paint of appd.quality as per manufacturer's specifications and instructions with 12.5 mm thick `Gypboard' Screw-fixed to the underside Of suspended G.I. grid. G.I. grid should be Constructed and suspended from the main ceiling as per manufacturer's instructions and as per specifications using Original Co. Specified Framework Sections G.I.24 gauge The Gypboard should be fixed to G.I. grid with 25 mm long Drawali Screws. The `Gypboard ' to be used should be 12.5mm thick tapered edge boards. The boards should Be taped and filled from underside to give smooth, seamless ceiling. The rate should include necessary additional ceiling sections and intermediate channels openings for light fixtures, A.C. ducts, vertical drops, offsets. etc.				
	Additional Intermediate channels should be fixed to strap hangers for additional support to prevent strap hangers from buckling/swaying at every 1200 mm. Item to be completed in all respect including necessary sleeves for ducts finishing of joints cut outs supports for A.C. grills, light fixtures, speakers etc.				
	The rate should include necessary additional ceiling sections and intermediate channels openings for light fixtures, A.C. ducts, vertical drops, offsets.and with two coats of putty, two coats of approved primer, and three coats of approved lusture paint. The visible drop should be of 4" & payment shall be made only for visible drop of 4".	SQ.F T.	415		

GENERAL ADMINISTRATION SECTION
3RD FLOOR, LUV KUSH TOWER
EXHIBITION ROAD
PATNA, BIHAR – 800 001
Ph. 0612 – 25000214/8102916784
Email: premisesopat@canarabank.com

सिंडिकेट Syndicate

II)	Grid False Ceiling				
	<p>Providing & fixing false ceiling at all heights with false ceiling tiles of Size 595x595 mm of approved texture, design and patterns having moisture content less than 2%, humidity resistance of 99%, NRC 0.50 to 0.75 as per IS 8225:1987, Non combustible as per BS 476 (part-4)-1970 and lightreflectance of 85% (minimum) to be laid in true horizontal level suspended on inter-locking metal T-Grid of hot dipped galvanised iron section of 0.33mm thick (galvanized @ 120 grams per sqm including both sides) comprising of main-T runners of size 15x32 mm of length 3000 mm, cross - T of size 15x32 mm of length 1200 mm and secondary intermediate cross-T of size 15x32 mm of length 600mm to form grid module of size 600 x 600 mm, suspended from ceiling using galvanised mild steel items (galvanizing @ 80 grams per sqm) i.e. 50 mm long, 8 mm outer diameter M-6 dash fasteners, 6 mm dia fully threaded hanger rod upto 1000 mm length and L-shape level adjuster of size 85x25x2 mm. Galvanised iron perimeter wall angle of size 24x24x0.40 mm of length 3000 mm to be fixed on periphery wall / partition with the help of plastic rawl plugs at 450 mm center to center and 40 mm long dry wall SS screws. The work shall be carried out as per specifications, drawing and as per directions of Engineer-in-Charge, With semi perforated micro tegular edged GRG false ceiling tiles.</p>	SQ.F T.	584		

GENERAL ADMINISTRATION SECTION
3RD FLOOR, LUV KUSH TOWER
EXHIBITION ROAD
PATNA, BIHAR – 800 001
Ph. 0612 – 25000214/8102916784
Email: premisesopat@canarabank.com

सिंडिकेट Syndicate

19	Panel box covering : Shall be made up of 19mm th BWP boarer free ISI marked -Fire resistant ply on all the sides. shutter shall be of 19mm th block board of BWPgrade ISI marked-Fire resistant (Minimum 2 hr.) and shall have holes 1/2" dia (25nos.) for ventilation and have glass piece (9"x9") for meter reading and shall be finished with 1.00mm High Gloss laminate of approved shade on all exposed sides and inside finished with 0.8 mm thick laminated. The rate is inclusive of all locks of Godrej or equivalent make, SS tower bolts, SS handles, heavy duty SS hinges etc.all hardware complete. Prior confirmation shall be obtained from the officer in charge for all the hardware, locks and fixture etc, complete. (Note :- Box should not touch the ground, Elevation area to be measured for payment)	SQ.F T.	32		
20	SHUTTER BOX COVERING -Shutter covering with ACP (aluminium composite panel) of 4mm thk. approved color & make with aluminium framing as/required with the provision of rolling shutter maintenance trap door,ele. point all complete job as per standard & specification	S.Ft.	62		
21	Vertical blinds : Providing & fixing levelor 10mm vertical blinds having top rail 39mmX34mm hgh with wall thickness of 1.2mm having 25mm decorative insert. Control unit shall be of Derlin. Plastic runner shall be moulded from Derlin plastic with artification head rail & the top end of the louver fabric shall be polyster viscose/polyster yarn dyed in fast colour with or without protective coating on louvers with chemical for stain resistance and soil repetancy and shall have GI weight and steel/polymer ball chain for spacing.	SQ.F T.	0		

GENERAL ADMINISTRATION SECTION
3RD FLOOR, LUV KUSH TOWER
EXHIBITION ROAD
PATNA, BIHAR – 800 001
Ph. 0612 – 25000214/8102916784
Email: premisesopat@canarabank.com

सिंडिकेट Syndicate

	The top rail should be fixed on bracket of 14 SWG galvanized spring steel fixed firmly on walls by nylon plug and screw as per approved design and direction of the Architect. (Makes - Vista, Universal).				
22	3 Seater Sofa - Size 3 Seater (2130x870x870)mm & Seat Height 400mm. Frame used is treated American pine wood with termite free & borer free. Soft & comfortable cushion with high density and resilient foam. Frame used is Treated american pine wood & the wood used in sofa has been 8% moisture, this prevents the wood from wrapping and bending. all wood used is termite free and borer free. Foam of sofa comfortable cushion with high density and resilient foam. all upholstery materials used in specially designed. all plywood used in BWP Grade.	Each	0		
23	2 Seater Sofa - Size 2 Seater (1420x870x870)mm & Seat Height 400mm. Frame used is treated American pine wood with termite free & borer free. Soft & comfortable cushion with high density and resilient foam. Frame used is Treated american pine wood & the wood used in sofa has been 8% moisture, this prevents the wood from wrapping and bending. all wood used is termite free and borer free. Foam of sofa comfortable cushion with high density and resilient foam. all upholstery materials used in specially designed. all plywood used in BWP Grade.	Each	0		
24	Providing & fitting paper based HD quality wallpaper as per approved design in Senior manager cabin	Sq.ft.	75		

सिंडिकेट Syndicate

25	Providing & fixing 8mm Glass rack in stainless steel F bricket for display purpose. Size 6"x18"	Each	4		
26	Tactile Tiles:- Polyurethane tiles of yellow colour, size 12"x12", 6mm thick, Anti skid, non-fade, Slip-resistant, for visually impaired safety measures. Durable and sturdy design with polyurethane coating for extra protection. Waterproof and easy to maintain for long-lasting use.	Sq.ft.	28		
27	Visible Laminate Change with 1 mm High Gloss of Cash Counter & 2 nos Officer Table with transportation from fitted as per approved layout with proper finish.	nos	0		
28	Dismantle & Removal of existing partition ,false ceiling, counters etc in Branch Room.debris from site, carrying and disposal of malba to dumpyard. as per bank/branch incharge direction. (Branch &atm)	LS	1.00		
TOTAL BRANCH					
ATM					
Sl. No	DESCRIPTION	UNIT	QTY	RAT E	AMOUN T
1	Paneling in the front portion of ATM Room providing & fixing in position .ACP (Aluminium Composite panel) with framing of aluminium tube section of min1.5"x1" and 20 gauge 2'-0" c/c both way .ACP to be in 2' wide or distributed equally .panel to be fixed to the frame with 3m or equi-valent adhesive joints to be finished with silicon based sealant .ACP thickness of 3mm.	S.FT.	118.00		
3	Providing & fixing Back room partition ACP both side. (Aluminium Composite panel) with framing of aluminium tube section of min1.5"x1" and 20 gauge 2'-0" c/c both way .ACP to be in 2' wide or distributed equally .panel to be fixed to the	S.ft.	64.00		

GENERAL ADMINISTRATION SECTION
3RD FLOOR, LUV KUSH TOWER
EXHIBITION ROAD
PATNA, BIHAR – 800 001
Ph. 0612 – 25000214/8102916784
Email: premisesopat@canarabank.com

सिंडिकेट Syndicate

	frame with 3m or equi-valent adhesive joints to be finished with silicon based sealant .ACP thicknessof 3mm. with Aircon Louvers 6" powder coated aluminium Louvers. All complete as per directions for the Architect /Bank				
4	Main Entrance Door: Full.ht.Glass Partitions (WITH DOOR) Entrance side Providing and fixing 12 mm thk. full ht. Toughened Glass partitions with etched horizontal liner of 1"ht. and 1/2"clear space in between as per design ,Rate should be inclusive of additional Aluminium profile fixed in the flooring and above finished false ceiling level with necessary patch fittings as required to hold the glass partition. All exposed edges surfaces should be machine polished edges. The Rate shall be also inclusive of floor spring ,necessary hardware 3'-0"ht. Matt steel door handles with floor locking arrangement of Enox co. etc. Complete as per desigens and details from the Architects.The rate shall be Inclusive of Horizontal Etched Lining in between 3' to 6' ht. horizontal etched lining of 1"frost and 1/2" clear as per design etc. complete. The door size to be 3ft width & 7ft height. Door stopper to be provided. center Door lock to be provided at 3ft height/ bottom of the door.Supplying and fixing banks logo – sticker as per drawing and design. Glass wall ,all complete as per directions for the Architect /Bank (MAKE:-Floor springs-Hyper/ Dorma/Hardwyn,Glass-MODIGUARD / AIS / SAINT)	S.Ft.	62.00		
5	GRID FALSE CEILING:- Providing & fixing false ceiling at all heights with false ceiling tiles of Size 595x595 mm of approved texture, design and patterns having moisture content less than 2%, humidity	S.FT	75.00		

GENERAL ADMINISTRATION SECTION
3RD FLOOR, LUV KUSH TOWER
EXHIBITION ROAD
PATNA, BIHAR – 800 001
Ph. 0612 – 25000214/8102916784
Email: premisescopat@canarabank.com

सिंडिकेट Syndicate

	<p>resistance of 99%, NRC 0.50 to 0.75 as per IS 8225:1987, Non combustible as per BS 476 (part-4)-1970 and lightreflectance of 85% (minimum) to be laid in true horizontal level suspended on inter-locking metal T-Grid of hot dipped galvanised iron section of 0.33mm thick (galvanized @ 120 grams per sqm including both sides) comprising of main-T runners of size 15x32 mm of length 3000 mm, cross - T of size 15x32 mm of length 1200 mm and secondary intermediate cross-T of size 15x32 mm of length 600mm to form grid module of size 600 x 600 mm, suspended from ceiling using galvanised mild steel items (galvanizing @ 80 grams per sqm) i.e. 50 mm long, 8 mm outer diameter M-6 dash fasteners, 6 mm dia fully threaded hanger rod upto 1000 mm length and L-shape level adjuster of size 85x25x2 mm. Galvanised iron perimeter wall angle of size 24x24x0.40 mm of length 3000 mm to be fixed on periphery wall / partition with the help of plastic rawl plugs at 450 mm center to center and 40 mm long dry wall SS screws. The work shall be carried out as per specifications, drawing and as per directions of Engineer-in-Charge, With semi perforated micro tegular edged GRG false ceiling tiles.</p>				
6	<p>Shutter covering with ACP (aluminium composite panel) of approved color & make with the provision of rolling shutter maintenance trap door , allcomplete job as per standard & specification.</p>	SQ.F T.	58.00		
	TOTAL ATMC65				
	NET TOTAL(BRANCH + ATM)				
	GST @18% extra				
	Notes:-				
	Contractor to Note that:-				

GENERAL ADMINISTRATION SECTION Internal
3RD FLOOR, LUV KUSH TOWER
EXHIBITION ROAD
PATNA, BIHAR – 800 001
Ph. 0612 – 25000214/8102916784
Email: premisesopat@canarabank.com

सिंडिकेट Syndicate

a)	Footrests to be provided (laminated) with each table / counter without any extra charges, @ 1 per person.				
b)	Extra members, wherever required for stability / otherwise, to be provided with the required finish without ant extra charges.				
c)	All the visible laminate of 1 mm should be High Gloss Laminate &				
d)	Vendor has to quote final rate after discount. No Additional Discount to be quoted.				
e)	GST Bills of purchasing of materials to be produced in front of Architect during work progress.				

This corrigendum shall be part of Tender documents and shall be submitted alongwith.

GENERAL ADMINISTRATION SECTION
3RD FLOOR, LUV KUSH TOWER
EXHIBITION ROAD
PATNA, BIHAR – 800 001
Ph. 0612 – 25000214/8102916784
Email: premisesopat@canarabank.com