

**CORRIGENDUM FOR CHANGE IN SPECIFICATION**

संदर्भ/ REF: MCEM/ SARJU/661/1 /2025-26/PKG.

दिनांक/ Date : 31.10.2025

- **Tender No.** : 661/MCEM/2025-26 date of issue 17.10.2025
- **Name of work** : Selection of contractor for Comprehensive Civil Repair work including Structural Repair work at Bank owned Building at "SARJU HOUSE", MIDC, 7<sup>th</sup> Street, Andheri (East), Mumbai.
- **Points discussed in Pre-Bid meeting dated** : 30.10.2025
- **Last Date of Receiving Tender** : 07.11.2025 upto 3.00 pm.
- **Opening of Technical Bid** : 07.11.2025 on or after 3.30 pm.

Tender document uploaded in the website has the following corrigendum :

Item No in Price bid	Original Description	To be read as
Part-B Item No. 33	<b>PROVIDING / FIXING OF NEW VITRIFIED ANTI SKID FLOOR TILES INSIDE THE WASHROOM (WHEREVER DAMAGED ONLY)</b> : Providing and laying 600 x 600 x 8 mm thk. vitrified tiles as specified below conforming to I.S.15622-2006 with water absorption less than 0.08% for flooring of an approved, quality, make and pattern /design for flooring including cement mortar bedding of 25 mm thick in 1:4 proportion, cutting, leveling, jointing, filling the joints by neat cement slurry or approved colour grout, curing, finishing etc complete as directed by Engineer In Charge. Light colored antiskid / matt vitrified tiles	<b>PROVIDING / FIXING OF NEW VITRIFIED ANTI SKID FLOOR TILES INSIDE THE WASHROOM (WHEREVER DAMAGED ONLY)</b> : Providing and laying 600 x 600 x 8 mm thk. vitrified tiles as specified below conforming to I.S.15622-2006 with water absorption less than 0.08% for flooring of an approved, quality, make and pattern /design for flooring including cement mortar bedding of 25 mm thick in 1:4 proportion, cutting, leveling, jointing, filling the joints by neat cement slurry or approved colour grout, curing, finishing etc complete as directed by Engineer In Charge. Light colored antiskid / matt vitrified tiles <b>(Basic cost of tiles Rs. 85/-per sqft excluding GST)</b>
Part-B Item No. 34	<b>PROVIDING / FIXING OF NEW CERAMIC WALL TILES INSIDE THE WASHROOM &amp; PANTRY (WHEREVER DAMAGED ONLY)</b> : Providing and fixing 6mm thk. ceramic tiles as specified below conforming to I.S. 15622-2006 of approved quality, pattern and colour for dado in the wet area including preparing the surface and levelling in the desired line, backing of 20 mm thk. cement mortar in proportion 1:3 with approved waterproofing compound, square cut top edge or chamfered top edge in cement mortar 1:3, cement float, machine cutting, leveling, jointing, filling the joints with neat cement slurry or approved colour grout, finishing, curing etc complete as directed by Engineer In Charge. Light coloured glazed ceramic tiles.	<b>PROVIDING / FIXING OF NEW CERAMIC WALL TILES INSIDE THE WASHROOM &amp; PANTRY:</b> Providing and fixing 6mm thk. ceramic tiles as specified below conforming to I.S. 15622-2006 of approved quality, pattern and colour for dado in the wet area including preparing the surface and levelling in the desired line, backing of 20 mm thk. cement mortar in proportion 1:3 with approved waterproofing compound, square cut top edge or chamfered top edge in cement mortar 1:3, cement float, machine cutting, leveling, jointing, filling the joints with neat cement slurry or approved colour grout, finishing, curing etc complete as directed by Engineer In Charge. Light colored glazed ceramic tiles. <b>(Basic cost of tiles Rs. 80/-per sqft excluding GST)</b>
Part-B Item No. 35	<b>PROVIDING / FIXING OF GRANITE STONE FOR MAKING PANTRY PLATFORM / DOOR &amp; WINDOW FRAMES:</b> Providing and fixing polished natural stone tiles as specified below of approved quality, pattern and colour for dado including preparing the surface and levelling in the desired line, backing of 20 thk. cement mortar in porportion 1:3, square cut top edge or chamfered top edge in cement mortar 1:3, cement float, machine cutting, leveling, jointing, filling the joints with neat cement or pigment mixed with cement, polishing, finishing, curing etc complete as directed by Engineer In Charge. 18mm thk. Steel gray Granite tiles/slab	<b>PROVIDING / FIXING OF GRANITE STONE FOR MAKING PANTRY PLATFORM / DOOR &amp; WINDOW FRAMES:</b> Providing and fixing polished natural stone tiles as specified below of approved quality, pattern and colour for dado including preparing the surface and levelling in the desired line, backing of 20 thk. cement mortar in porportion 1:3, square cut top edge or chamfered top edge in cement mortar 1:3, cement float, machine cutting, leveling, jointing, filling the joints with neat cement or pigment mixed with cement, polishing, finishing, curing etc complete as directed by Engineer In Charge. <b>18mm thick steel Gray Granite tiles /slab</b> <b>(Basic cost of tiles Rs. 190 /-per sqft excluding GST)</b>

All other tender terms & specification remains unchanged.