

SCHEDULE OF QUANTITIES

INTERIOR FURNISHING WORK FOR HO ANNEXE AT SOUTH END, BENGALURU

S.No	DESCRIPTION OF ITEM	QTY	UNIT	RATE in Rs	AMOUNT in Rs
I	PARTITIONS				
1	FIXED GLAZED PARTITION WITH TOUGHENED GLASS				
	Providing and fixing of full height fixed partitions with 12mm thick toughened glass partitions fixed using powder coated solid fish mouth sections (30x42x3mm) of unit weight 1.53 Kg/m of approved colour at the top, bottom and sides of approved makes including cutting, making holes in glass, fixing the fittings in the floor and ceiling /partition supports with proper levels. The glass joints to be consealed with silicon sealants. Rate shall be for all necessary materials, labour, transportation for the works and measurements shall be made for the entrie area of glass including the sections.	600	Sft		
	Location : Main Entrnace, Cabins, Mini Conference				
2	TOP SUPPORT PARTITION ABOVE TOUGHENED GLASS				
	Providing and fixing double skin partition using 50mmx50mm Aluminium sections of thickness 1.18mm with verticals at a maximum spacing of 2 ft. c/c in both directions and anchored to the true ceiling and ajacent partitions. The partition shall be covered by 8mm thick MR grade commercial thick plywood on both sides and on the bottom face. The partition shall project below the false ceiling level by 100mm and the exposed surfaces shall be provided with 1.2mm thick gloss finish PVC laminate of approved shade. Payable area shall be the area of the frame work.	180	Sft		
	Location : Above Glass partitions				
3	ALUMINIUM PROFILE PARTITION (with Toughened Glass)				
	Providing and fixing fully glazed partition using powder coated aluminium profile section of size 46mm x 20mm for alround frameworks. The horizontal profiles shall be provided at top and bottom and the vertical profiles shall be provdied every 26" to 32". The panels shall be glazed with toughened ultra clear glass of 12mm thickness. Item includes all necessary gaskets, materials, labour, transportation for the works. Colour of powder coating shall be approved by the Engineer In Charge.	120	Sft		
	Location : Cabin Front Glass				

SCHEDULE OF QUANTITIES

INTERIOR FURNISHING WORK FOR HO ANNEXE AT SOUTH END, BENGALURU

S.No	DESCRIPTION OF ITEM	QTY	UNIT	RATE in Rs	AMOUNT in Rs
4	FULLY PANELLED PARTITION				
	Providing and fixing double skin partition using 50mmx50mm Aluminium sections of thickness 1.1mm with verticals at a maximum spacing of 3' ft. c/c in both directions supported to the walls, floor and ceiling. The partition shall be covered by 8mm MR grade commercial thick plywood on both sides. Necessary openings for the door shall be provided which shall be finished with beach wood beadings. The finishing shall be provided upto the false ceiling level. Payable area shall be for the height of frame work excluding the door openings. Surface finishes shall be as per subhead V.	3355	Sft		
	Location : Conf Room Sides, Record Room, GM/DGM Cabin sides				
5	GLASS DOORS FOR PARTITIONS				
	Providing and fixing door of size 3' x 8' using 12mm thick toughened glass including patch fittings of approved makes and fixed at the bottom and top using heavy duty floor spring and pivot respectively of Ozone/Dorma make. The necessary hardwares shall be of stainless steel finish matching with the patch fittings. The item shall also include 2 Nos of powder coated metal handles of matte finish (Basic Cost : Rs. 2000/-+GST per set). Rate shall be for all necessary materials, labour, transportation for the works. Each door shall have approximate dimension of 3' x 8'. Any change in dimension shall be paid proportionately.	18	Nos		
6	DOOR FOR PARTITIONS - FLUSH DOOR				
	Providing and fixing door of size 3' X 8' (W X H) using 30mm thick water proof flush door shutters with around beach wood beading. An opening of required size shall be provided and fixed with 6mm thick fluted glass using beechwood beadings. The door shall be finished with 1mm thick lamination of approved shade except for the opening. All the exposed wood / wooden beadings shall be neatly finished with 2 coats of wood polish & stained to required colour. All the accessories used shall be of concealed type. There shall be 4" height skirting in the bottom with 1mm lamination finish of approved shade. Each door to be fixed to the partition using 5" length stainless steel hinges - 3 Nos and provided with 1 No. of concealed mortice lock, 2 Nos SS tubular handles, 1 No door closer (Godrej make or equivalent) and SS door stopper. Any variation in size shall be paid proportionately.	12	No		
	Location : GM Ante Room, Conf Room, Toilet Entrance				

Internal

SCHEDULE OF QUANTITIES					
INTERIOR FURNISHING WORK FOR HO ANNEXE AT SOUTH END, BENGALURU					
S.No	DESCRIPTION OF ITEM	QTY	UNIT	RATE in Rs	AMOUNT in Rs
7	FIRE RESISTANT DOORS WITH FRAME				
	Supplying and fixing in position steel fire doors & suitable frame conforming to IS 3614 Part 2 & BS 476 Part 20 & 22 having 2 Hours fire rating with powder coated finish, vision panel.	1	No		

Internal

Internal

SCHEDULE OF QUANTITIES

INTERIOR FURNISHING WORK FOR HO ANNEXE AT SOUTH END, BENGALURU

S.No	DESCRIPTION OF ITEM	QTY	UNIT	RATE in Rs	AMOUNT in Rs
8	GI FRAMED DIVIDER PARTITION Providing and fixing divider partitions as per sketch using outer framework using MS Flats 50mmx5mm as per design, provided with 8mm thick fluted glass, laminated 18mm thick plywood panels as per design. The frame work shall be welded as per design and joints shall be neatly grinded & buffed. All exposed surfaces shall be finished with primer and PU paint in two or more coats. Location : Workstation cluster ends	220	Sft		
9	ALUMINIUM FRAMED PARTLY GLAZED LOW HEIGHT PARTITION (FOR CUBICLES) Providing and fixing of double skin partition using 50mmx50mm (5% tolerance allowed)) aluminium sections of thickness 1.18mm for frame works with verticals at a maximum spacing of 2'6" C/C and three horizontals at 0', 2', 3.5'. The panel shall be covered by 6mm thick MR grade commercial plywood on both sides for full height. The exposed edges, trims shall be provided with 8mm thick MDF beadings. There shall be 4" height skirting in the bottom on both sides with 1mm lamination finish. All the exposed wood / woden beadings shall be neatly finished with minimum 2 coats of PU paint (Duco Paint) of approved shade. Necessary Holes must be made in the frame sections to run the wires, computer cables wherever necessary. Similarly necessary cuttings to be made in the partition to fix switch boxes of electrical, telephone sockets, computer Information outlets etc. Surface finishes shall be as per Subhead V	920	Sft		
II	FURNITURES				
1	GM TABLES				

Internal

SCHEDULE OF QUANTITIES					
INTERIOR FURNISHING WORK FOR HO ANNEXE AT SOUTH END, BENGALURU					
S.No	DESCRIPTION OF ITEM	QTY	UNIT	RATE in Rs	AMOUNT in Rs
	Providing and fixing Tables of following sizes with front, working top and side vertical support, intermediate vertical support . There shall be three draws of size 15" X 22" X 5" fixed in around boxing with top, side vertical, intermediate supports of the table as common side & top. The table & draws shall be made by all by using 19mm thick block board except for the draw bottom which shall be with 6mm MR grade commercial ply wood. The draw shall be fixed with telescopic channels for easy push and pull. The front elevation of the table shall be as per the design using 8mm thick MDF to provide recession and finished with beach beadings. The inner surfaces shall be provided with 0.6mm liner laminate. The exposed surfaces shall be provided with Surface finishes as per subhead V.				

Internal

Internal

SCHEDULE OF QUANTITIES

INTERIOR FURNISHING WORK FOR HO ANNEXE AT SOUTH END, BENGALURU

S.No	DESCRIPTION OF ITEM	QTY	UNIT	RATE in Rs	AMOUNT in Rs
	A foot rest of made of 19mm blockboard shall be provided. All the exposed edges shall be provided with beach wood beadings of size 19mm x 6 mm and finished with wood polish. The inner surface of drawers shall be finished with 0.8mm thick laminate of white colour. Each draw shall be provided with recess mounted handles with individual locks . Necessary openings for the access of the wires and plugs with wire manager to be provided with PVC caps for the counter top at appropriate location. Any variation in dimension shall be paid on volumetric proportion basis.				
a	3' 0" (W) x 7' 6" (L) x 2' 6" (H) for General Manager	1	No.		
2	RECEPTION TABLES				
	Same as Item 1 : 'GM Table' , but with Curvilinear/arc shaped profile designed with outer length of 7.5' and table top width of 2'. The customer top of width 9" shall be provided at a height of 3'6" using 19mm thick MR grade plywood. The front elevation of the table shall be as per the design using 8mm thick MDF to provide projections/recession. The inner surfaces shall be provided with 0.6mm liner laminate. The exposed surfaces shall be provided with Surface finishes as per subhead V. Internal	1	No.		
3	RUNNING STORAGE CUPBOARDS (SWING SHUTTERS)				
	Providing and supplying running storage cupboards of width 16" and height 30" or upto the specified height as per site conditions with top, sides, verticals at every 3ft C/C, horizontal shelves at 1.5 ft C/C or part thereof. The storage unit's verticals, horizontals & front swing shutters all shall be made by using 19mm block board and only rear side covered by 6 mm Mr grade commercial ply wood. The front shutters may be of size 18" to 21" width. There shall be skirting of height 2" to 3". The inner surfaces shall be provided with 0.6mm liner laminate. The exposed surfaces shall be provided with surface finishes as per Sub Head V All the exposed edges shall be provided with PVC edge banding of 2mm thickness. There shall be one number of multi-purpose lock for every two shutters. For shutter opening, tapered recess provided in the shutters . . Each shutter shall have a a magnetic catch, SS tower bolt 3" size as the case may be. The payment shall be based on the elevation area of storage units . Any variation in dimensions shall be paid on proportionate basis, considering volume as the parameter.	535	SFT		

Internal

SCHEDULE OF QUANTITIES					
INTERIOR FURNISHING WORK FOR HO ANNEXE AT SOUTH END, BENGALURU					
S.No	DESCRIPTION OF ITEM	QTY	UNIT	RATE in Rs	AMOUNT in Rs
	Location : Workspace & cabins				

Internal

Internal

SCHEDULE OF QUANTITIES

INTERIOR FURNISHING WORK FOR HO ANNEXE AT SOUTH END, BENGALURU

S.No	DESCRIPTION OF ITEM	QTY	UNIT	RATE in Rs	AMOUNT in Rs
4	METAL FRAMED TROPHY CABINET				
	<p>Metal Framed Open Shelf Upper : Providing and fixing Trophy Shelf as per design using framework using light guage GI tubular sections of size 25mmx25mm for outer framework. The frame work shall be welded as per design and joints shall be neatly grinded & buffed.</p> <p>The horizontal open shelves of depth 350mm shall be provided with 25mm thick HDF boards finished on all exposed faces with with 1mm satin finish lamination and 2mm PVC edge banding. The exposed edges shall be chamfered and the chamfered edges shall be provided with mathcing paint. All exposed metal surfaces shall be finished with primer, putty and PU paint in two or more coats.</p> <p>The payment shall be based on the elevation area of enitre unit.</p>	130	Sft		
III	FALSE CEILING				
1	GYPBOARD CEILING				
	<p>Providing and fixing suspended false ceiling, which includes providing and fixing GI perimeter channels of size 0.55mm thick having one flange of 20mm and another flange of 30mm and a web of 27mm along with perimeter of ceiling, screw fixed to brick wall/partition with the help of nylon sleeves and screws at 610mm centers. The suspending GI intermediate channel of size 45mm, 0.9mm thick with two flanges of 15mm each from the soffit at 1220mm centers with ceiling angle of width 25mmx 10mmx 0.55mm thick fixed to soffit with GI cleat and steel expansion fastene. Ceiling section of 0.55mm thickness having knurled web of 51.5mm and two flanges of 26mm each with lips of 10.5mm are then fixed to the intermediate channel with the help of connecting clips and in direction perpendicular to the intermediate channel at 457mm centers. 12.5mm tapered edge Gypboard (Conforming to IS- 2095-1982) is then screwed fixed to ceiling section with 25mm dry wall screw at 230mm centers. Screw fixing is done mechanically.</p>	6300	Sft		

Internal

SCHEDULE OF QUANTITIES

INTERIOR FURNISHING WORK FOR HO ANNEXE AT SOUTH END, BENGALURU

S.No	DESCRIPTION OF ITEM	QTY	UNIT	RATE in Rs	AMOUNT in Rs
	Finally the boards are to be jointed and finished so as to have a flush look which includes filling as finishing the tapered and square edge of the boards with joining compound, paper tape and two coats of primer suitable for Gypboard (as equivalent) extra frame work for electrical fittings, A/C diffusers, and/or any other cutout, trap doors, etc. complete including opening to be made for AC grills, light fittings, trap doors etc. The tiles shall be finished with 2 coats of satin finish acylic emulsion with sheen (The quoted rate shall be inclusive of suspenders at all heights)				

Internal

Internal

SCHEDULE OF QUANTITIES

INTERIOR FURNISHING WORK FOR HO ANNEXE AT SOUTH END, BENGALURU

S.No	DESCRIPTION OF ITEM	QTY	UNIT	RATE in Rs	AMOUNT in Rs
2	PERFORATED GYPSUM ACOUSTIC CEILING				
	Same as above item, using 12.5mm thick perforated Acoustic Ceiling Sheets (Knauff Danoloft ®) of size 600mmX1200mm sheets instead of gypsum board.	640	Sft		
3	MINERAL FIBRE BOARD GRID TYPE FALSE CEILING				
	Providing, fabricating, erecting lay-in type tegular/ drop type Mineral fibre board false Ceiling of 600mm x 600mm grid as per the following specifications. The approved brands are ARMSTRONG/ NITTOBO / SAINT GOBAIN. The following specifications are the minimum and tenderers may quote for the equivalent or better specification.	310	Sft		
	The grid system having 600mm x 600 mm or part thereof wherever necessary, shall be made using hot dipped galvanized steel section, exposed surface chemically cleaned capping prefinished in baked polyester paint, main Tee of size 14 x 38 x 0.33mm at every 1200mm c/c max and rotary stitched cross tee of size 14 x 38 x 0.33mm at every 600mm c/c and cross Tee of size 14x 38 x 0.33mm at every 1200 c/c max and 14 x 22 x 0.457mm wall angle around the wall to form grid size of 600 x 600mm. The suspension system shall have 4mm dia pre-straightened GI rods which are in-turn supported from real ceiling using 6mm size anchor bolts, connected with adjustable Hanger clips/ J bolts and other accessories as per the manufacturers specifications. The T Sections have a Galvanizing of 120 grams per M2 & passed through for 500 hrs of Salt test.				
	The tiles/ panels shall be of prima Microlook tegular of ARMSTRONG or Fine Fissured High NRC(Narrow reveal) edge Tiles of Saint Gobain Mineral Fibre Acoustic Ceiling Tiles of size 600 x 600 x 18 mm thick over the formed grid, in module size of 600mm x 600mm x 18mm Thick.				
	The item shall include the cost of additional Tee or L supports & other accessories near the ends/ odd size edges/corners, making necessary openings for electrical light fittings, fire alarm detectors and any other fixtures. No extra payment shall be made for making openings in the panels/ grid for the purpose of light fittings. Item rate shall include all the taxes, transportation, erection, loading & unloading and any other incidental expenditure that may be required to be spent in completing the work in totality as per above specifications. The tiles removed to place light fittings shall be handed over to bank's custody and there may not be any deduction for light fittings area.				

Internal

SCHEDULE OF QUANTITIES					
INTERIOR FURNISHING WORK FOR HO ANNEXE AT SOUTH END, BENGALURU					
S.No	DESCRIPTION OF ITEM	QTY	UNIT	RATE in Rs	AMOUNT in Rs

Internal

Internal

SCHEDULE OF QUANTITIES

INTERIOR FURNISHING WORK FOR HO ANNEXE AT SOUTH END, BENGALURU

S.No	DESCRIPTION OF ITEM	QTY	UNIT	RATE in Rs	AMOUNT in Rs
4	GI OPEN CELL CEILING				
	<p>Open Cell False Ceiling System Installed on grid system of 2' x 2' size in standard 9/16" T-Bar grid systems The grid shall be provided with pre-assembled 2' x 2' open cell ceiling panels of opening size 100mm x 100mm formed using GI powder coated U bend panels of 0.4mm thickness. Colour : As approved by Engineer in Charge</p> <p>Cell System main runners 48" x 2 inch x 3/8 inch, 0.020 inch roll-formed aluminum, with a 3/32 inch top return flange finished and fabricated to match cells. Cell System cross runners 24" x 2" x 3/8 inch, 0.020 inch roll-formed aluminum, with a 3/32 inch top return flange finished and fabricated to match cells.</p> <p>Sliding clips (four per panel) are installed in lower blade sections for securing cell panel to runners.</p> <p>Suspension System: Hanger Wire of Minimum 12 gage galvanized carbon steel hanger wire and attached to holes provided in main runners using manufacturers clips</p> <p>The axiom/mouldings/trims may be used as a perimeter for floating installation. In case of non-floating installation wall angle may be used. The color of the axiom/wall angle used should be of same color as that of cell ceiling.</p>	2750	Sft		
5	ALU EXPANDED MESH CEILING				
	<p>Installed on grid system of 4' x 2' size in standard 9/16" T-Bar grid systems The grid shall be provided with 4' x 2' Expanded Mesh Ceiling tiles made of 1.5mm thick Aluminium sheet to form a hex formation of 38mm/16mm diamond structure. Mesh and grid system shall be powder coated in RAL finish as approved by Enginner In Charge and to be placed inside 15mm T grid and is supported by GI wire of 3mm and butterfly clips at every 800mm. Mesh shall be embedded to form tegular aluminium frame.</p> <p>The axiom/mouldings/trims may be used as a perimeter for floating installation. In case of non-floating installation wall angle may be used. The color of the axiom/wall angle used should be of same color as that of cell ceiling.</p>	650	Sft		
6	ALU BAFFLE CEILING				

Internal

SCHEDULE OF QUANTITIES					
INTERIOR FURNISHING WORK FOR HO ANNEXE AT SOUTH END, BENGALURU					
S.No	DESCRIPTION OF ITEM	QTY	UNIT	RATE in Rs	AMOUNT in Rs
	<p>Providing and fixing box shaped 1.2mm thick extruded sections of size 50mmx100mm spaced at 100 to 125mm c/c. The box sections shall be of plain finish and powder coated to required RAL code.</p> <p>Frameworks : Using powder coated GI C channel 25x40 at adequate spacing, supported from the ceiling using M6 threaded rods. The channels shall be fixed to box sections using M5 bolts.</p>	320	Sft		

Internal

Internal

SCHEDULE OF QUANTITIES

INTERIOR FURNISHING WORK FOR HO ANNEXE AT SOUTH END, BENGALURU

S.No	DESCRIPTION OF ITEM	QTY	UNIT	RATE in Rs	AMOUNT in Rs
7	<p>ACOUSTIC SUPSPENDED CLOUDS</p> <p>Supply and installation of Acoustic cloud ceiling, of rectangle/any other shape. The suspended clouds shall be customized with 12mm thick Acoustic Panel for the bottom panel and 40mm depth side MDF boards of 11mm thickness for edges alround. Additional stiffners made of MDF boards 16mm thick shall be provided at every 900mm c/c bothways.</p> <p>The internal cavities of size 900mmX900mm or part thereof shall be infilled with acoustical absorbent resin bonded mineral wool of thickness 40mm, fixed to the MDF framework using 20 SWG GI wires. Extra stiffners if required shall be provided to avoid the saging of Panel ceiling. Panel ceilings are suspended from the true ceiling using necessary hardweres.</p> <p>The panels shall beThe panels shall be upholstered with good quality fabric of Basic Cost Rs. 600/metre.</p> <p>Each Cloud is provided with sets of accessories containing Corkscrew spring , levelling hook and hanger wires. Corkscrew spring to be rotated and anchored at back of each panel at four points to hold the panel stable. Supplied hanger wires to be first dropped from the beam/slab/truss to desired height with suitable anchor bolts and S hook.</p> <p>Clouds are then suspended using spring hooks and hanger wires and levelled into position with levelling clips. The Cost should includes necessary extra MS supports,anchors ,scaffolding to take the false ceiling from Roof slab/metal frame as per the Engineer In Charge's Instructions." Design/Shape/Finish shall be as per colour approved by the Engineer in Charge.</p>	1200	Sft		
8	<p>ACOUSTIC SUSPENDED OPEN CELL</p> <p>Supplying and Installation of Acoustic suspended open cell ceiling using 12mm thick acoustic PET panels with 0.7NRC. interlocked each other forming grid size of 600mm x 600mm as per design all around. Depth of the acoustic open cell panels shall be 220mm. Rate shall include the cost of suitable suspension system, connectors, end caps, hanging brackets, threaded rods etc. Supply & installation to be done as per manufacturers specification. Finish: of approved shade. Necessary supports to be given from true ceiling. Rate to be inclusive of all kinds of profiles and cut outs required for light fixtures, speakers, smoke detector in the ceiling. Curved designs shall be achieved by bending of the acoustic panels.</p>	400	Sft		

SCHEDULE OF QUANTITIES

INTERIOR FURNISHING WORK FOR HO ANNEXE AT SOUTH END, BENGALURU

S.No	DESCRIPTION OF ITEM	QTY	UNIT	RATE in Rs	AMOUNT in Rs
9	ACOUSTIC COFFERED CEILING				
	Providing and fixing of Acoustic Coffered Ceiling in modules of size 600x 600 as per approved design and reference image. Ceiling shall be formed with a base made of 12mm thk ply framework fixed to the false ceiling. Modules of size 600mm X 600mm shall be formed using 12mm thick PET panels with 0.7NRC for the base and verticals. Rate shall be inclusive of all hardware and accessories as required to complete installation.	400	Sft		
IV	PANELLING				
1	ALUMINIUM FRAMED WALL/COLUMN PANELLING				
	Providing & fixing wall panelling using 50mmx 25mm Aluminium sections of thickness 0.9 mm for the frame work spaced at 2 ft C/C and clad with 8mm thick MR grade commercial plywood. Surface finishes shall be as per subhead V.	7125	Sft		
2	ACOUSTIC PANELS				
	Providing & fixing Paneling on existing surfaces using PET (Polyethylene Terephthalate) panels of following thickness and pattern. The panels shall be cut to required sizes as per instruction of the Engineer in Charge and fixed to partitions/walls with headless nails/suitable adhesives. The exposed edges/corners shall be chamfered.				
a	9mm thick, with CNC cut grooved design	1450	Sft		
b	12mm thick, plain	300	Sft		
3	CLADDING ON EXISTING PARTITIONS/WALLS				
a	Cladding on top of existing partitions/walls by fixing with 6mm thick MR grade commercial plywood as per instructions of the Engineer In Charge. Surface finishes shall be as per subhead V.	600	Sft		
b	Cladding on top of existing partitions/walls by fixing with 4mm thick MDF cladding of width 60mm-75mm with 6mm thick grooves as per instructions of the Engineer In Charge. Groove shall be painted with matching colour. Surface finishes for non-grooved areas shall be as per subhead V.	815	Sft		

Internal

SCHEDULE OF QUANTITIES					
INTERIOR FURNISHING WORK FOR HO ANNEXE AT SOUTH END, BENGALURU					
S.No	DESCRIPTION OF ITEM	QTY	UNIT	RATE in Rs	AMOUNT in Rs
c	Cladding on top of existng partitions/walls by fixing with 12mm thick Gypsum Board with as per instructions of the Engineer In Charge. Surface finsihes shall be as per subhead V.	750	Sft		

Internal

Internal

SCHEDULE OF QUANTITIES

INTERIOR FURNISHING WORK FOR HO ANNEXE AT SOUTH END, BENGALURU

S.No	DESCRIPTION OF ITEM	QTY	UNIT	RATE in Rs	AMOUNT in Rs
V	SURFACE FINISHES				
1	SOLID SURFACE TOPS FOR TABLES				
	Providing & fixing 6mm thick solid surface of Dupont/Corian/LG/Samsung/Merino makes of gloss finish of approved shade/ combination of shades pasted to the surfaces of counter tops, customer tops and storage tops and exposed side surfaces of tables as specified by the engineer in charge using good quality adhesives and joints to be neatly grinded to give a seamless finish. Necessary bends/curves to be achieved as per design. The solid surface shall be fade and stain resistant and the contractor shall provide a warranty for a period of 5 years for the same. Measurement shall be carried out for the finished area. Wastages shall not be considered.	50	Sft		
	Location :GM Cabin				
2	LAMINATES				
	Providing and fixing 1.0mm thick texture finish lamination on already prepared surface using necessary adhesives. (Archidlam 11024 Frosty White (ASH)) or equivalent	6500	SFT		
	Providing and fixing 1.0mm thick satin finish lamination on already prepared surface using necessary adhesives.	7500	SFT		
	Providing and fixing 1.0mm thick Uni Core lamination on already prepared surface using necessary adhesives.	800	SFT		
	Providing and fixing 1.0mm thick Fluted lamination on already prepared surface using necessary adhesives.	68	SFT		
	Providing and fixing 1.0mm thick metallic lamination on already prepared surface using necessary adhesives.	66	SFT		
	4mm thick Veneer on top of existing surfaces and provided with PU polish. Basic Cost of Veneer ; Rs. 150/- per Sft	450	SFT		
3	STONE POLYMER COMPOSITE FLOORING TILES				
	Providing & fixing wood finish stone polymer composite tiles of size 48"x8"x4mm thick with click lock mechanism with wear layer thickness of 0.3mm on existing flooring including the cost of cushion backing, skirting, reductor etc of approved shade. Laying pattern : Herringbone. Make : Welspun or equivalent	170	Sft		
	Location :GM Cabin				

Internal

SCHEDULE OF QUANTITIES					
INTERIOR FURNISHING WORK FOR HO ANNEXE AT SOUTH END, BENGALURU					
S.No	DESCRIPTION OF ITEM	QTY	UNIT	RATE in Rs	AMOUNT in Rs

Internal

Internal

SCHEDULE OF QUANTITIES

INTERIOR FURNISHING WORK FOR HO ANNEXE AT SOUTH END, BENGALURU

S.No	DESCRIPTION OF ITEM	QTY	UNIT	RATE in Rs	AMOUNT in Rs
4	CARPET TILES				
	Providing & fixing carpet tiles of thickness 5-6mm on existing flooring including suitable adhesives as per shade and patterns approved by the Engineer In Charge. Make : Welspun or equivalent	650	Sft		
	Location :Conference Room				
5	PU PAINTING				
	Providing & applying water based two component interior grade PU painting of approved shade using machine sprayers in semi gloss/satin finish. Item includes preparation of surface, applying putty and interior grade sealer coat. Min 3 colour coats.	450	Sft		
6	LACQUERED GLASS PANELLING				
	Providing and fixing lacquered glass of following thickness of St. Gobain 'Plainique' make or equivalent with non staining adhesives. The edges shall be polished and necessary cutouts for fixing electrical points to be provided.				
	Internal				
	6mm thick	125	Sft		
7	MDF FLUTED PANELS				
	Supply and fixing unfinished MDF fluted panels on top of existing prepared surfaces using suitable clamps, adhesives.	250	Sft		
8	FLUTED GLASS				
	Providing and fixing fluted glass panels of thickness 8mm on existing framework as per design.	160	Sft		
9	TEXTURED GLASS				
	Providing and fixing textured glass panels of thickness 8mm on existing framework as per design.	160	Sft		
10	SS RIPPLE SHEET				
	Providing and fixing Stainless Steel Ripple Sheet of thickness 0.8mm of approved electroplating shade, polished finish on existing surfaces as per design.	96	Sft		
11	SS SHEET				
	Providing and fixing Stainless Steel Plain Sheet of thickness not less than 0.8mm of matt finish on existing surfaces as per design, using suitable adhesives, supports etc.	192	Sft		

SCHEDULE OF QUANTITIES

INTERIOR FURNISHING WORK FOR HO ANNEXE AT SOUTH END, BENGALURU

S.No	DESCRIPTION OF ITEM	QTY	UNIT	RATE in Rs	AMOUNT in Rs
12	CNC CUT HRHMR PANELS Providing & fixing 18mm thick HDHMR panels with 3D CNC cutting of approved pattern and fixing on existing prepared surfaces.	160	Sft		
13	INTERIOR EMULSION PAINTING (WALLS) Providing & applying to the interior wall surfaces with interior grade water based luxury emulsion of Asian Paints Royale Shyne Luxury Emulsion make with high sheen or equivalent using shades approved by the Bank with anti-fungal properties in TWO or more coats as per methodologies prescribed by the manufacturer. The item includes filling the cracks with approved crack fillers, providing 1mm thick of wall putty, rubbing, washing, thorough scraping of existing loose paint layers, dirt etc. The rate coated shall include cost of all leads and lift, cost and conveyance of all materials, labour, scaffolding and subsequent cleaning of floor etc after completion of works.	1500	SFT		
14	INTERIOR EMULSION PAINTING (CEILING) Providing & applying to the interior wall surfaces for basement level with interior grade water based emulsion of Asian Paints Tractor make or equivalent using shades approved by the Bank with anti-fungal properties in TWO or more coats as per methodologies prescribed by the manufacturer. The item includes filling the cracks with approved crack fillers, providing touchup wall putty, washing, thorough scraping of existing loose paint layers, dirt etc. The rate coated shall include cost of all leads and lift, cost and conveyance of all materials, labour, staging, scaffolding and subsequent cleaning of floor etc after completion of works. Shade : Black/Dark Grey	1000	SFT		
15	TEXTURE PAINTING - STUCCO Providing & applying Plaster of Paris punning/ putty in two layers , followed by wall primer, 2 coats of Luxury Emulsion and one coat of Special Effects Paint as Top Coat using roller/spray. Effect : Asian Paints Royale Play Stucco Mirror or equivalent	200	SFT		
VI	OTHER UTILITIES				
1	ROLLER BLINDS				

Internal

SCHEDULE OF QUANTITIES					
INTERIOR FURNISHING WORK FOR HO ANNEXE AT SOUTH END, BENGALURU					
S.No	DESCRIPTION OF ITEM	QTY	UNIT	RATE in Rs	AMOUNT in Rs
	Providing and fixing of roller blinds using premium quality blackout fabric of approved colour with thickness 0.45mm (+-) 5% , control unit and idler made of high strength reinforced plastic , bottom rail made of PVC extruded section of approved colour, operating chain made of plastic beads of thickness 4.5mm on polyester chords.	2000	sft		

Internal

Internal

Internal

SCHEDULE OF QUANTITIES

INTERIOR FURNISHING WORK FOR HO ANNEXE AT SOUTH END, BENGALURU

S.No	DESCRIPTION OF ITEM	QTY	UNIT	RATE in Rs	AMOUNT in Rs
2	PLANTER BOX				
	Providing and fixing Planter Box using 18mm BWR Grade Plywood (base + sides) and finishing with 0.7mm liner laminate for inner faces and 1mm thick satin finish lamination for exposed faces. Edges shall be finished with 2mm thick PVC edge bands. Depth : 9" ; Width 1'4". Payment shall be made for running length basis	65	Rft		
3	FLOOR PROTECTIONS SHEETS				
	Providing and fixing laminated foam floor protection sheet of thickness 2mm on top of existing tile flooring, including taping	16000	sft		
TOTAL AMOUNT OF WORK					
CGST					
SGST					
GRAND TOTAL					

Total in words :

Internal

Internal