

**SCHEDULE :**

NAME OF WORK : Electrical work at Bank Owned flats at "RAJESHDEP" (2 BHK - 4 NOS) at Kalyan

NAME OF CONTRACTOR : \_\_\_\_\_

ITEM NO.	PARTICULARS	QTY (per flat)	UNIT	RATE	AMOUNT
<b>A</b>	<b>PART -I WIRING AND DB</b>				
<b>1</b>	<b>CIRCUIT WIRING FROM METER ROOM TO MAIN DB</b>				
	Providing and laying 6 sq. mm x 2 core flexible wire, 2.5 sq. mm green earth wiring laying from meter cabin to flat Main incoming.	15	MTR		
<b>2</b>	<b>DP MCB FOR METER CABIN</b>				
	Providing and fixing 63 A DP MCB with box for Meter cabin	1	No		
<b>3</b>	<b>DB BOX</b>				
	Suply and installation of 8 way, Single phase DP MCB Distribution Board(double door) flush mounted on wall, sheet metal fabricated, powder coated, having dust-proof and vermin 'proof, gasketed and hinged door with all internals such as DIN rails, neutral.				
<b>a</b>	1 no., 63A, DP, MCB incomer				
<b>b</b>	20/10A, SP, MCB -6 Nos. outgoing	1	No		
<b>B</b>	<b>PART II – LIGHTING</b>				
	<b>SWITCH CONTROLLED</b>				
	Supply & installation of concealed point wiring using 600 V grade 1.5 sq mm copper conductor wire with PVC Conduit pipe (with proper RYB Colour code) laid concealed over false ceiling or in wall chases, including 1.5 sqmm green colour earth wire & provision of modular type grid plate type switches & sockets as per below configuration :				
	<b>Note:</b> Cost of Anchor Roma switches and box included along with the point rates, including 2.5 sq.mm circuit wiring lighting DB to switch board, including inverter wiring.				
	1 Lighting Primary points for lights and fans	59	Nos.		
	2 TWO way point wiring	4	Nos.		
	3 Bell point with Luminous indicator bell	1	Nos.		
	4 P & Fixing 5 Amp. Primary plug point	11	Nos.		
	5 P & Fixing 5 Amp. Secondary plug point	7	Nos.		
	6 P & Fixing 15 Amp. plug point	2	Nos.		
<b>C</b>	<b>PART-III POWER POINTS FOR HEATING APPLIANCES/AC</b>				
	P & Laying 4 Sq. mm x 3 core copper flexible with 2.5 sq. mm green earth wire with 1 no 20 amp MCB	4	Nos.		
<b>D</b>	<b>3 PART-IV LIGHTING FIXTURES</b>				
	Supply & Installation of lighting fixtures with lamps as per the details below including necessary hardware such as clamos,nuts, bolts, nails, screws and suspension rods as required for fixing the fixtures in position as directed by architect / consultant / client.				
	i S, I, T, C of Philips or equi. Green LED square light fitting of panel 15 watt	0	Nos		
	iii S & I of (1 X 24W) patti fittings 4'-0"	3	Nos		
	iv S & I of (1 X 18W) patti fittings 2'-0"	3	Nos		
	v LED BULBS 12 WATTS	4	Nos		
	<b>2 FANS</b>				
	i S & I of Wall mounted exhaust fan (9" dia.) of decorative plastic body and blade with louvers on the outside of approved make	3	Nos		
	ii 1200 mm Ceiling Fan ( Usha/Bajaj/ Crompton/standard) including Step electronic regulator	3	Nos		
<b>E</b>	<b>TEMPERARY WIRING</b>				
	Providing light point wiring and temperary lighting arrangement.	1	JOB		
	<b>GRANT TOTAL RS. (A TO E) - FOR 1 NO OF FLAT</b>			(A)	
	<b>GRANT TOTAL Rs. (FOR 4 NOS.) FLATS (4 x SL NO. F)</b>			(B) = (A) x 4	

NOTE : Kindly quote your Rates excluding of GST which will be payable extra as applicable.

ISSUED BY

SIGNATURE OF CONTRACTOR WITH SEAL