

SOQ FOR INTERIOR FURNISHING WORK OF CANARA BANK - VARNE BRANCH					
Sno	Description	Qty.	Unit	Rate	Amount
	GENERAL NOTES: -				
	WOOD WORK:				
	All internal woodwork / Plywood shall be treated with antitermite preservative. All internal framework shall be of Aluminium unless otherwise specified as Teakwood. All exposed edges of Plywood shall be fixed with C.P. Teak Lipping of size as directed by Architect. All Plywood shall be of MR GRADE IS 303 Commercial ply unless otherwise specified. The skinning shall be in 12 mm thk ply MR GRADE IS 303 unless otherwise specified. All exposed 1.0mm thk. laminate surfaces shall be finished. The thickness of the laminate shall be 1.00mm However no extra charges are payable for the additional thickness. The approved laminate shall be finished with bidding patti with polish finish where ever required.				
	Rate for high partition to include the cost of framework above false ceiling as required to fix the same to the ceiling slab. Measurement of Partition & Panelling shall be limited upto 6" above False ceiling & no separate payment shall be made for the work above 6". The item if executed for AC purpose shall be measured in the relevant item. The partition shall be measured including the door & the door frame & no separate payment for door shall be made. The rate shall be all inclusive of the necessary hardware, fittings, fixtures, floor spring, door closers, hinges, handles (1 pair of 300mm long S. S. (H Shape)), locks for the door (Godrej or approved equivalent) & including glass & finishing for the same. The rate shall be also inclusive of pattas & bands including the necessary framing/ openings for Electrical, Telephone & AC outlets.				
	PARTITIONS / PANELLING				
	General Specification for partition :-				
	Main frame -Aluminium sections of 16 Gauge mentioned are out of size 2"x2" Aluminium section verticals at minimum 2'-0" Centre-Centre spacing approx. and 2" X 1" size Aluminium sections horizontal at 2'-0" Centre-Centre spacing approx. Extra frame below slab soffit for conduit to run above. All verticals shall be secured to the ceiling.				
	SKIN: -12mm ply shall be screwed to frame work on both sides with joints as shown or directed.				
	SKIRTING : In the same alignment, 3" high in 12mm thk ply with a groove finished with laminate as the case maybe, or as directed by the Architect.				
	Finishing :- Approved laminate shall be of 1.0mm thk.				
	Laminate shall be fixed on plywood skins with glue having grooves as shown or directed. Internal surfaces at specified places shall be 1.0 mm thick as directed by Architect.				
1	PARTITIONS				
(i)	FULL HEIGHT PARTITIONS (SOLID) (with door and door frame)				
	Providing and fixing Full ht.Both side laminate Partitions as per specifications including skirting, complete as per the drawings and instructions complete in all respects.				

SOQ FOR INTERIOR FURNISHING WORK OF CANARA BANK - VARNE BRANCH					
Sno	Description	Qty.	Unit	Rate	Amount
	Main frame -2"x2" Aluminium section of 16 Gauge verticals at minimum 2'-0" Centre spacing approx and 2" X 1" size Aluminium sections horizontal at 2'-0" Centre spacing approx extra frame below slab soffit for conduit to run above. All verticals secured to ceiling.				
	Skin:- Both side with 12mm thk ply screwed to frame work on both sides or One side with 12 mm thk ply and other side with 12 mm calcium silicate board or Both sides with 12 mm thk calcium silicate board with joints as shown or directed.				
	SKIRTING : In the same alignment, 3" high in 12mm thk ply with a groove finished with laminate as the case maybe, or as directed by the Architect.				
a	Finishing : Both side finished in 1.0 mm thk Laminate as shown in drawing or as directed by Architect.	170.0	Sq.ft		0
c	Same as above but with ply on one side of the main frame to be finished with 1.0mm thk approved laminate finish and the other side of the main frame to be finished with calcium silicate board , 12mm thk to be finished with approved acrylic emulsion paint as shown or directed by Architect including necessary grooves, skirting etc complete. UPS	260.0	Sq.ft		0
2	FULL HEIGHT SEMI-GLAZED PARTITION (with door and door frame) for BM Cabin and Elsewhere	190.0	Sq.ft		0
	Providing & Fixing full height Semi-Glazed partition with following specifications				
	Main frame - 2"x2" Aluminium section of 16 Gauge verticals, not exceed 2'-0" centres and 2" X 1" size Aluminium sections horizontal at floor level / skirting ht, 3'-0" level and door height at 7'-0" level.				
	Skin:- Both sides of the main frame shall be finished with 12mm thk ply screwed to the frame with joints as directed upto 3'0" level and from 7'0" level to the top upto false ceiling level and 3'0" level and from 7'0" top upto false ceiling level, also from 7'0" prvindig top upto 6mm thk. clear glass Straight / segmented with bevelled edges including frosted film of approved make & design and drawing to be fixed with t.w moulding all around of approved size & design including grooves, mouldings etc complete as directed by Architect & as shown in the drawing.				
	SKIRTING : In the same alignment, 3" high in 12mm thk ply with a groove finished with laminate as the case maybe, or as directed by the Architect.				
	Finishing : both side finished in 1.0mm thk approved laminate finished with polish as shown or directed by Architect.				
3	LOW HEIGHT PARTITION	15.0	Sq.ft		0

SOQ FOR INTERIOR FURNISHING WORK OF CANARA BANK - VARNE BRANCH					
Sno	Description	Qty.	Unit	Rate	Amount
a	Providing & Fixing Low height Partition of about height 4'-0" height to be erected in 2" X 2" Aluminium section of 16 Gauge verticals, not exceeding 2' 0" centres and 2" X 1" size Aluminium sections horizontal at floor level / skirting ht, intermediate level & 3'-0" level with 12mm. thk ply skin on both sides of the frame to be screewed to the frame with joints as directed, including 12mm. toughened glass with chamfered edges of 1'0" to 1'6" height, including approved frosted film of approved make & design on the glass including soft board panel & White board with felt cloth on one side of the partition. The ply skin to be finished with 1.0mm thk. approved laminate with t.w. beading all throughout the exposed edges & periphery including fixing the glass, sealing all the joints, grooves in laminate, polish to the mouldings & t.w members, complete as per the directions of Architect Note:-actual mesurment as per site.				
4	FULL Ht. FULLY GLAZED PARTITION INCLUDING DOOR (Main branch entry+ATM Entry+ BH Front)	175.0	Sq.ft		0
	Providing and fixing partition framing consisting of Heavy duty Aluminium Box Sections 50mm x 50mm @ 600mm c/c Horizontally and Vertically . The vertical alternate frames to be fixed to the ceiling with necessary fixtures. The framing shall be finished with 12 mm thk. ply on both side and finished with 1.00 mm thk. Laminate finish and beading patti around glass finished with polish. The shade of laminate and polishing finish to be got approved from Bank / Architect. Approved make 12mm thick toughened glass to be fixed from skirting level to 2100mm level (in the top line of Door) The skirting should be as per approved laminate as per drawing and direction. Rate shall be inclusive of necessary hardware items, etc. Complete. The edge beadings with steam beach wood and finished with melamine.All damages to the floor work to be reinstated without any extra cost as per directions of Architect.(Toughened glass partition will be measured upto 7' height and rest will be solid). The rates are inclusive of entrance door as per the specifications provided.				
	ENTRANCE DOOR				
	Door- Providing and fixing 12mm thk toughened glass door with wooden frame all around fixed with necessary patch fittings (Dorma or equivalent make) including cutting, making holes, cutouts in the frame of required shape and size to accommodate fittings and fixing the fittings in floors, soffits, jambs including necessary fixtures, screws, sealant wherever required and SS cover over patch fittings. Rate shall include necessary etching film /, approved patch fitting locking systems, 1 pair of 600mm long S. S. (H Shape) Handles of approved make, floor springs, and any necessary hardware items.(DORMA MAKE Top Pivot - PT 24, Top Patch Fittings - PT 20, Bottom Patch fittings - PT 10, Floor Spring - BTS 75 V, Corner lock with strike plate and Euro Profile Cylinder - US 10, Handle - TG DIH600 - 600mm length) complete as per the directions of Architect Note:-actual mesurment as per site.				
6	PARTITION ABOVE FALSE CEILING				0

SOQ FOR INTERIOR FURNISHING WORK OF CANARA BANK - VARNE BRANCH					
Sno	Description	Qty.	Unit	Rate	Amount
	Providing and extending frame works of full height partitions wherever directed and finishing with 12 mm thkply on both sides and finishing the same with approved paint including insulating the same with approved insulating material upto soffit of beam or ceiling including properly anchoring the same making necessary cut-outs for AC ducts etc complete wherever directed.				
7	PANELLING :-				
a	Providing and fixing Wall & Column Panelling for the existing surfaces to be made out of 16 gauge Aluminium framework backing of size 2" X 1" at 1'6" to 2' c/c to be covered with 12mm thk ply and finished with approved 1.0mm thk laminate including skirting & band at top in the same alignment with a groove of approved size as shown in detailed drawing or as directed by Architect	450.0	Sq.ft		0
	ACP (3 mm thickness) and nd Aluminium section				
b	Providing and fixing Wall & Column Panelling for the existing surfaces to be made out of 16 gauge Aluminium framework backing of size 2" X 1" at 1'6" to 2' c/c to be covered with 12mm thk ply and finished with approved interior grade ACP including skirting & band at top in the same alignment with a groove and including teakwood moulding of approved size including the necessary ply backing to match the level of other finishes such as 1.0mm thk. laminate in required areas as shown in detailed drawing or as directed by Architect	300.0	Sq.ft		0
c	Providing & Fixing Soft Board panelling over framework of 25 mm x 18 mm T.W. Frame at 600 mm c/c with 6mm ply skinning on top & 12mm thk. soft board with fabric finishing over ply. Complete as per drawings & directions of the Competent Authority, 25 mm x 12 mm T. W.Moulding on edges.	45.0	Sq.ft		0
	FALSE CEILING WORK : ATM has gypsum false ceiling				
8	General :				
	The filler, paper tapes, finishes and primers suitable for Gypsum boards, shall be as per recommended practises of India Gypsum.				
	Framework grid and suspenders shall be fixed to avoid fouling with services such as ducting, sprinklers, electricals fixtures, etc				
	T.W. framing may be allowed in certain areas for the Gypsum Board ceiling with the approval of the Architect. The same should have three coats of fire resistant paint.				
	Note: All the hardware such as fastners, hangers, suspenders, etc. required for erection of the false ceiling shall be of INDIA GYPSUM make. And approved by the Architect.				
	Metal frame False Ceiling of 12 mm thk. Gypsum Board including vertical drop panels.	500.0	Sq.ft		0
i	Providing and Fixing 12 mm Thk. Gypsum board on metallic grid, conforming to IS: 2095: :1982. The metallic grid shall consists of the following :				
	GI Perimeter channels of size 27mm and 0.5mm thk. having one flange of 20mm and another flange of 30mm.				
	GI intermediate channel of size 45mm 0.5mm thk. With two flange of 15mm each at 4'-0" centre to centre.				
	GI Hanger of size 1"x1", 0.5mm thk. A 4'-0" centre to centre distance.				
	GI Cleat and Steel Expansion Fasteners.				

SOQ FOR INTERIOR FURNISHING WORK OF CANARA BANK - VARNE BRANCH					
Sno	Description	Qty.	Unit	Rate	Amount
	Ceiling section of 0.5mm thickness having curled wedge of 51.5 mm and two flanges of 26mm each with lips of 10.5mm at 450mm center to center. Connecting clips & 12.5 mm dry wall screws at 230 mm center to center.				
	The metallic grid shall be installed as follows :				
	The perimeter channel along the perimeter of the ceiling with screw fixed to brickwall / partition with the help of rawl plugs and screws.				
	The intermediate channels shall be suspended from the ceiling with steel GI hanger fixed to the slab soffit with GI cleat and steel expansion fasteners. The intermediate channels shall be at 4'-0" centre to centre distance.				
	The ceiling section placed in a direction perpendicular to the intermediate channel at 1'-6" C/C distance shall be fixed to the intermediate channel with the help of connecting clips and 12.5 mm dry wall screws at 230 mm centre to centre distance.				
	Finally, the 12mm thk. Gypsum boards shall be fixed to the metal frames and the tapered/square edges of the boards shall be finished to a flush joint with requisite filler, paper tapes, finisher and primer suitable for Gypsum plaster boards, (as per recommendations of manufacturers, Indian Gypsum or equivalent) including <u>3 coats of Acrylic Emulsion Paint of approved make and shade and colour.</u>				
	The rate shall include the cut-outs to be made for light fittings, grills, diffusers, speakers, smoke detectors, sprinklers etc. with provision of the frame along perimeter of the cut outs/ opening with channels/ ply to support the ceiling adequately as per the directions of Architect. The rate shall include necessary shapes, designs, patterns in curvature, sloping, dome, oval & elliptical shaped etc including the necessary provisions of coved lighting scheme etc including finished complete as per the designs, drawings and instructions of the Architect.				
	Armstrong Modular False Ceiling	360.0	Sq.ft		0
ii	Providing and constructing Modular False Ceiling of 24"X24". The tile shall be laid on Armstrong Silhouette profile grid system with 15mm white flanges incorporating a 6mm central reveal in black colour and with a web height of 38 mm and a load carrying capacity of minimum 11.25 Kgs/m ² & minimum pull out strength of 100 Kgs. Silhouette, Main Runners & Cross Tees to have mitred ends & "birdsmouth" notches to provide mitred cruciform junctions. The T Sections have a Galvanizing of 90 grams per m ² and need to be installed with Suspension system of Armstrong or equivalent make. including cutouts for recessed lamps fixtures, twin and single tubes , scaffolding etc complete.				
	TABLES				
9	Table for (B.M) (6'-0" x 3'0")	6.0	Rft		0
a	Providing and supplying table for the BM to be made out of 19mm MR GRADE IS 303 Commercial ply d finished with approved 1.0mm thk. laminate with polish for the top & 1.0 mm thk laminate for all other exposed areas. The top of the table to have t.w. moulding all around. The rate shall be inclusive of providing a keyboard tray on sliding telescopic channels & a pedestal drawer unit made out of 16mm thk ply on side with 2 nos of equal sized drawers on sliding channels & openable shutter below. The side credenza shall be on the other side & shall be paid for separately in the relevant item.				

SOQ FOR INTERIOR FURNISHING WORK OF CANARA BANK - VARNE BRANCH					
Sno	Description	Qty.	Unit	Rate	Amount
	All internal surfaces to be finished in approved 0.8mm thk laminate. All the external surfaces shall be finished with 1.0mm thk. laminate with polish including the drawer unit. The table shall have 6mm. thk clear glass on top with bevelled edges. The rate shall also include CPU trolley of reputed manufacturer, keyboard trays as per the approved makes which shall be heavy duty. The necessary hardware such as automatic locking, ball catches, wire managers etc. to be provided as per the instructions of the Architect. The rate shall also include providing stand-alone foot rest to the table of projection width as directed to be finished with approved laminate etc complete for the entire length of the table. The Elevation of the table shall be as directed by Architect on site.				
	Table for (Manager)				
b	WORK STATION SWO's & CASH (Nominal Size: 2'-6" Wide X2'-6" High) 27 Rft- 5 Workstations+ 1 Meeting table				
10	Providing and erecting in position linear work station as per the instructions and drawings to be made out of 19mm .(IS - 303) Plywood for work top and verticals finished with 1.0mm thk approved laminate externally for all the exposed surfaces & 0.8mm thk approved laminate internally. The top of the table to have t.w. moulding all around. The rate shall be inclusive of providing a keyboard tray on sliding channels & a drawer unit on side with 2 nos of equal sized drawers on channels with internal seperations in ply for keeping temporary cash & openable shutter below.	19.0	Rft		0
a i)	The side credenza however shall be paid for seperately in the relevant item. The rate shall be inclusive of CPU trolley of approved make, necessary fittings, fixtures, hardware such as channels, hinges, ball catches, automatic locking arrangement, wire managers etc including providing the necessary openings for electrical/computer wiring complete as per the instructions of Architect. Elevation of the table shall be as directed by Architect on site.				
a ii)	Cash counter and Single Window counter with additional working Top: Description similar to item no a i) with additional Customer top counter at 4'0" high and 9" wide made of 19 mm thick plywood finished with 1 mm thick laminate	5.5	Rft		0
a iii)	Counting Plank: Providing counting plank of 2 foot width and with drawers as per the specifications provided as per running counter.	3.0	Rft		0
a iv)	<u>PATTA & BANDS:</u>				
b	Providing and fixing 75mm wide Patta on the wall with 12mm Thk. (IS-303) ply including 12 mm t.w beading with polishing etc complete as per the instructions. Finished in 1.0mm thk approved laminate.polish	18.0	Rft		0
	Glass dividers fixed in wooden frame				
d	Providing & Erecting in position, bevelled Glass dividers out of 12mm thk glass between the two workstations admeasuring approx " to be placed in position with the D-brackets including edging of the glass, etching / frosted film etc complete	30.0	Sq.ft		0

SOQ FOR INTERIOR FURNISHING WORK OF CANARA BANK - VARNE BRANCH					
Sno	Description	Qty.	Unit	Rate	Amount
	12MM THK GLASS RAILING ABOVE CASH COUNTER				
11	Providing and fixing 12mm thick toughened glass with frosted film above counter fixed with D brackets to wall/partition.(slits and opening to be provided in the glass as per banks requirement)	20.0	Sq.ft		0
11 a	Front Glass above Working counter				
	Providing and fixing 12mm thick toughened glass with frosted film above counter fixed with D brackets to wall/partition.(slits and opening to be provided in the glass as per banks requirement)	40.00	Sqft		0
13	CENTER TABLE (2'-0" x3'-0")				
	Providing and supplying in position center table to be made out of 2" x 2" t.w. frame with 12mm thk. clear glass top with bevelled edges and etching with polish etc. complete as instructed by Architect.	1.0	Nos		0
14	WRITING DESK				
	Writing desk at entrance area in 19mm MR GRADE IS 303 Commercial ply and 1.00mm laminate finish surface 12 mm clear glass on top with shelves/partition (at 6 inches centre to center) in glass to keep slip books including acid etching / frosting of approved design and exposed edges in machine polished.and bank's printed brochures for public complete as per Architect's design and instructions. Size: 3'-0" x 1'-6" x 1 no.	1.0	nos		0
15	STORAGES				
	Providing and fixing Full height Storage of ht. 7'-0" and 1'-6"depth as specified in the drawings as per specification below.	110.0	Sq.ft		0
16	LOW HEIGHT STORAGE				
	Providing and fixing Low height Storage of ht. 4'-0" and depth as specified in the drawings as per specification below.	35.0	Sq.ft		0
	Skeleton - made out of 19mm MR GRADE IS 303 Commercial ply at end verticals, top and bottom and verticals 450mm to 600mm Centres as shown in drawing and 6 mm thk back MR GRADE IS 303 Commercial ply				
	SHELVES - 19mm Thk. Plywood top and edges finished in 0.8mm thk. Laminate to accommodate file height removable and supported on pins.				
	SHUTTERS-made out of 19mm MR GRADE IS 303 Commercial ply externally finished in 1.0mm thk. Laminate and Internally finished in 0.8 mm thk. Laminate as shown or directed.				
	HINGES - Each shutter shall have 100mm long oxidised brass butt hinges. Mimimum 4 nos. hinges for each of the shutter for Full height Storage and 3 Nos. hinges for each of the shutter for Low Height Storage to be provided.				
	BOLTS - Flush tower bolts from inside at top and bottom to the shutters and magnetic catch fixed top and bottom.				
	LOCKS - of approved make 4 -lever brass body dead lock with S.S. Key.				
	HANDLES - 100mm wide handles of c.p. brass as approved by the Architect.				
	SKIRTING -As instructed by Architect, 18 plywood finished in Laminate.				
	BACK - Back side of storage to have 6mm thk. MR GRADE IS 303 Commercial ply.				

SOQ FOR INTERIOR FURNISHING WORK OF CANARA BANK - VARNE BRANCH					
Sno	Description	Qty.	Unit	Rate	Amount
	Finishing :- All external surface finish with 1.0 mm thk Laminate. All the exposed woodsurfaces shall be finished in melamine polish. In side visible surface complete with 0.8mm thk Laminate. Top to have tw moulding as instructed.				
17	TABLE SIDE CREDENZA				
	Providing and erecting in position Credenza for the tables of 750mm height and 450mm deep or as instructed by the Architect to be made out of 19mm MR GRADE IS 303 Commercial ply & having t.w. moulding all round with 2 nos of drawers on top and openable or sliding shutters below. The openable shutters and shelves (to accommodate file height removable and supported on pins) to be made out of 19mm tk. MR GRADE IS 303 Commercial ply with all internal surfaces to be finished in 0.8 mm thk approved laminate and externally with 1.0mm thk laminate including brass hinges, ball catches, 100mm brass handles, brass locks etc. complete as per the instruction of the Architect. 3 Nos	20.0	Sq.ft		0
	Finished with approved laminate (1.0 mm externally & 0.8 mm internally)				
18	WICKET GATE				
	P & F wicket gate wherever required with required SS hinges, SS tower bolts, automatic surface mounted spring door closer, Godrej Night latch, etc. Rubber wood capping made out of sect. 65 x 15 mm fixed at edges incl. natural polish / painting etc. complete as directed	17.0	Sq.ft		0
19	ROLLER BLINDS				
	Providing and supplying of Roller blinds of VISTA Make as approved shade including tilt, cords, pulling strings, top track etc.complete (Regular make)	72.0	Sq.ft		0
20	NOTICE BOARD				
	Providing and fixing notice board 4'-0" X 2'-0" to be made out of 19mm thk. ply with 3" deep with front glass shutter, 10mm thk. ply back covered with soft board and felt cloth including polishing locks etc. finished as per instruction of the Architect.	20.0	Sq.ft		0
21	Providing and fixing White board with ceramic coating including soft board with fabric of approved shade and design complete as per the specifications and directions of the competent authority.size 3'.0"X 3'-0" 1 Nos.	20.0	Sq.ft		0
22	Box for Rolling shutter				
	Providing and erecting boxing to cover the rolling shutter to be for casing and openable shutters below for servicing to be finished with approved 3mm thk exterior grade ACP including hardware such as hinges, locks etc.complete as per instructions of Architect.	120.0	Sft		0
23	PAINTING :				
	Note : The Rates for the Painting works shall be inclusive of three coats.The paint should be free from lead and Arsenic.				
	Painting of wall with minimum of 3 coats of Flat Oil Paint of approved shade & make on the rolling shutter and grill/ collapsible gate surface to apply paint. As per the directions / to the satisfaction of the Architect.				

SOQ FOR INTERIOR FURNISHING WORK OF CANARA BANK - VARNE BRANCH					
Sno	Description	Qty.	Unit	Rate	Amount
a					
c	Providing and applying Acrylic Emulsion Paint in minimum of three coats of approved make and shade on Walls, Ceiling, plywood, gypsum board, surfaces etc including all the necessary surfaces preparation. The wall shall be cleaned, filled with putty & applied with one coat of primer so as to achieve a even surface to apply paint. As per the directions / to the satisfaction of the Architect.	2,000.0	Sq.ft		0
c					
24	CABINET FOR ELECTRIC PANEL:				
	Providing, making and placing in position cabinet with openable shutter around the electric panel. Cabinet and shutter made of 18mm thick exterior grade MR commercial plywood All visible surfaces shall be laminated with 1.00 mm thick laminate on external surfaces of approved shades painting the internal surfaces with two or more coats of synthetic enamel paint including providing teakwood lipping of size 20 x 6 mm on edges. Horizontal slots (approx. 10 mm wide) to be cut in the shutter at top & bottom for ventilation. Rate to include for necessary hardware fixture like providing with 3 nos. of 75mm long SS hinges for each shutter, two nos of 75 mm tower bolt (one top and bottom), SS handles to shutters, magnetic catchers for each shutter and multipurpose Godrej or Ebco lock. (Measurement area =	35.0	Sq.ft		0
26	CHEQUE DROP BOX:				
	Providing and fixing Cheque drop box of size 1' 6"x1' 6"x 6" with all sides and back with 18mm thick MR grade comm. Ply wood and lockable shutters in 18mm ply. Top of the box to be provide with slot of size 6" x 2" wide for dropping cheques/ suggestions. All exposed areas and inside to be finished with 1 mm thick laminate of approved shade. The edges of shutter and box to be lipped with steam beach beading polished with melamine. Rate shall be inclusive of all necessary approved fittings like hinges, godrej cabinet lock or approved e, etc. and any necessary hardware items.	1.0	Nos		0
27	SUGGESTION BOX:				
	Providing and fixing suggestion box of size 1' 6"x1' 6"x 6" with all sides and back with 18mm thick comm. Ply wood and lockable glass shutters in 18mm ply , with 5 mm glass. All exposed areas and inside to be finished with 1 mm thick laminate of approved shade. The edges of shutter and box to be lipped with steam beach beading polished with melamine. Rate shall be inclusive of all necessary approved fittings like hinges, Godrej cabinet lock or approved equivalent, etc. and any necessary hardware items.	1.0	Nos		0
28	GLASS SHELF	30.00	sft		0
	Providing and fixing 12 mm thick polished edge glass shelf on D-Brackets				
29	Push pull stickers	6.00	No.		0
	Proving and fixing push pull stickers on the doors				
30	Rearranging Items	1.00	job		0

SOQ FOR INTERIOR FURNISHING WORK OF CANARA BANK - VARNE BRANCH					
Sno	Description	Qty.	Unit	Rate	Amount
	Rearranging the existing counters in the branch premises till the new counters will be in the position. Rearranging the existing items like books,, racks, records etc. for making the partions, painting and iother activities required to finish the work. After work completion items must be kept to its original position.				
31	L G Rubber Mat- 16 mm thickness	20.00	Sq.Ft.		0
	Proving and fixing the Rubber mat approved make wherever required. 3X 3, 2 X2				
32	sparkler frosted Film with logo	160.00	Sq.Ft.		0
	Proving and fixing frosted film on the glass door for height of 3 foot				
33	Exhaust fan frame	3.00	Nos.		0
	Proving and fixing exhaust fan frame mad up of 19 mm plywood nad provision to be made for exhaust fan. The rates ar einclsuive of all .				
34	cover for Meter room box and Main switch	15.00	sft		0
	The meter room box and main switch to be covered with the plywood, ACP and a glass as slt to take the reading. The rate is inclsuive of all,.				
35	Mirror	20.00	Sq.Ft.		0
	Providing and fixing Mirror (Modiguard or Saint globain) 6mm thick of required size above wash basin. Mirror of approved make shall be fixed with 2" long S.S. Studs, 4 Nos. complete as directed.including frame work if necerrasy at any height with scaffolding etc complete.				
36	PVC Tactile	40.00	Sq.Ft.		0
	Providing and Fixing PVC Tactile Size of 300mmX600mm Installation With Adhesive backed etc complete as directed. Note Coloured, pattern etc will be approved by Architect Bank by considering basic rate for the tiles.				
37	PVC Flush Doors				
	Providing & fixing flsuh doors for toilets . The rate is inclusive of all fixtures, locks from both sides, provision for pad locks, Lock bolt (Lockable tadi Patti), hinges, handles, tower bolts, laminate, labour transporation etc. complete.	35.00	Sq.Ft.		0
GRAND TOTAL INTERIOR FURNISHING WORK					0
(GST will be payable Extra by the Bank)					