

BILL OF QUANTITY FOR CIVIL WORKS AT CANARA BANK VIVEK VIHAR, NEW DELHI

S.NO.	DESCRIPTION OF ITEM	UNIT	QTY	RATE (Rs.) (Excl. GST)	AMOUNT (Rs.) (Excl. GST)
1	UPVC WINDOW	Sq.Ft.	520.00		
	Providing and fixing new UPVC two track sliding window , minimum 2.5mm guage (Medium) (Fenestech/ Torfenster or approved make with 6mm glass with all fittings like rollers, locking arrangement, beading, handle etc. & required hardware of approved quality etc. The work shall include completion of work including civil works surface preparation, plaster, putty and painting of the window surface.				
	The rate shall include removal of the existing windows, holdfast in concrete, side plaster, cutting the existing shutters by welding, removal of glass and refixing the grill with concrete, plastering the sides and jambs in cement mortar 1:5. The existing grill to be altered to required size for refixing.				
2	Providing and fixing new UPVC fixed glass window , minimum 2.5mm guage (Medium) (Fenestech/ Torfenster or approved make with 6mm glass with all fittings like rollers, locking arrangement, beading, handle etc. & required hardware of approved quality etc. The work shall include completion of work including civil works surface preparation, plaster, putty and painting of the window surface.	Sq.Ft.	460.00		
	The rate shall include removal of the existing windows, holdfast in concrete, side plaster, cutting the existing shutters by welding, removal of glass and refixing the grill with concrete, plastering the sides and jambs in cement mortar 1:5. The existing grill to be altered to required size for refixing.				
3	TERRACE WATERPROOFING: Cleaning the full roof surface with tar brush, washing the roof surface with water pressure, preparing the surface smooth, then supply and laying one coat of Berger LATEX PLUS CHEMICAL mixing with grey cement and then providing and applying FIBER MESH on roof. Again, providing and applying two coats of BERGER LATEX PLUS CHEMICAL mixing with grey cement. The works to be carried out in accordance with the Bank's specification in strict supervision of Bank's Architect or Official. The tenderer can use the equivalent or superior material as approved by the Engineer in charge, but the treatment shall be guaranteed for at least 5 years period . The Methodology of application/ treatment should be as per manufacturer's specifications. Certificate in this regard shall be submitted with bills for payment.	Sq.Ft.	950.00		
4	Repairing existing Window M.S. grill with provision of fixing additional member to close opening develop for window Acs or due to rear tear of grill. The job shall include all the related works.	JOB	4.00		
5	P&F of Round stool of 18" dia & 18" high with Culting as per design as per instruction given by Architect. (Basic Cost Rs. 3500)	Nos	1.00		
6	P&F of 2'-6" high & 16" deep & 24" wide Ht. Console / Dressing Table for keeping valuable over the top as per instruction given by Architect. (Basic Cost Rs. 3200)	Nos	2.00		
7	P&F of Coffee Chair with upholsetry & culting as per instruction given by Architect. (Basic Cost Rs. 5000)	Nos	2.00		
8	P&F Centre Round Table as per instruction given by Architect. (Basic Cost Rs. 3000)	Nos	2.00		
9	P&F Framed Painting as per instruction given by Architect. (Basic Cost Rs. 2000)	Nos	4.00		
10	P&F Wall feature frame/ artistic wall artifact as per instruction given by Architect. (Basic Cost Rs. 3000)	Nos	2.00		
11	P&F Wooden ladder of 3 steps as per instruction given by Architect. (Basic Cost Rs. 2000)	Nos	2.00		
12	Providing and fixing of Wall Paper including labour, material, transportation etc. complete in all respects (Basic Cost Rs. 65/Sq.Ft.)	Sq.Ft.	300.00		

13	P&F Vinyl Flooring - Supplying & laying of approved brand of scratch proof, semi flexible P.V.C. blended homogeneous marble Vinyl flooring in tiles conforming to IS:3461, fixing with synthetic acrylic adhesive after preparing the floor, levelling & smothering when necessary with suitable putty, as per the design & instruction of the Engineer-incharge. 2 mm thick. Make Solar Bright, Solutia or equivalent.	Sq.Ft.	500.00		
14	Supplying Indoor Plants & FRP Planter 15"x15"x15" made of white or any shade required FRP (Fibre Reinforced Polymer) Planter	Nos.	5.00		
15	Dismantling and removing external window glazing wherever required in a manner which facilitates easy fixing of new doors and windows without undue expense. the rate shall include removal of debris from site.	Sq.Ft.	45.00		
16	Grinding & polishing of existing kota stone on staircase (from ground floor to terrace floor) including grout filling wherever cracked or required. The works shall be completed in all respects as per direction of the Bank/ Architect.	JOB	1.00		
17	Providing and fixing 4.5" wide seamless panel on the existing wooden surface i/c cutting the same and fixing with the help of suitable adhesive / nailing etc in approved design and pattern etc complete as reqd.	Sq.Ft.	200.00		
18	P&F Anti Grip 3M strip on staircase treads from ground floor to terrace floor wherever required. The works shall be completed in all respects as per direction of the Bank/ Architect.	JOB	1.00		
19	Providing & fixing of double layer Syntex tank of 10000 litre capacity at terrace of the floor, complete in all respects including all plumbing and related connections etc.	JOB	2.00		
20	Deep Cleaning of Second floor of the Branch including cleaning of floor, furnisture and fixtures, walls, windows fixtures, switch, sockets etc as per the requirement of the Bank	JOB	1.00		
A	TOTAL FOR WORKS (EXCLUDING GST)				
	Discount If any (Only on Excluding GST amount only)				
	Net Amount (After Discount if any - Excluding GST) (Discount if any shall be given on Amount in Sub part (A -Excluding GST) Not on sub part (C)).				
		GST as extra as applicable - By Bank			
PLACE:					
DATE:					
				SEAL AND SIGNATURE OF THE CONTRACTOR WITH ADDRESS	