

BOQ for Painting and Repair works of KARAD BRANCH Building of CANARA BANK					
SR. No	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
1	Excavation for foundation in soil soil/hard murum / mosaic flooring including removing the excavated material outside the barnch premises and in approved municipal dump yard as directed (Lift upto 1.50m) By Mechanical / manual Means.	Cu.ft	1000.00		0.00
2	Demolisjhing brick masonry, including one window M S window and disposal the debris way from the site in approved municipal dump yard	sft	70.00		0.00
3	Filling in plinth and floors with muroom brought from outside and approved by Engineer incharge in layers of 15 cm to 20 cm including watering and compaction etc. complete.	Cu.ft	750.00		0.00
4	Providing second class Burnt Brick masonry with conventional/ I.S. type bricks in cement mortar 1:6 in superstructure including striking joints, raking out joints, watering and scaffolding etc. Complete.	Cu.ft	100.00		0.00
5	Providing and laying Cast in situ/ Ready Mix cement concrete in M-15 of trap/ granite/ quartzite/ gneiss metal for foundation and bedding including bailing out water, formwork, laying/ pumping, compacting, roughening them if special finish is to be provided, finishing if required and curing complete, with manual / mixer/concrete Batch mix plant (Pan mixer) etc. complete. With fine aggregate (Natural sand/ Crushed sand V.S.I. Grade finely washed etc.)	Cu.ft	165.00		0.00
6	Providing and laying IPS flooring 50 mm thick with M15 cement concrete laid to proper level and slope in alternate bays including compaction, filling joints, marking lines, cutting the surface withmachnie upto 25 mm depth to give the appearance of tiles of 30 cm x 30 cm or other size laid diagonally /square etc finishing smooth (with extra cement) in any colour as directed and curing etc. complete.with Crushed sand VSI Grade	sft	500.00		0.00
7	Providing and fixing MS Grill with MS square bars 12mm thick at 4" c/c both ways welded to one aother at every joint with MS flat 1.25" x 5 mm thick welded to the grill, to be anchored into wall with anchor fasteners at 2' c/c. To be fixed at bottom of staircase cap roofing sheets bottom including all materials, labour, lead, lifts, scaffolding, painting the grill with anti corrosive primer and two coats of flat oil paint to satisfaction etc complete.	sft	140.00		0.00

BOQ for Painting and Repair works of KARAD BRANCH Building of CANARA BANK					
SR. No	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
8	Providing and fixing P.V.C. Rain water pipes of 110 mm outer diameter and having wall thickness of 2.2 to 2.7mm confirming to I.S.13592-1992 including proper rain water receiving recess with P.V.C. plug, bend, necessary fittings, such as, offsets, shoes, including fixing the pipe on wall using approved wooden cleats projecting 25mm to 40mm from face of wall a fixing with clips of approved quality and One Number, filing the joint using rubber gasket with solvent cement and properly resting the shoe of pipes on C.C. or masonry blocks, including necessary scaffolding and maintenance for 3 yrs for any leakages or dislocations of pipes. All the P.V.C. fittings and additional 2 piece socket clips shall be got approved from engineer etc. complete.	Rft	30.00		0.00
9	Providing & Fixing clamps of appropriate sizes to rain water pipes including labours, materials etc. complete.	No	30.00		0.00
10	Block board wooden door				
	Providing & fixing 30 mm thick external wooden door. The rate of the door includes all fixtures, locks from both sides, pad locks, hinges, handles, tower bolts, laminate, labour transportation etc. complete.	sqft	21.00		0.00
	Note: The painting is to be carried out upto the natural Level ground. Hence the materials stacked to the wall should be removed before painting including buses at the side of wall.				
11	Exterior weather coat- Apex Ultima with exterior putty				
	Providing and applying two coats of exterior weather shield paint of approved manufacture and of approved colour to the plastered surfaces including cleaning with watering, preparing the plaster surface, applying primer coat, scaffolding if necessary and watering the surface for two days etc complete. <u>Including filling up damaged parts of plaster with exterior putty</u> as and where required to satisfaction.	sqft	12000.00		0.00
12	Acrylic Emulsion paint				
	Providing and applying Acrylic Emulsion Paint in minimum of three coats of approved make and shade on Walls, Ceiling, plywood, gypsum board, surfaces etc including all the necessary surfaces preparation. The wall shall be cleaned, filled with putty & applied with one coat of primer so as to achieve an even surface to apply paint. As per the directions / to the satisfaction of the Architect.	sqft	6000.00		0.00
13	oil paint				

BOQ for Painting and Repair works of KARAD BRANCH Building of CANARA BANK					
SR. No	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
	Providing and applying oil-paint of approved colour and shade to old and new surfaces in two coats including scaffolding, preparing the surfaces.(excluding the primer coat.) etc. complete..	sqft	1200.00		0.00
14	Glasses of 5 mm Bajara type to be fixed with u clamps, Putty for all sides as per standard procedure. The rate is inclusive of removing old damaged glasses and disposal away from the site.	sqft	100.00		0.00
15	Removing of waste materials from the site including the bedris all around building cleaning the bushes all around the building etc. and dumping the materials in approved municipal dump yard.	LS	1.00		0.00
Electric work					
16	SITC of following concealed point wiring using 1100V grade 3C x 1.5 sq.mm. copper conductor PVC insulated FRLS wires (with proper R,Y,B colour code) pulled through 25mm / 20mm Size, MMS Grade PVC conduits. All wiring below false ceiling shall be concealed. The wires from ceiling junction to light points shall be drawn in flexible PVC conduit with adaptor & cover for junction box & crimp type lugs at both ends. Each circuit feeding not more than average 12 points (800 watts). The rate shall include circuit wiring (2C x 2.5 sq.mm. + 1C x 1.0 sq.mm.) from Lighting DB to switchboard and to the fixtures. (No seperate measurements for circuit wiring & PVC Conduits)The First Point will be considered as Primary Point and balance points as Secondary Points.				
17	Primary Light points, on LDB	No	10.00		-
	Rate in words : -				
	SITC 5A Primary light points including MS concealed box, grid plate, 6A switch & circuit wiring through LDB				
18	Secondary Light points	No	10.00		-
	Rate in words : -				
	SITC 5A Secondary light points looped from primary light point. All MCB controlled light points will be considered as secondary light points.				
19	Primary 5 A socket points	No	5.00		-
	Rate in words : -				
	SITC Primary 5 A Socket points using circuit wiring (with proper color code) pulled through medium gauge PVC conduits.				
	Each point consisting of 1 Nos of 5 A sockets controlled by 1 Nos of 6A switch , wired together forming a point with Green colour Earth wire.				

BOQ for Painting and Repair works of KARAD BRANCH Building of CANARA BANK					
SR. No	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
20	Secondary 5 A socket points (on Board plug points)	No	6.00		-
	Rate in words : -				
	SITC Secondary 5 A Socket points using circuit wiring (with proper color code) pulled through haevy gauge PVC conduits. These points are installed on the Lighting Switch Board.				
	Each point consisting of 1 Nos of 5 A sockets controlled by 1 Nos of 6A switch , wired together forming a point. Earth wire to be of Green colour only.				
21	Ceiling fan points	No	8.00		-
	Rate in words : -				
	SITC Ceiling Fan point operated on seperate switch shall be Controlled by 2 Module, Step type Fan regulator, Rate should be including the cost of Fan hook, Suspending suitable fan rod, Connecting cord and Step type Fan Regulator				
22	SITC of following concealed / surface mounted fixtures of makes as specified with all fixture accessories like suitable tubes/ bulbs/ ballast & internal wiring etc. The contractor has to assemble & install the said fixtures at position with necessary hardware required for installation like S-hook, chain link etc. as per requirement.				
	LED tube lights 4'	No	20.00		-
	Rate in words : -				
	SITC 1200 mm Long Surface/Wall Mounted extruded Aluminium channels, with 20 w LED Tube light fixtures complete. Rate should be including the cost of Fixture, Suspending suitable rods, other accessories & hardware etc.				
	Make : Philips, Model : BN021 LED25S 6500 PSU GR S1,				
	Make : Crompton Model : Linea LDLL20-CDL, LDLL20-WW				
	Make : Wipro, Model : Garnet D532065, D552065				
	Make : Havells Model : E-Lite LED Pride Pus LHEXBLP7PN1W020				
23	Ceiling Fans				
	Supplying & Installing following mentioned Aluminum, medium duty, powder coated with glossy color Ceiling Fans / Wall Fans / Exhaust Fans with necessary clamps hook, bracket, hardware etc				
	SITC 1200 mm sweep Ceiling fans Complete with Mounting rod, Clamps, Locking pin etc. (Color -White / Ivory / Brown)	No	8.00		-

	BOQ for Painting and Repair works of KARAD BRANCH Building of CANARA BANK				
SR. No	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
	Grand Total (Excluding GST)				0.00
	(Applicable GST will be paid Extra by the Bank)				