

SOQ FOR ELECTRICAL WORKS IN KUDAL BRANCH					
<b>The stickers to be pased for all raw power points and UPS power points</b>					
<b>The stickers to be pasted for all DBS</b>					
<b>ALL FRLS wires to be used</b>					
<b>ALL Cables to be used in 'Item B'</b>					
<b>Seperate meters are available for ATM &amp; Branch</b>					
Type of wiring	Concealed				
Casing capping (as per approval)	Modi make/ Precision (ISI grade)				
PVC pipe and accessories	Precision / Polycab / Swastik (ISI make)				
Wires	Polycab / Finolex / R R kabel make FRLS				
	grade insulation, flexible copper conductor,				
Computer DataCable	D-Link / Molex / Awaya make				
Power cable	Polycab / Finolex / R R kabel make (ISI grad				
MCB / MCB DB	L & T, Legrand / Siemens (ISI)				
ELMCB	L & T, Legrand / Siemens (ISI)				
Ft. tubes & fixtures	Philips / Wipro / Crompton / Havells / Bajaj				
Ceiling fans / Wall fans / Exhaust Fans	Crompton Greaves / Havells / Usha / Bajaj				
screws	Nettlefold				
Earthing material	Strictly Bare Copper and with charcoal				
Switch fuse unit	L & T make (ISI)				
Switches/sockets & accessories	Legrand / Anchor Roma Modular type				
switchboards	Concealed modular type				
Copper strip type busbar	Havells / Standard make				
ONLINE UPS	Fuji / Vertiv				
SMF Batteries	Exide / Amaron				
Offline UPS / Inverter	Microtek / Havells				
Tubular Batteries	Exide / Amaron				
<b>SR</b>	<b>SUMMARY</b>				<b>AMOUNT</b>
<b>A</b>	<b>TOTAL OF MAIN PANEL / DB's / MCCBs :-</b>				<b>-</b>
<b>B</b>	<b>TOTAL OF CABLES &amp; TERMINATIONS</b>				<b>-</b>
<b>C</b>	<b>TOTAL OF POINT WIRING</b>				<b>-</b>
<b>D</b>	<b>TOTAL OF FIXTURES</b>				<b>-</b>
<b>E</b>	<b>TOTAL OF EARTHING SYSTEM</b>				<b>-</b>
<b>F</b>	<b>TOTAL OF TELEPHONE SYSTEM</b>				<b>-</b>
<b>G</b>	<b>TOTAL OF DATA CABLING SYSTEM</b>				<b>-</b>
<b>H</b>	<b>TOTAL FOR MISCELLANEOUS WORKS</b>				<b>-</b>
	<b>TOTAL FOR ELECTRICAL WORKS</b>				<b>-</b>
<b>J</b>	<b>LESS DISPOSAL &amp; BUYBACK VALUE</b>				<b>-</b>
	<b>TOTAL FOR ELECTRICAL WORKS</b>				<b>-</b>
	<b>DISCOUNT OFFERED -</b>				<b>%</b>
	<b>GRAND TOTAL FOR ELECTRICAL WORK</b>				<b>-</b>
					<b>GST extra</b>
<b>SOQ FOR ELECTRICAL WORKS IN KUDAL BRANCH</b>					
<b>SR. NO.</b>	<b>ITEM</b>	<b>UNIT</b>	<b>QTY</b>	<b>RATE</b>	<b>AMOUNT</b>

SOQ FOR ELECTRICAL WORKS IN KUDAL BRANCH					
SR. NO.	ITEM	UNIT	QTY	RATE	AMOUNT
<b>A</b>	<b>MAIN PANEL / DISTRIBUTION BOARDS / MCCBs :-</b>				
<b>1</b>	<b>Meter room Mains MCCB's</b>				
	<b>Supplying &amp; Installing 63A/ 80A / 100A, FP MCCB in Sheet Steel Enclosure, complete with Gland Box etc</b>				
	a. 63 A FP MCCB 16kA	Nos.	2.00		-
	Rate in words :-				
	<b>Make</b> : Legrand, <b>Type</b> : DPX3 160 with Thermal & Magnetic protection Unit				
	b. Sheet steel Enclosure Box for FP MCCB	Nos.	2.00		-
	Rate in words :-				
<b>2</b>	<b>MCB DISTRIBUTION BOARDS</b>				
	SITC sheet metal fabricated & powder coated Double Door Type MCB Distribution Boards (surface/flush mounted). DB's shall have MCB/MCCB as incomer, RCCB as sub-incomer & SP/DP/TP MCB as outgoing, complete with Per Phase Isolation. All MCBs of C characteristics and 10 KA breaking capacity & ELCB's, RCCB's, RCBO's should be of 100mA sensitivity. The DB shall have appropriate no. of top & bottom knock outs for outgoing circuits & shall be complete with necessary bus bars, interconnecting terminals & earth studs. All terminations in DB shall be complete with feruling, dressing with lugs & all circuits shall be properly labeled with PVC strip (sticker type) having identification as per the final approval of the Consultant. <u>The rate is inclusive of blanking plates whenever required.</u>				
<b>2.1</b>	<b>SITC Mains DB, for BRANCH</b>				
	i) <b>4 way VTPN - MCCB DB,</b>	Nos.	1.00		-
	Rate in words :-				
	ii) <b>63 A - TP MCCB, 16kA</b>	Nos.	1.00		-
	Rate in words :-				
	iii) <b>40 A - TP MCB, outgoing to AC DB &amp; spare</b>	Nos.	2.00		-
	Rate in words :-				
	iv) <b>25/32 A - SP MCB, outgoing to UPS Input, Inverter Input, Signage, ATM DB &amp; Spare</b>	Nos.	6.00		-
	Rate in words :-				
<b>2.2</b>	<b>SITC Mains DB, for ATM</b>				
	i) <b>4 way VTPN - MCCB DB,</b>	Nos.	1.00		-
	Rate in words :-				
	ii) <b>63 A - TP MCCB, 16kA</b>	Nos.	1.00		-
	Rate in words :-				
	iii) <b>25 A - TP MCB, outgoing to LDB for branch</b>	Nos.	1.00		-
	Rate in words :-				

SOQ FOR ELECTRICAL WORKS IN KUDAL BRANCH					
SR. NO.	ITEM	UNIT	QTY	RATE	AMOUNT
iv)	<b>32 A - TP MCB, outgoing to AC DB &amp; spare</b>	Nos.	1.00		-
	Rate in words :-				
v)	<b>25/32 A - SP MCB, outgoing to UPS Input of ATM, Lighting of ATM, ATM DB &amp; Spare</b>	Nos.	6.00		-
	Rate in words :-				
<b>2.2</b>	<b>SITC LIGHTING DB for Branch through ATM meter</b>				
i)	<b>6 way SPN - MCB DB,</b>	Nos.	1.00		-
	Rate in words :-				
ii)	<b>32 A - DP MCB, as incomer</b>	Nos.	1.00		-
	Rate in words :-				
iii)	<b>25 A - DP 30mA RCCB / ELCB, as sub-incomer</b>	Nos.	3.00		-
	Rate in words :-				
iv)	<b>16 A - SP MCB outgoing BRANCH LIGHT</b>	Nos.	12.00		-
	Rate in words :-				
<b>2.3</b>	<b>SITC RAW POWER &amp; AC DB for Branch through Branch meter</b>				
i)	<b>6 way TPN - MCB DB,</b>	Nos.	1.00		-
	Rate in words :-				
ii)	<b>40 A - TPN MCB</b>	Nos.	1.00		-
	Rate in words :-				
iii)	<b>40 A - DP 100mA RCCB / ELCB, as sub-incomer</b>	Nos.	3.00		-
	Rate in words :-				
iii)	<b>16/20/25/32 A - SP MCB outgoing</b>	Nos.	8.00		-
	Rate in words :-				
<b>2.4</b>	<b>SITC UPS Output DB for Branch through Branch meter</b>				
i)	<b>6 way SPN - MCB DB,</b>	Nos.	1.00		-
	Rate in words :-				
ii)	<b>32 A - DP MCB as incomer</b>	Nos.	1.00		-
	Rate in words :-				
iii)	<b>32A - SP MCB outgoing, .... for Branch UPS DB</b>	Nos.	1.00		-
	Rate in words :-				
iv)	<b>16A - SP MCB outgoing, .... for CCTV, Network rack, Security Alarm system, Fire Alarm System etc Emmergency socket points.</b>	Nos.	3.00		-
	Rate in words :-				
<b>2.5</b>	<b>SITC BRANCH UPS DB for Computers</b>				
i)	<b>6 way SPN - MCB DB,</b>	Nos.	1.00		-
	Rate in words :-				
ii)	<b>32 A - DP MCB as incomer</b>	Nos.	1.00		-
	Rate in words :-				
iii)	<b>16/20A - SP MCB outgoing</b>	Nos.	4.00		-

SOQ FOR ELECTRICAL WORKS IN KUDAL BRANCH					
SR. NO.	ITEM	UNIT	QTY	RATE	AMOUNT
	Rate in words :-				
<b>2.6</b>	<b>SITC INVERTER Lighting DB through Branch meter</b>				
i)	<b>6 way SPN - MCB DB,</b>	Nos.	1.00		-
	Rate in words :-				
ii)	<b>25 A - DP MCB as incomer</b>	Nos.	1.00		-
	Rate in words :-				
iii)	<b>6/10A - SP MCB outgoing</b>	Nos.	4.00		-
	Rate in words :-				
<b>2.7</b>	<b>SITC ATM LDB / AC DB through ATM Meter</b>				
i)	<b>6 way SPN - MCB DB,</b>	Nos.	1.00		-
	Rate in words :-				
ii)	<b>32 A - DP MCB as incomer</b>	Nos.	1.00		-
	Rate in words :-				
iii)	<b>10A - SP MCB outgoing, .... for Lighting &amp; Socket points.</b>	Nos.	2.00		-
	Rate in words :-				
iv)	<b>16/20A - SP MCB outgoing, .... for ATM AC and Power socket points.</b>	Nos.	2.00		-
	Rate in words :-				
<b>2.8</b>	<b>SITC ATM UPS Output DB through ATM Meter</b>				
i)	<b>6 way SPN - MCB DB,</b>	Nos.	1.00		-
	Rate in words :-				
ii)	<b>16/20 A - DP MCB as incomer</b>	Nos.	1.00		-
	Rate in words :-				
iii)	<b>10/16A - SP MCB outgoing</b>	Nos.	4.00		-
	Rate in words :-				
<b>2.9</b>	<b>MCB BOX</b>				
a.	<b>SITC 4 way - MCB with Box, for switching off the lighting DB near Main Entrance Door to switch OFF all the light points after office hours</b>				
i)	<b>Sheet steel Enclosure Box for FP MCB</b>	Nos.	1.00		-
	Rate in words :-				
ii)	<b>20/25 A - FP MCB</b>	Nos.	1.00		-
	Rate in words :-				
b.	<b>SITC 4 way - MCB with Box, for switching off the AC DB near Main Entrance Door to switch OFF all the AC's after office hours</b>				
i)	<b>Sheet steel Enclosure Box for FP MCB</b>	Nos.	1.00		-
	Rate in words :-				
ii)	<b>40/63 A - TPN MCB</b>	Nos.	1.00		-
	Rate in words :-				

SOQ FOR ELECTRICAL WORKS IN KUDAL BRANCH					
SR. NO.	ITEM	UNIT	QTY	RATE	AMOUNT
d.	<b>SITC 2 way - MCB with Box, for UPS Input / Output and for switching OFF the UPS outputs to the branch after office hours</b>				
i)	<b>Sheet steel Enclosure Box for DP MCB</b>	Nos.	2.00		-
	Rate in words : -				
ii)	<b>32/25 A - DP MCB</b>	Nos.	2.00		-
	Rate in words : -				
e.	<b>SITC 2 way - MCB with Box, for Signage and for switching OFF the Inverter outputs to the branch after office hours</b>				
i)	<b>Sheet steel Enclosure Box for DP MCB</b>	Nos.	2.00		-
	Rate in words : -				
ii)	<b>20 A - DP MCB</b>	Nos.	2.00		-
	Rate in words : -				
<b>3</b>	<b>Signage Timer</b>				
	Supplying and Installing programmable <b>Digital Timer</b> microcontroller based with real time clock to operate on derived switching "ON" and switching "OFF" glow sign board light as per daily sunset and sunrise respectively automatically having 4 digit LED continuous time display erected in M.S. box.	No.	1.00		-
	Rate in words : -				
<b>4.0</b>					
a)	<b>Supplying &amp; Installing 10/20 A Modular Power Socket points complete MS concealed box, Modular Switch plate, 20A Modular Socket, controlled by a Modular 20 / 25A SP MCB with necessary screws, nylon plug, Saddles, hardware etc. including cost of 3 x 4.0 sqmm PVC insulated FRLS copper Wires and 25mm/20 mm PVC conduit, For ATM UPS &amp; Inverter Input &amp; Output connections and ACs conncted through the stabilizers</b>	Nos.	7.00		-
	Rate in words : -				
b)	<b>Supplying &amp; Installing 20 A Power Socket points complete MS concealed box, Modular Switch plate, 20A Modular Socket, controlled by a Modular 20 / 25A SP MCB with necessary screws, nylon plug, Saddles, hardware etc. including cost of 2x4.0 sqmm + 1x2.5 sqmm PVC insulated FRLS copper Wires and 25mm/20 mm PVC conduit, For High Wall Split AC Units. The rate should include pin top for all the plit ACs.</b>	Nos.	7.00		-
	Rate in words : -				
	<b>For Strong Room Entrance control from outside</b>				

SOQ FOR ELECTRICAL WORKS IN KUDAL BRANCH					
SR. NO.	ITEM	UNIT	QTY	RATE	AMOUNT
e	Supplying & Installing 20 A Power Socket points complete MS concealed box, Modular Switch plate, 20A Modular Socket, controlled by a Modular 20A SP MCB with necessary screws, nylon plug, Saddles, hardware etc. including cost of 2x2.5.0 sqmm + 1x1.5 sqmm PVC insulated FRLS copper Wires and 25mm/20 mm PVC conduit, For Strong Room / Cash room Entrance as It's Lighting circuit control from outside. Lighting switch board inside the Strong room / Cash room to be connected using, 2 mets of 3 core 1.5 sq mm flexible copper cable with 15 A plug top from this power socket installed outside the room ( rate should be given inclusive of flexible cable, plug top and circuit )	Nos.	1.00		-
	Rate in words :-				
	<b>A. TOTAL OF MAIN PANEL / DB's / MCCBs :-</b>				<b>0.00</b>
<b>B</b>	<b>CABLES &amp; TERMINATIONS</b>				
	Supply and Laying of following LT cables confirming to IS 1554 (part 1) with necessary M.S. clamps. All such cables shall be provided with temporary labeling at every 20 mtr. & then finally with metal identification tags showing the size & the location from/to the specific panel/DB; at both the ends. <b>The rate is inclusive of termination charges</b>				
<b>1</b>	<b>Aluminium Armoured Cables</b>				
a.	4 C x 25 Sq.mm Aluminium AYFY Armoured Cables, <b>from MSEB Meter to Main Power DB. Separate cables for ATM DB and Branch DB. Separate meters available.</b>	Rmt	90.00		-
	Rate in words :-				
<b>2</b>	<b>Copper Flexible Cables</b>				
a.	3 C x 4 Sq.mm Copper Flexible Cables, <b>from UPS Output to UPS o/p DB to Main MCB near Entrance to Branch UPS DB &amp; for Inverter. Also for the stabiliiers.</b>	Rmt	110.00		-
	Rate in words :-				
b.	3 C x 6 Sq.mm Copper Flexible Cables, <b>for UPS Input from Main Power DB</b>	Rmt	25.00		-
	Rate in words :-				
c.	3C x 6 Sq.mm Copper Flexible Cables, <b>for ATM DB from Main Power DB &amp; from MSEB Meter to Main Power DB (ATM)</b>	Rmt	25.00		-
	Rate in words :-				

SOQ FOR ELECTRICAL WORKS IN KUDAL BRANCH					
SR. NO.	ITEM	UNIT	QTY	RATE	AMOUNT
d.	4C x 4 Sq.mm Copper Flexible Cables, <b>from Main DB to Main MCB near Entrance to Lighting DB</b>	Rmt	25.00		-
	Rate in words :-				
e.	4C x 6 Sq.mm Copper Flexible Cables, <b>from Mains DB to AC Main MCB near Entrance to AC Power DB .</b>	Rmt	25.00		-
	Rate in words :-				
f.	3 C x 2.5 sq.mm. Cu flexible cables, <b>for Signage</b>	Rmt	25.00		-
	Rate in words :-				
<b>B. TOTAL OF CABLES &amp; TERMINATIONS</b>					<b>-</b>
<b>C</b>	<b>POINT WIRING</b>				
<b>1</b>	<b>POWER POINTS</b>				
	SITC of following concealed Power Point Wiring using 1100V grade 3C x 2.5 sq.mm. PVC insulated, PVC Sheathed White Colored flexible copper FRLS cable, laid through 20mm / 25mm size MMS Grade, PVC conduits. All cabling / conduiting below false ceiling shall be concealed. Each circuit feeding not more than 3 Tables / Work Stations). The rate shall include cabling including conduit cost from DB to mentioned Power Points. <b>(No seperate measurements for circuit wiring &amp; PVC Conduits)</b>				
a.	<b>Primary UPS points</b>	No	8.00		-
	Rate in words :-				
	Supplying & Installing <b>Primary UPS or Stabilized Power points</b> on workstations / tables for computers using <b>3C x 2.5 Sq.mm PVC sheathed white color flexible copper FRLS cable pulled through 25mm size MMS Grade PVC conduites</b> , laid on surface above false ceiling and taken upto table top using 25/20 mm size MMS Grade PVC rigid or flexible conduits run within wooden or metal partitions.				
	Each point consisting of <b>2 Nos of 6A, 5 Pin Modular sockets and 1 No. of 6/16A, 6 pin socket controlled by 1 No 20A Modular switch</b> , wired together forming one point. Earth wire to be of Green colour only. <b>Switch should be above table top &amp; sockets should be below table top</b>				

SOQ FOR ELECTRICAL WORKS IN KUDAL BRANCH					
SR. NO.	ITEM	UNIT	QTY	RATE	AMOUNT
	<b>Only 3 tables served by one circuit from UPS DB.</b> The Rate should be including the cost of Conduits, Cables, Switch boards, internal looping wires, necessary Gang Box, PVC box, Modular Plates of other color, Modular Switches, Sockets, Compete Job with necessary screws, nylon plug, Saddles, hardware. Etc. All Switch Boards should be Properly numbered for identifications.				
	<b>b. Secondary UPS points</b>	No	6.00		-
	Rate in words :-				
	Supplying & Installing <b>Secondary UPS or Stabilized Power points</b> on workstations / table for computers using 3C x 2.5 Sq.mm PVC sheathed white color flexible FRLS copper cable pulled through 25mm size MMS Grade PVC conduites, laid on surface above false ceiling and taken upto table top using 25/20 mm size MMS Grade PVC rigid or flexible conduits run within wooden or metal partitions.				
	Each point consisting of <b>2 Nos of 10A, 5 Pin Modular sockets and 1 No. of 6/16A, 6 pin socket controlled by 1 No 20A Modular switch</b> , wired together forming one point. Earth wire to be of Green colour only. <b>Switch should be above table top &amp; sockets should be below table top</b>				
	<b>for 2 table served by the same circuit from adjacent Primary point.</b> The Rate should be including cost of Cable, Switch board internal looping wires, necessary Gang Box, PVC box, Modular Plate of other color , Modular Switches, Sockets, Compete Job with necessary screws, nylon plug, Saddles, hardware. Etc. All Switch Boards should be Properly numbered for identifications.				
	<b>c. Primary 10/20 A power points, for Printers, Cash counting machine and Water cooler and for strong room inverter supply etc</b>	No	2.00		-
	Rate in words :-				
	Supplying & Installing Primary 10/20 A Power Socket points using 2 X 4.0 Sq.mm. + 1 X 2.5 Sq.mm. PVC insulated multistanded FRLS Grade flexible copper wires				
	(with proper color code) pulled through haevy gauge PVC conduits.				
	Each point consisting of <b>1 Nos of 10/20 A Modular sockets controlled by 1 Nos of 20A Modular switch</b> , wired together forming a point. Earth wire to be of Green colour only.				

SOQ FOR ELECTRICAL WORKS IN KUDAL BRANCH					
SR. NO.	ITEM	UNIT	QTY	RATE	AMOUNT
	Only 2 Sockets served by one circuit taken from Raw Power & AC DB				
	<b>d. Secondary 10/20 A power points, for Printers &amp; Aqua guard etc</b>	No	1.00		-
	Rate in words :-				
	Supplying & Installing Secondary 10/20 A Power Socket points using 2 X 2.5 Sq.mm. + 1 X 1.5 Sq.mm. PVC insulated multistanded FRLS Grade flexible copper wires				
	(with proper color code) pulled through haevy gauge PVC conduits.				
	Each point consisting of <b>1 Nos of 10/20 A Modular sockets controlled by 1 Nos of 20A Modular switch</b> , wired together forming a point. Earth wire to be of Green colour only.				
	Only 2 Sockets served by one circuit taken from Raw Power & AC DB				
<b>2</b>	<b>LIGHT POINT WIRING</b>				
	SITC of following concealed point wiring using 1100v grade 3C x 1.5 sq.mm. copper conductor PVC insulated <b>FRLS wires</b> (with proper R,Y,B colour code) pulled through 25mm / 20mm Size, MMS Grade PVC conduits. All wiring below false ceiling shall be concealed. The wires from ceiling junction to light points shall be drawn in flexible PVC conduit with adaptor & cover for junction box & crimp type lugs at both ends. Each circuit feeding not more than average 12 points (800 watts). The rate shall include circuit wiring (2C x 2.5 sq.mm. + 1C x 1.5 sq.mm.) from Lighting DB to switchboard and to the fixtures. <b>(No seperate measurements for circuit wiring &amp; PVC Conduits)The First Point will be considered as Primary Point and balance points as Secondary Points.</b>				
	<b>a. Primary Light points, on LDB</b>	No	20.00		-
	Rate in words :-				
	SITC 5A Primary light points including MS concealed box, grid plate, 6A switch & circuit wiring through LDB				
	<b>b. Primary Light points, on Inverter including wiring rate from inverter</b>	No	18.00		-
	Rate in words :-				
	SITC 5A Primary light points including MS concealed box, grid plate, 6A switch & circuit wiring through Inverter DB				
	( No seperate measurements for Inverter circuit wiring & PVC Conduits, as it's wiring costs to be considered in the Light Point wiring )				

SOQ FOR ELECTRICAL WORKS IN KUDAL BRANCH					
SR. NO.	ITEM	UNIT	QTY	RATE	AMOUNT
<b>c.</b>	<b>Secondary Light points</b>	No	7.00		-
	Rate in words :-				
	SITC 5A Secondary light points looped from primary light point. All MCB controlled light points will be considered as secondary light points.				
<b>d.</b>	<b>Primary 5 A socket points</b>	No	2.00		-
	Rate in words :-				
	SITC <b>Primary 5 A Socket points</b> using circuit wiring (with proper color code) pulled through medium gauge PVC conduits.				
	Each point consisting of <b>1 Nos of 5 A sockets controlled by 1 Nos of 6A switch</b> , wired together forming a point with Green colour Earth wire.				
<b>e.</b>	<b>Secondary 5 A socket points (on Board plug points)</b>	No	11.00		-
	Rate in words :-				
	SITC <b>Secondary 5 A Socket points</b> using circuit wiring (with proper color code) pulled through heavy gauge PVC conduits. These points are installed on the Lighting Switch Board.				
	Each point consisting of <b>1 Nos of 5 A sockets controlled by 1 Nos of 6A switch</b> , wired together forming a point. Earth wire to be of Green colour only.				
<b>f.</b>	<b>Exhaust fan points</b>	No	4.00		-
	Rate in words :-				
	SITC of concealed point wiring for Exhaust fan using 1100V grade 3C x 1.5 sq.mm. copper conductor PVC insulated FRLS wires				
	(with proper R,Y,B colour code) pulled through 25mm / 20mm Size, MMS Grade PVC conduits. All wiring below false ceiling shall be concealed. The wires from ceiling junction to fan points shall be drawn in flexible PVC conduit with adaptor & cover for junction box & crimp type lugs at both ends. The rate shall include circuit wiring (2C x 2.5 sq.mm. + 1C x 1.0 sq.mm.) from Lighting DB to switchboard and to the Exhaust fan. (No separate measurements for circuit wiring & PVC Conduits)				
	Each Exhaust Fan will be operated on separate switch, Rate should be including the cost of 5 A switch, 4 way closed 5A connector & Mounting Plates				
<b>g.</b>	<b>Wall Fan points on Inverter including wiring rate from inveter DB</b>	No	7.00		-

SOQ FOR ELECTRICAL WORKS IN KUDAL BRANCH					
SR. NO.	ITEM	UNIT	QTY	RATE	AMOUNT
	Rate in words :-				
	SITC of concealed point wiring for Wall fan using 1100V grade 3C x 1.5 sq.mm. copper conductor PVC insulated FRLS wires				
	(with proper R,Y,B colour code) pulled through 25mm / 20mm Size, MMS Grade PVC conduits. All wiring below false ceiling shall be concealed. The wires from ceiling junction to fan points shall be drawn in flexible PVC conduit with adaptor & cover for junction box & crimp type lugs at both ends.				
	The rate shall include circuit wiring (2C x 2.5 sq.mm. + 1C x 1.0 sq.mm.) from Inverter DB to switchboard and to the Wall fan Socket point. (No separate measurements for circuit wiring & PVC Conduits)				
	Each wall fan will be operated on separate switch, Rate should be including the cost of 5 A switch, 5 A socket, gang box & Mounting Plates. No separate inverter wiring will be paid				
	( No separate measurements for Inverter circuit wiring & PVC Conduits, as it's wiring costs to be considered in the Point wiring )				
	<b>h. Ceiling fan points</b>	No	4.00		-
	Rate in words :-				
	SITC Ceiling Fan point operated on separate switch shall be Controlled by 2 Module, Step type Fan regulator, Rate should be including the cost of Fan hook, Suspending suitable fan rod, Connecting cord and Step type Fan Regulator				
	<b>i. Bell points</b>	No	2.00		-
	Rate in words :-				
	SITC Bell point consisting of 5A Modular Bell switch & Suitable Bell, ( <i>Bell switch to be installed in Manager Cabin and in Strong room. The Sound of both the bells should be different</i> )				
	<b>j. Indicator Light points</b>	No	4.00		-
	<b>R-Y-B Indicator Light point from Main Power DB to Banking area, for indication of Mains power supply with wiring, indicator lamps etc., easily visible from the Exit / Entrance Door, so that the Last Person to leave the Branch / office should Turn OFF the Power Supply (MCB) Located in Power DB's to switch Off the Lighting, fans, AC's etc.</b>				

SOQ FOR ELECTRICAL WORKS IN KUDAL BRANCH					
SR. NO.	ITEM	UNIT	QTY	RATE	AMOUNT
	Each Indicator Light Point Wiring to be done with 3 X 1.5 Sq.mm. PVC insulated multistanded FRLS Grade flexible copper wires / 3 core 1.5 sq.mm flexible cable drawn through Heavy gauge PVC conduit from Respective DB Power to the Respective Colored Indicator Lamp.				
	<b>Raw Power to be written / Identified on the respective DB with Red Colour</b>				
	<b>UPS Power to be written / Identified on the respective DB with Yellow Colour</b>				
	<b>Lighting Power to be written / Identified on the respective DB with Blue Colour</b>				
	<b>Inverter Power to be written / Identified on the respective DB with Green Colour</b>				
	Rate in words : -				
	<b>C. TOTAL OF POINT WIRING</b>				-
	<b>D FIXTURES</b>				
	SITC of following concealed / surface mounted fixtures of makes as specified with all fixture accessories like suitable tubes/ bulbs/ ballast & internal wiring etc. The contractor has to assemble & install the said fixtures at position with necessary hardware required for installation like S-hook, chain link etc. as per requirement.				
<b>1</b>	<b>LED tube lights 4'</b>	No	11.00		-
	Rate in words : -				
	SITC 1200 mm Long Surface/Wall Mounted extruded Aluminium channels, with 20 w LED Tube light fixtures complete. Rate should be including the cost of Fixture, Suspending suitable rods, other accessories & hardware etc.				
	<b>Make : Philips, Model : BN021 LED25S 6500 PSU GR S1,</b>				
	<b>Make : Crompton Model : Linea LDLL20-CDL, LDLL20-WW</b>				
	<b>Make : Wipro, Model : Garnet D532065, D552065</b>				
	<b>Make : Havells Model : E-Lite LED Pride Pus LHEXBLP7PN1W020</b>				
<b>2</b>	<b>LED tube lights 2'</b>	No	3.00		-
	Rate in words : -				
	SITC 600 mm Long Surface/Wall Mounted extruded Aluminium channels, with 10 w LED Tube light fixtures complete. Rate should be including the cost of Fixture, Suspending suitable rods, other accessories & hardware etc.				
<b>4</b>	<b>15 w Down lighter with LED</b>	No	18.00		-
	Rate in words : -				

SOQ FOR ELECTRICAL WORKS IN KUDAL BRANCH					
SR. NO.	ITEM	UNIT	QTY	RATE	AMOUNT
	SITC 15 w White Powder Coated Housing LED Round / Square Down Lighter with High Efficiency LEDs & Ballasts				
	Make : Philips, Model : DN193B LED12S-6500 PSU WH S1				
	Make : Crompton, Model : PEARL LSCRM-18W-CDL, LSCSM-18W-CDL/NW/WW, LSDRM -18W-CDL,				
	Make : Wipro, Model : CRDL10R015HP40 17W				
	Make : Havells, Model : LHEBJNP7PZ1W018				
<b>5</b>	<b>600 x 600 mm square LED panel fittings</b>	No	13.00		-
	Rate in words : -				
	SITC 36 / 40 w LED Panel of 600mm X 600mm size, Square, Powder coated Recess mounting LED Light Fitting				
	<b>Make:</b> Philips, <b>Model:</b> RC380B G2 LED28S / RC140B G2 LED31S-6500 PSE OD WH				
	<b>Make:</b> Crompton, <b>Model :</b> LCTLR-36-CDL 36 w, LCPL-36-TL(2X2)				
	<b>Make:</b> Wipro, <b>Model :</b> Gartnet D424065, D414065 CRCO10R038HP57				
	<b>Make :</b> Havells, <b>Model :</b> Venus Neo PLR36WLED865PO, Plano PLR42WLED865S				
<b>6</b>	<b>Fans</b>				
	Supplying & Installing following mentioned Aluminum, medium duty, powder coated with glossy color Ceiling Fans / Wall Fans / Exhaust Fans with necessary clamps hook, bracket, hardware etc				
	a. SITC 1200 mm sweep Ceiling fans Complete with Mounting rod, Clamps, Locking pin etc. (Color -White / Ivory / Brown)	No	1.00		-
	Rate in words : -				
	b. SITC 900 mm sweep Ceiling fans Complete with Mounting rod, Clamps, Locking pin etc. (Color -White / Ivory / Brown)	No	3.00		-
	Rate in words : -				
	c. SITC 250mm sweep Exhaust fan of metal body & blade with louvers on the outside	No	3.00		-
	Rate in words : -				
	d. SITC 400mm sweep Wall fan of 1350 RPM. Oscillating type, plastic blades chrome plated guard with speed regulator and moisture proof treatment to winding and with 'E' class insulation.	No	7.00		-
	Rate in words : -				
	<b>D. TOTAL OF FIXTURES</b>				-
<b>E</b>	<b>EARTHING SYSTEM</b>				

SOQ FOR ELECTRICAL WORKS IN KUDAL BRANCH					
SR. NO.	ITEM	UNIT	QTY	RATE	AMOUNT
1	<b>Plate Earthing chemical</b>				
	S & P of Earthing Earth Electrode Station into the true ground level by earthing electrode material refer IS 3043-1987. The rod should be 50 mm diameter and 2 meter in length. The chemical earthing compound should be used.				
a.	<b>Chemical earthing. ....Each one Dedicated Earthing for UPS, Raw Power and ATM</b>	No	3.00		-
	Rate in words :-				
2	<b>Earthing Wires</b>				
	SITC of insulated copper earthing wire laid through 20 mm PVC conduits from separately made earth pit to the equipment in following sizes				
a.	<b>Single core, 4 sqmm FRLS PVC insulated multi threaded, flexible copper wire laid through 20 mm size, MMS Grade PVC Conduites for Raw Power Earthing.</b>	Rmt	80.00		-
	Rate in words :-				
b.	<b>Single core, 6 sqmm FRLS PVC insulated multi threaded, flexible copper wire laid through 20 mm size, MMS Grade PVC Conduites for UPS power Earthing.</b>	Rmt	80.00		-
	Rate in words :-				
3	<b>Main Earth Bus</b>	No	2.00		-
	Supplying & Installing of Main bus for isolated earth comprising of 200mm x 40mm x 6mm thick copper bar fixed on insulated support and having 20 nos of holes and nut bolts studs for clamping the earth leads,all contained in MS / PVC				
	box of size 300mm x 200mm x 50mm deep and having transparent acrylic inspection cover as approved by Bank / Architect.				
	Rate in words :-				
	<b>E. TOTAL OF EARTHING SYSTEM</b>				-
	<b>F. TELEPHONE / VOICE CABLING AND OUTLETS</b>				
1	<b>Telephone points</b>	No	1.00		-
	Rate in words :-				

SOQ FOR ELECTRICAL WORKS IN KUDAL BRANCH					
SR. NO.	ITEM	UNIT	QTY	RATE	AMOUNT
	Providing and laying 2 Pair Grey Color 0.5mm Tinned Cu , PVC insulated cable for Telephone / Voice, laid through 20 / 25 mm size, MMS Grade PVC Conduites and Supplying & terminating with RJ-11 Telephone Jack / Outlet with face plates in suitable modular PVC / MS box from EPABX / Krone Tag Box to the work stations and terminate the other on a 10 pair Krone module installed in a Krone Tag box, complete with numbering of each cable with Ferule and Telephone Connection Chart <b>(No seperate measurements for PVC Conduits)</b>				
	<b>F. TOTAL OF TELEPHONE SYSTEM</b>				-
<b>G</b>	<b>DATA CABLING SYSTEM</b>				
<b>1</b>	<b>Data points</b>	No	11.00		-
	Rate in words :-				
	Supplying and laying D-Link / Molex / Awaya / Amps make, Cat 6 cable for Data, laid through 20/25 mm size, MMS Grade PVC conduites and providing & terminating with RJ-45 Information Outlet Ports with face plates in suitable modular PVC / MS box from Server Rack/ Patch Panel/ Data Switch to individual work stations & terminating other end with RJ-45 connector including numbering with ferule <b>(No seperate measurements for PVC Conduits)</b>				
<b>2</b>	<b>Supplying &amp; laying Cat-6, RJ-45, 1 m. length Data Patch Cords,</b>	No	11.00		-
	<b>Make : D-Link / Molex / Awaya</b>				
	Rate in words :-				
<b>3</b>	<b>Supplying &amp; laying Cat-6, RJ-45, 2 met length Data Patch Cords,</b>	No	6.00		-
	<b>Make : D-Link / Molex / Awaya</b>				
	Rate in words :-				
<b>4</b>	<b>Patch panel</b>				
<b>a</b>	Supplying and Installing D-Link make, preloaded, Cat-6, RJ-45, 24 Port Patch Panel, complete with terminations & numbering with ferule	No	1.00		-
	Rate in words :-				
<b>5</b>	Supplying & Installing D-Link / HCL / iBall make <b>12-U Networking Wall mounting rack</b> , complete with following mentioned accessories	No	1.00		-
	* 2U Horizontal Cable Manager				
	* Power Distribution Unit / Power Strip of 6 Sockets				
	* Cooling Fans				
	* Cantilever Trays / Shelves				

SOQ FOR ELECTRICAL WORKS IN KUDAL BRANCH					
SR. NO.	ITEM	UNIT	QTY	RATE	AMOUNT
	* Hardware Packet				
	Rate in words :-				
	<b>G. TOTAL OF DATA CABLING SYSTEM</b>				-
<b>H</b>	<b>MISCELLANEOUS WORKS</b>				
<b>1</b>	<b>Temporery Lightning supply &amp; data connectivity</b>				
	Arranging temporary Power, data supply & Lighting for all agencies and for staff PCs at work place . The rate shall include statutory aproval from Local MSEDCL / Electrical Inspectorate & other required satatutory bodies, preparation of AS-BUILT drawings, Testing of the installation & prepraition of test report as required by statutory bodies. Note: The rate to include cost of suitable temporary Lighting for all areas as per requirement during work.	Job	1.00		0.00
	Rate in words :-				
<b>2</b>	<b>Buy Back of existing Light fixtures and Fans</b>				
	The Lightning fixtures, Fans and other unused electrical fittings like DBs, switche boards , wiring etc. under Buy back. The rate is including remvoing existing fixtures. The minimum reserve price is <b>Rs. 5,000/- + applicble GST.</b>	Lumsu mp	-1.00		0.00
	<b>H. TOTAL FOR MISCELLANEOUS WORKS</b>				-
	<b>TOTAL FOR ELECTRICAL WORKS</b>			<b>TOTAL</b>	-
				CGST 9%	-
				SGST 9%	-
				<b>GRAND TOTAL</b>	-
	<b>( Amount in Words Rs.</b>				