

CANARA BANK

INVITATION TO TENDER

ONLY FOR EMPANELLED CONTRACTORS

OF

CIRCLE OFFICE KOLKATA

TENDER FROM ANY OTHER CONTRACTOR WILL BE SUMMARILY REJECTED

INSTRUCTION TO BIDERS

AND

GENERAL CONDITIONS OF CONTRACT

FOR

CIVIL WORKS

AT

CANARA BANK – KOLKATA SHYAMBAZAR BRANCH

TENDER NO.: 112/25-26/BDS

NAME OF THE CONTRACTOR:

.....

ADDRESS:

.....

SEAL & SIGNATURE OF TENDERER

NOTICE INVITING THE TENDER

To,

M/s

Sealed tenders on item rate basis are invited from panel Contractors for **Civil Works at premises of Kolkata Shyambazar Branch.**

Tender Documents may be obtained at free of cost from the Premises & Estate Section, Circle Office Canara Bank, Kolkata during working hours from **03.11.2025 till 10.11.2025.**

Earnest Money Deposit : NIL

Period of completion : 21 days

**Last date, time and place for Submission of tender : On or before 3:00 pm, 10.11.2025 to
The Assistant General Manager,
General Administration Section
Canara Bank, Circle Office
Kolkata**

Time and date of opening of tender : 3.30 pm on 10.11.2025

The Bank will not be bound to accept the lowest tender and reserves the right to accept or reject any or all the tenders without assigning any reason whatsoever.

**Assistant General Manager
Premises & Estate Section
Canara Bank, Circle Office
Kolkata**

.....

Date: 03.11.2025

SEAL & SIGNATURE OF TENDERER

GENERAL RULES & INSTRUCTIONS TO TENDERERS

Name of the work: Civil Works to be carried out at premises of Kolkata Shyambazar Branch

The rates quoted shall also be inclusive of materials, labour charges, work contract tax, surcharge and all the taxes except GST.

GST WILL BE PAID EXTRA.

The rates quoted by the tenderer shall hold good till the completion of the work from the date of issue of the "WORK ORDER" and no enhancement in the rates are allowed during the period of execution of the work under any circumstances. The rates quoted shall also cover for the work to be executed before and after office hours and also on holidays.

The time stipulated for the completion of the work is 20 days from the date of issue of the WORK ORDER and the work is to be carried out as per the convenience of occupants without disturbing other occupants of the building.

TENDERS:

The entire set of tender paper issued to the tenderer should be submitted fully priced and also signed on the last page together with initials on every page. Initials / signatures will indicate the acceptance of tender papers by the tenderers.

The schedule of quantities shall be filled in as follows:

- The "rate" column to be legibly filled in ink in both English figures and words.
- 'Amount' column to be filled in for each item and the amount for each sub-head as detailed in the "schedule of quantities".
- All corrections to be initialed.
- The "Rate" column for all the items shall be filled up.
- The "Amount" column for the items for which the quantities are not mentioned shall not be filled up.
- In case of any errors / omissions in the quoted rates, the rates mentioned in the tender in words shall be taken as correct rates.

No modifications, over-writings or corrections can be made in the tender papers by the tenderer, but may at his option offer his comment or modifications in a separate sheet of paper attached to the original tender papers.

The Bank reserves the right to reject the lowest or any tender or all of the tenders for each section or to split up and distribute any item of work to any specialist firm or firms, without assigning any reason.

The tenderers should note that tender is strictly on the item rate basis and their attention is drawn to the fact that the rates for each and every item should be correct, workable and self – supporting. If called upon by the bank, detailed analysis of any or all the rates shall be submitted. The architects/bank shall not be bound to accept the contractor's analysis.

The Quantity mentioned in the BOQ is approximate measurements. The works will be paid for as "measured work" on the basis of actual work done and not as "lump sum" contract.

All the items of work described in the schedule of quantities are to be deemed and paid as complete works in all respects and details including preparatory and finishing works involved, directly, related to and reasonably detectable from the drawings, specifications and schedule of quantities and no further extra charges will be allowed in this connection. In the case of lump-sum charges in the tender in respect of an item of works, the payment of such items of work will be made for the actual work done on the basis of lump-sum charges as assessed to be payable by the architects/bank.

SEAL & SIGNATURE OF TENDERER

The bank has power to add or delete any work or described in specifications or included in schedule of quantities and intimates the same in writing but no addition, omissions or variation shall be made by the contractor without authorization from the bank. No variation shall vitiate the contract. The bank reserves the right to delete any of the items in the tender without assigning any reasons whatsoever.

The tenderer shall note that his tender shall remain open for consideration for a period of 90 days from the date of opening of tender.

AGREEMENT

The successful contractor is required to sign agreement as may be drawn up to suit the local conditions and shall pay for all the stamps and legal expenses incidental thereto. The original will be kept with the Bank and duplicate with contractor.

EARNEST MONEY AND SECURITY DEPOSIT:

There is NO Earnest Money Required to deposit/ submit along with the bids. Retention Money shall be deducted from the final bill at 5% of the gross value of bill. The Retention amount will be refunded to the contractor 15 days after the end of defects liability period provided he has satisfactorily carried out all the work and attended to the entire defect in accordance with the condition of the contract. No interest is allowed on Retention Money.

A part of the Security Deposit if and as decided by the constituent bank can also be furnished in the form of a Bank Guarantee on the bank other than that of the constituent bank.

CONTRACTOR TO PROVIDE EVERYTHING NECESSARY:

The contractor shall provide everything necessary for the proper execution of the work according to the intent and meaning of the drawings, schedule of the quantities and specifications taken together weather the same may or may not be particularly shown or described therein provided that the same can reasonably be inferred there from and if the contractor finds any discrepancies therein he shall immediately and in writing, refer the same to the Architects/Bank whose decision shall be final and binding.

The rates quoted against individual items will be inclusive of everything necessary to complete the said items of works within the contemplation of the contract, and beyond the unit price. No extra payments will be allowed for incidental or contingent labour and/or materials inclusive of all taxes and duties whatsoever except for specific items, if any, stipulated in tender documents

The contractor shall supply, fix and maintain at his own cost, for the execution of any work, all tools, tackles, machineries and equipment and all necessary scaffolding, staging and lighting by night as well as by day required not only for proper execution and protection of the said work.

The contractor shall take down and remove any or all such scaffoldings as occasion shall be required or when ordered to do so, and shall fully reinstate and make good all matters and things disturbed during the execution of work to the satisfaction of architect/bank.

The contractor shall all times give access to workers employed by the bank or any men employed at site and to provide such parties with proper sufficient and if required, special scaffolding and ladder and provide them lighting as may be required to enable such workmen to inspect the work, lay or fix pipes, Civil & furnishing wiring, special fittings etc. The quoted rates of tenderers shall accordingly include all these above-mentioned contingent works.

LIQUIDATED DAMAGES:

Should the work be not completed to the satisfaction of bank within the stipulated period, the contractor shall be bound pay the bank a sum calculated as given below by way of Liquidated Damages after the expiry of completion date

.1.00% of the estimated amount shown in the tender per week subject to a ceiling of 10% of the accepted contract sum.

TIME PERIOD FOR COMPLETION: 20 days from the date of award of work.
--

SEAL & SIGNATURE OF TENDERER

FINAL PAYMENTS

The final bill shall be accompanied by a certificate of completion from the Occupant/Bank Officials. Payments of the final bill shall be made after deduction of retention money as specified in clause 9 of these conditions which sums shall be refunded after the completion of the defects liability period after receiving the banks certificate that the contractor has rectified all defects to the satisfaction of the banks. The acceptance of payments of the final bill by the contractor would indicate that he would have no further claims in respect of the work executed.

ESCALATION:

The rates quoted shall be firm throughout the tenure of the contract [including extension of time, if any granted] and will not be subject to any fluctuation due to increase in cost of materials, labour, sales tax, octroi etc, unless specifically provided in these documents.

CONTRACTORS EMPLOYEES:

The contractor shall employ technically qualify and competent supervisors for the work who shall be available [by turn] throughout the working hours to receive and comply with the instructions of the bank officials. The contractor shall engage at least one experienced engineer, as site in-charge for the execution of the work the contractor shall employ in connection with the work persons having appropriate skill or ability to perform their job efficiently. The contractor shall employ local labours on the work as far as possible. No laborers below age of 16 and who is not an Indian national shall be employed on the work. Any laborers supplied by the contractor to be engaged on the work on day-work basis either wholly or partly under the direct order or control of bank or its representative shall be deemed to a person employed by the contractor.

The contractor shall comply with provision of all labour legislation including the requirements of

- a. Payments of minimum wages act
- b. Employers liabilities
- c. Workmen's compensation act
- d. Contract labour (regulation and abolition) act, 1970 and central rules 1971
- e. Apprentices act 1961
- f. Any other act or enactment relating thereto and rules framed there under from time to time

The contractor shall keep the bank saved harmless and indemnified against claims if any of the workmen and all costs and expenses as may be incurred by the bank in connection with any claim that may be made by any workmen.

The contractor shall comply at his own cost with the order of requirement of any health officer of state or any local authority or of the bank regarding the maintenance of proper environmental sanitary condition of the area.

The contractor shall arrange to provide first aid treatment to the laborers engaged on the works. He shall within 24 hrs of occurrence of any accident at or about the site or in connection with execution of work, report such accidents to the bank and also the competent authority where such report is required by law.

The contractor shall obtain all Risk Insurance Policy at their cost within 7 days of commencement of work, for the laborers/workmen working at the site including the work till the work is completed. The policy shall be in the joint name of the Bank and contractor and Bank's name shall appear First.

PAYMENTS:

The contractor, in the form prescribed by the bank shall prepare all the bills and submit the same to Bank with measurement of work. Normally one interim bill shall be prepared each month. Bank may release payment within 15 days of receipt of bills/after check measurement, after deduction of retention money, Income Tax etc. The contractor shall have a competent engineer at site for the supervision of the work.

The contractor shall have to make his own arrangements for watch and ward of the work/building, till the work is handed over to the bank.

The decision of the bank will be final and binding with regard to the quality of work is concerned.

SEAL & SIGNATURE OF TENDERER

The contractor is responsible for procuring the required materials for the work and stores the same at site at his cost and risk.

The amount stated in the interim certificate shall be the 75% of total value of the work executed up to date of the bill, less the amount to be retained by the bank as retention money. If the bank has supplied any materials or goods to the contractors, the cost of such materials will be progressively deducted from the amount due to the contractor on accordance with the quantities consumed in the work. All the interim payments shall be regarded as payments by way of advance against the final payment only and not as payments for works actually done and completed and shall not preclude the requiring of bad, unsound or imperfect or unskilled work to be removed and taken away and reconstructed or re-erected or be considered as an admission of the due performance of the contract or any part there of if any respect or accruing of any claim nor shall it conclude, determine of effect in any way the power if the bank under conditions or any of them add to the final settlement and adjustment of the accounts or otherwise or in any other way or affect the contract.

The contractor shall submit the final bill within one month from the date of completion of the work. A certificate of completion from the bank shall accompany the final bill. The payment of the final bill shall be made after deduction of retention money as specified elsewhere in these documents.

ARBITRATION:

All disputes or differences of any kind whatsoever which shall at any time arise between the parties here to touching or concerning the works or the execution or maintenance thereof of this contract or the rights touching or concerning the works or the execution of maintenance thereof of this contractor or the construction remaining operation or effect thereof or to the rights or liabilities of the parties are arising out of or in relation thereto whether during or after determination foreclosure or branch of the contract[other than those in respect of which the decision of any person is by the contract expressed to be final and binding] shall after written notice by either party to the contract to the other of them and to the employer hereinafter mention to deal referred for adjudication to a sour arbitrator to be appointed as hereinafter provided.

For the purpose of appointing the sole arbitrator referred to above, the employer will send within 30 days of receipt of the notice, to the contractor a panel of 3 names of persons who shall be presently unconnected with the organization for which the work is executed.

The contractor shall on receipt of the names as aforesaid, select, anyone of the person's name to be appointed as a sole arbitrator and communicate his name to the employer within 30 days of the receipt of the names. The employer shall thereupon without any delay appoint the person as the sole arbitrator. If the contractor fails to communicate such selection as provided above within the period specified, the competent authority shall make the selection and appoint the selected person as the sole arbitrator.

If the employer fails to send to the contractor the panel of 3 names as a foresaid within the period specified, the contractor shall send to the employer a panel of 3 names of persons who shall be unconnected with either party. The employer shall on receipt of the name as a foresaid select anyone of the person's names and appoint him sole arbitrator. If the employer fails to select the person and appoint him as a sole arbitrator within 30 days of the receipt of the panel and inform the contractor accordingly, the contractor shall be entitled to appoint one of the persons from the panel as the sole arbitrator and communicate his name to the employer.

If the arbitrator as appointed is unable or unwilling to act or resigns his appointment or vacates his office due to any reason whatsoever another sole arbitrator shall be appointed as aforesaid.

The work under contract shall, however, continue during arbitration proceedings and payment due or payable to the contractor shall be withheld on account of such proceedings.

SEAL & SIGNATURE OF TENDERER

The arbitrator shall be deemed to have entered on the reference the data he issued notice to both the parties fixing the date of the first hearing.

The arbitrator may from time to time, with the consent of parties, enlarge the time or making and publishing the award.

The arbitrator shall give a separate award of each disputes or difference referred to him. The arbitrator shall decide each dispute in accordance with the terms of the contract and give a reasonable award. The venue of arbitration shall be such place as may be fixed by the arbitrator in his sole discretion.

The fee, if any, of the arbitrator shall, if required to be paid before the award is made and published, be half and half by each of the parties. The cost of the reference and of the award including the fees, if any, of the arbitrator who may direct to and by whom and in what manner, such costs or any part thereof shall be paid and may fix or settle the amount of costs to be so paid.

The award of the arbitrator shall be final and binding on both the parties.

Subject to aforesaid the provision of the arbitration act 1940 or any statutory modification or re-enactment thereof and the rules made there under, and for the time being in force, shall apply to the arbitration proceeding under this clause.

The employer and the contractor hereby also agree that arbitration under the clause shall be a condition precedent to action under the contract with regard to the matters hereby expressly agreed to be so referred to arbitration.

Date:

**Signature of the Contractor
With seal and address**

SCHEDULE OF CIVIL WORKS AT KOLKATA SHYAMBAZAR BRANCH					
Sl No.	Description Of Item	Qty.	Unit	Rate (Rs.)	Amount (Rs.)
1	Dismantling existing Wall/Floor Tiles, any types of masonry work, wooden door & windows, cooking counter, sanitary fittings, water line etc. and removing the rubbish outside the compound of building / premise complying local municipal rules as per direction of Bank / Architect.				
a	wall / floor tiles/mosaic in toilet / banking hall	1300.00	sq. ft.		
b	door (toilet)	3.00	unit		
c	existing ALL bathroom fittings (all 3 toilet & 1 pantry will be considered as 1 unit)	1.00	set		
d	existing ALL water supply lines & fittings (all 3 toilets & 1 pantry will be considered as 1 unit)	1.00	set		
e	existing plastering	400.00	sq. ft.		
f	PCC	12.00	c ft.		
g	RCC work (column / beam / lintel etc.)	25.00	c ft.		
2	Providing and applying two coats of single component liquid Rust remover cum passivator (Sika Rustoff-100 of M/s Sika India Pvt Ltd. or similar equivalent) to the steel reinforcement at the dosage recommended by the manufacturer, all complete as directed. Payment will be made on the contact area of old concrete surface.	100.00	sq. ft.		
3	Providing and applying two coats of cement bound modified anti-corrosive protective coating (Sika Top Armatec- 108 of M/s Sika India Pvt Ltd. or similar equivalent) to the steel reinforcement at the dosage recommended by the manufacturer, all complete as directed. Payment will be made on the contact area of old concrete surface.	100.00	sq. ft.		
4	Providing and applying epoxy based bonding agent (Sikadur- 32 LP of M/s Sika India Pvt Ltd. or similar equivalent) for application to old concrete surface, all complete as per direction. Payment will be made on the concrete area of the old concrete surface.	100.00	sq. ft.		
5	Providing and applying average 40 mm thick SikaRep® Microcrete-4 of sika India Pvt. Ltd. or similar equivalent make to R.C.C. columns, beams, fins, chajja etc. over the chemically treated surface at the dosage recommended by the manufacturers, including providing support props & slurry tight shuttering of 12 mm. thk. plywood all complete as directed. (quoted	25.00	c. ft.		

SEAL & SIGNATURE OF TENDERER

	price should include cost of providing 6 mm. down graded stone chips with recommended proportion)				
6	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete above plinth level. :Mild steel and Medium Tensile steel bars	80.00	kg.		
7	Plain cement concrete works with coarse aggregate of sizes 13mm to 32mm in plinth, walls, brick works etc. as directed and specified including dewatering if necessary, and curing complete (shuttering where necessary shall be measured and paid separately). (a) In prop 1cement: 3 sand :6 coarse aggregate by volume	15.00	c ft.		
8	Brick work with 1st class bricks in cement mortar In superstructure				
a	125 thk. (1 : 4)	80.00	sq. ft.		
9	15 mm. thk. Plastering with sand and cement mortar including rounding off or chamfering corners as directed and raking out joints or roughening of concrete surface, including throating, noising and drip course where necessary. With 6:1 sand-cement mortar. including cost of scaffolding etc.	850.00	sq. ft.		
10	Rendering the Surface of walls and ceiling with White Cement based water proof wall putty of approved make & brand.(1.5 mm thick) complete as directed.	5000.00	sq. ft.		
11	Applying Interior grade Acrylic Primer of approved quality and brand on plastered or concrete surface in old or new work to receive Distemper/ Acrylic emulsion paint including scraping and preparing the surface throughly, complete as per manufacturer's specification and as per direction of the EIC at any floor. Water based interior grade Acrylic Primer One coat.	7000.00	sq. ft.		
12	Applying Acrylic Emulsion Paint of approved make and brand (Asian Paints Apcolite/ ICI Dulux Super Clean / Berger Easy clean) on walls and ceiling including sand papering in intermediate coats including putty (to be done under specific instruction of Superintending Engineer) : Two coats with Luxury Quality.	7000.00	sq. ft.		

13	Priming one coat on steel or other metal surface with synthetic oil bound primer of approved quality including smoothening surfaces by sand papering etc. (This item is applicable to new work or old work when the original surface has been exposed by removal of old paint)	750.00	sq. ft.		
14	Painting with best quality synthetic enamel paint of approved make and brand (ICI Dulux 5 in 1 or Equivalent) including smoothening surface by sand papering etc. including using of approved putty etc. on the surface, if necessary.				
a	Two coats (with any shade except white) with super gloss (hi-gloss) of approved quality on steel or other metal surface.	750.00	sq. ft.		
15	Supplying and laying true to line and level double charge Vitrified Tiles of approved brand conforming to IS 15622: 2006 (Group B I a) and tested as per IS 13630:2006 (relevant parts) [Non-modular sizes for tiles with Water absorption (av.) ≤ 0.08 %] in floor, skirting etc. using polymerised adhesive of 6mm thick layer applied directly over finished artificial stone floor/Mosaic etc. without any backing course and polishing the tiles using soft and dry cloth upto mirror finish complete including the cost of materials,labour and all other incidental charges complete as per direction of Architect. Floor Tiles : 600 x 600 mm	1500.00	sq.ft.		
16	Supplying and laying true to line and level Step Vitrified Tiles of approved brand, using polymerised adhesive of 6mm thick layer applied directly over finished artificial stone floor/Mosaic etc. without any backing course and polishing the tiles using soft and dry cloth upto mirror finish complete including the cost of materials,labour and all other incidental charges complete as per direction of Architect.				
	Trade	50.00	sq.ft.		
	Riser	35.00	sq.ft.		
	Landing	15.00	sq.ft.		
17	Providing & fixing Marble slab strip 75 mm wide laid on 20 mm (average) thick cement mortar 1:3 (1 cement: 3 coarse sand) and jointed with white cement slurry mixed with pigment to match the shade of the slabs, including rubbing, moulding and polishing complete. (Location : Window sill , Ramp)	100.00	rft		

18	Providing existing Steel window servicing with supplying and fixing necessary hardwares etc. complete.	8.00	Nos.		
19	Providing & fixing 4 mm. thk. Clear Float glass into the existing shutter / frame of steel window with necessary putty, nails etc. complete.	150.00	sq. ft.		
20	Dismantling & Removal of existing wooden shutter of window in ground floor	20.00	Nos.		
21	Providing and fixing 2 / 3 track Sliding Aluminium Anodized (white colour anodized of 15 micron thickness in mat satin finish) glazed windows made from extured section of necessary hardware fitting including providing and fixing 4 mm. thick clear/obscered float glass panes and / bug mesh with gaskets, glazing beads and sealing joints between wall and window with silicon sealants of approved make, provision for fixing glass panes from inside and Neoprene weather seals etc. complete with labour and materials.	110.00	sq.ft		
22	providing and laying factory made chamfered edge cement Concrete paver blocks in footpath, parks, lawns, drive ways or light traffic parking etc, of required strength, thickness & size/ shape, made by table ibratory method using PU mould, laid in required colour & pattern over 50mm thick compacted bed of sand, compacting and proper 6 embedding/laying of inter locking paver blocks into the sand bedding layer hrough vibratory compaction by using plate vibrator, filling the joints with sand and cutting of paver blocks as per required size and pattern, finishing and sweeping extra sand. complete all as per direction of ngineer-in-Charge. 60 mm thick CC paver block of M-30 Grade with approved color design and pattern.	300.00	sq.ft		
23	Providing and fixing 1st quality Ceramic Glazed / matt Wall/ floor tiles conforming to IS : 15622 (thickness to be specified by the manufacturer), of approved make, in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge, in skirting, risers of steps and dados, over 12-20 mm thick bed of cement mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm, including pointing in white cement mixed with pigment of matching shade complete. (Location : Toilet)				

a	In walls with tile adhesive / Sand Cement Mortar (1:3) 15 mm thick & 2 mm thick cement slurry at back side of tiles using cement @ 2.91 Kg/Sq.m & joint filling using white cement @ 0.20kg/Sq.m. Coloured decorative premium quality tile size 450 x 300 mm.	480.00	sq.ft		
b	In floor with tile adhesive / Sand Cement Mortar (1:4) 20 mm thick & 2 mm thick cement slurry at back side of tiles using cement @ 2.91 Kg/Sq.m & joint filling using white cement slurry @ 0.20kg/Sq.m. Area of each Coloured decorative premium quality tile size 300 x 300 mm.	120.00	sq.ft		
24	Black Stone Slabs 25 mm thick in structure of cooking platform laid on 12 mm (average) thick cement mortar 1 : 4 (1 cement : 4 coarse sand) and jointed with grey cement slurry/adhesive mixed with pigment to match the shade of the slabs, including rubbing and polishing complete. (Location : Kitchen)	60.00	sq.ft		
25	Granite slabs (Sadar Ali / Galaxy) 18 mm thick in cooking platform laid on 12 mm (average) thick cement mortar 1:3 (1 cement: 3 coarse sand) and jointed with grey cement slurry mixed with pigment to match the shade of the slabs, including rubbing, moulding and polishing complete. (Location : Kitchen)	40.00	sq.ft		
26	Supplying, Fitting & Fixing Factory made P.V.C. door frame of size 50 mm x 47mm with a wall thickness of 5mm, made out of extruded 5mm, PVC sheet miter cut at two corners and joined with two nos of 1.5 mm long brackets of 15mm x 15mm M.S. square tube. The two vertical door profiles are to be reinforced with 19mm x 19mm M.S. Square tube of 19 gauge, weather seal to be provided throughout the frame. The door frame shall be fixed with the wall using 65/100 mm long M.S. Screws through the frame by using P.V.C fasteners. A minimum of 4Nos of screws to be provided for each vertical member and minimum 2 Nos for horizontal member etc. complete as per Manufacturer's specification and direction of Engineer-in-Charge. (Make: Sintex)	50.00	rft.		

27	Supplying, Fitting & Fixing 30 mm thick factory made Poly Vinyl Chloride (PVC) door shutter made of styles and rails of a UPVC hollow section of size 60 x 30 mm and wall thickness 2 mm (± 0.2 mm), with inbuilt decorative moulding edging on one side. The styles and rails mitred and joint at the corners by means of M.S. galvanised/ plastic brackets of size 75 x 220 mm having wall thickness 1.0 mm and stainless steel screws. The styles of the shutter reinforced by inserting galvanised M.S. tube of size 25x20 mm and 1 mm (± 0.1 mm) wall thickness. The lock rail made up of 'H' section, a uPVC hollow section of size 100x30 mm and 2 mm (± 0.2 mm) wall thickness fixed to the shutter styles by means of plastic/galvanised M.S. 'U' cleats. The shutter frame filled with a uPVC multi-chambered single panel of size not less than 620 mm, having over all thickness of 20 mm and 1 mm (± 0.1 mm) wall thickness . The panels filled vertically and tie bar at two places by inserting horizontally 6 mm galvanised M.S. rod and fastened with nuts and washers, complete as per manufacturer's specification and direction of Engineer-in-charge.	35.000	sq.ft		
SANITARY - PLUMBING WORKS					
28	Providing and fixing Wash Basin with C.I. brackets, 15 mm C.P. brass pillar taps, 32 mm C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever require				
a	White Vitreous China Wash basin size 630 x 450 mm	2	Nos.		
29	Supplying, fitting and fixing pedestal of approved make for wash basin (white) (Make: Hindware/Parryware).	2	Each		
30	Supplying, fitting and fixing Flat back Full Stall Urinal in white vitreous chinaware of approved make in position with brass screws on 75mm X 75mm X 75mm wooden blocks complete. Size: 635mm X 395mm X 420mm	2	each		
31	Providing and fixing white vitreous china (European type) Water Closet . [Base Price : 1050.00 - 1100.00]	2	Nos.		
32	Providing and fixing P.V.C. low Level Flushing Cistern with manually controlled device (handle lever) conforming to IS : 7231, with all fittings and fixtures complete.				
a	10 litre (full flush) capacity-white	2	Nos.		
33	Providing and fixing Solid Plastic Seat with lid for pedestal type W.C. complete.				

a	White solid plastic seat with lid	2	Nos.		
34	Providing and fixing P.V.C. Waste Pipe for sink or wash basin including P.V.C. waste fittings complete.				
a	32 mm dia	2	Nos.		
35	Providing and fixing Mirror of superior glass (of approved quality) and of required shape and size with plastic moulded frame of approved make and shade with 6 mm thick hard board backing.				
a	Rectangular shape 450 x 600 mm	2	Nos.		
36	Providing and fixing Chlorinated Poly Vinyl Chloride (CPVC) pipes , having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, i/c fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and the cost of cutting chases and making good the same including testing of joints complete as per direction of Engineer in Charge.				
	Concealed work , including cutting chases and making good the walls etc.				
a	20 mm nominal outer dia Pipes	120.00	r.ft.		
b	40 mm nominal outer dia Pipes	30.00	r.ft.		
37	Providing and fixing on wall face unplasticised Rigid PVC soil / waste water pipes conforming to IS : 13592 Type B , including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion, (i) Single socketed pipes. : 110 mm diameter including all coupler, tee, door tee, bend, shoe, pipe clip etc. in wall / floor by PVC clamp using rawl plug and screw in wall etc. complete in all respect.	25.00	r.ft.		
38	Providing and fixing unplasticised P.V.C. connection pipe with PTMT Nuts, collar and bush of approved quality and colour.				
a	15 mm nominal bore with 60 cm length	6	Nos.		
39	Supplying, fitting and fixing of CPVC Ball Valve conforming to IS-15778 : 2007 of approved make / brand.				
a	25 mm. dia.	2	Nos.		
40	Providing and fixing Chromium plated Angular Stop Cock with wall flange (Equivalent to Code No. 5053 & Model - Florentine of Jaquar or similar brand).				
	15 mm nominal bore	6	Nos.		

SEAL & SIGNATURE OF TENDERER

41	Providing and fixing Chromium plated Bib Cock with wall flange (Equivalent to Code No. 5047 & Model - Florentine of Jaquar or similar brand)..				
	15 mm nominal bore	4	Nos.		
42	Providing and fixing C.P. Long Body Bib Cock with wall flange (Equivalent to Code No. 5047 & Model - Florentine of Jaquar or similar brand)..				
	15 mm nominal bore	2	Nos.		
43	Providing and fixing CP 2-way bib Cock - 15 mm, supplied, fitted and fixed. (Code No.5041 & Model - FLORENTINE of JAQUAR or similar brand).	2	Nos.		
44	Providing and fixing Hand Shower (Health Faucet) with 1mtr Flexible Tube with Wall Hook(Equivalent to Code No.573 & Model - ALLIED of Jaquar or similar)	2	Nos.		
45	Providing and fixing SS Liquid Soap Container 109 mm wide, 125 mm high and 112 mm distance from wall of standard shape with bracket of the same materials with snap fittings of approved quality and colour, weighing not less than 105 gms.	2	Nos.		
46	Providing and fixing SS Towel Ring trapezoidal shape 215 mm long, 200 mm wide with minimum distances of 37 mm from wall face with concealed fittings arrangement of approved quality and colour, weighing not less than 88 gms.	2	Nos.		
47	Providing and fixing SS Towel Rail complete with brackets fixed to wooden cleats with CP brass screws with concealed fittings arrangement of approved quality and colour.				
	600 mm long towel rail	2	Nos.		
48	Providing and fixing in position 100mm dia S.S Grating with frame square / round for cockroach repellent	4	Nos.		
49	Providing and fixing Tactile Tiles Anti Skid, Direction, PU 300 x 300 mm	45.00	sq. ft.		
50	Providing and fixing inside strong room 1.5 mm. thk. Vinyl Flooring available in roll form fixed to floor with adhesive complete.	100.00	sq. ft.		
A	TOTAL EXCLUSIVE OF GST				
B	DISCOUNT IF ANY				
C	TOTAL AFTER DISCOUNT (A-B)				
D	GST				
E	TOTAL INCLUSIVE OF GST (C+D)				

SEAL & SIGNATURE OF TENDERER

APPROVED MAKE OF MATERIALS		
1	Paints (Synthetic Enamel / Acrylic Emulsion)	Asain Paints / Berger / Dulux
2	Cement	Ultratech / Lafarge / ACC
3	MS ANGLE / FLAT / SQ. BAR	TATA / JINDAL / RINL
4	Reinforcement Bar	SAIL/ TATA/ RINL
5	Construction Chemicals	Sika / Pidilite / Fosroc
6	UPVC / CPVC Pipes	Supreme / Astral
7	PVC Flooring	Krishna Vinyl / Armstrong / Birla
8	European WC / Washbasin	Hindware /Parryware
9	Plumbing Fittings	Jaquar / Essco Delux
10	G.I. Pipe	Tata (Medium)
11	Vitrified Tiles	Johnson / Nitco / Kajaria
12	Ceramic Tiles	Johnson / Nitco / Kajaria

SEAL & SIGNATURE OF TENDERER