

SOQ FOR ELECTRICAL WORK AT KISRUL BRANCH (1905)					
	The stickers to be pasted for all raw power points and UPS power points				
	The stickers to be pasted for all DBS				
	ALL FRLS wires to be used				
	The cables to be used for Item 'B'				
	Electrical Power Load 12 Kw				
	Type of wiring	Concealed			
	Casing capping (as per approval)	Modi make/ Precision (ISI grade)			
	PVC pipe and accessories	Precision / Polycab / Swastik (ISI make)			
	Wires	Polycab / Finolex / R R kabel make with			
	Computer DataCable	D-Link / Molex / Awaysa make			
	cable	Polycab / Finolex / R R kabel make (ISI grade)			
	MCB / MCB DB	L & T, Legrand / Siemens (ISI)			
	ELMCB	L & T, Legrand / Siemens (ISI)			
	Ft. tubes & fixtures	Philips / Wipro / Crompton / Havells / Bajaj			
	Ceiling fans	Crompton Greaves / Havells / Usha			
	screws	Nettlefold			
	Earthing material	Strictly Bare Copper and with charcoal			
	Switch fuse unit	L & T make (ISI)			
	Switches/sockets & accessories	Legrand / Anchor Roma Modular type			
	switchboards	Concealed modular type			
	Copper strip type busbar	Havells / Standard make			
	ONLINE UPS	Fuji / Vertiv			
	SMF Batteries	Exide / Amaron			
	Offline UPS / Inverter	Microtek / Havells			
	Tubular Batteries	Exide / Amaron			
	Labelling for Raw power and UPS power to be done at all switches				
SR	SUMMARY				AMOUNT
A	TOTAL OF MAIN PANEL / DB's / MCCBs :-				-
B	TOTAL OF CABLES & TERMINATIONS				-
C	TOTAL OF POINT WIRING				-
D	TOTAL OF FIXTURES				-
E	TOTAL OF EARTHING SYSTEM				-
F	TOTAL OF TELEPHONE SYSTEM				-
G	TOTAL OF DATA CABLING SYSTEM				-
H	TOTAL FOR MISCELLANEOUS WORKS- Temporery Shifting				-
	TOTAL FOR ELECTRICAL WORKS				-
	DISCOUNT OFFERED -	0%			
	Less Buy back				-
	GRAND TOTAL FOR ELECTRICAL WORK				-
					GST extra
	Amt. in Rs. :- Rs. Only.				
					GST extra
SOQ FOR ELECTRICAL WORK AT KISRUL BRANCH, (DP CODE- 1905)					
SR. NO.	ITEM	UNIT	QTY	RATE	AMOUNT
A	MAIN PANEL / DISTRIBUTION BOARDS / MCCBs :-				

Name and Address of the Contrcator with Sign and Seal

SOQ FOR ELECTRICAL WORK AT KISRUL BRANCH, (DP CODE- 1905)					
SR. NO.	ITEM	UNIT	QTY	RATE	AMOUNT
1	Meter room Mains MCCB's				
	Supplying & Installing 80A / 100A, FP MCCB in Sheet Steel Enclosure, complete with Gland Box etc				
	a. 80A / 100 A FP MCCB 16kA	Nos.	1.00		-
	Make : Legrand, Type : DPX3 160 with Thermal & Magnetic protection Unit				
	b. Sheet steel Enclosure Box for FP MCCB	Nos.	1.00		-
2	MCB DISTRIBUTION BOARDS				
	SITC sheet metal fabricated & powder coated Double Door Type MCB Distribution Boards (surface/flush mounted). DB's shall have MCB/MCCB as incomer, RCCB as sub-incomer & SP/DP/TP MCB as outgoing, complete with Per Phase Isolation. All MCBs of C characteristics and 10 KA breaking capacity & ELCB's, RCCB's, RCBO's should be of 100mA sensitivity. The DB shall have appropriate no. of top & bottom knock outs for outgoing circuits & shall be complete with necessary bus bars, interconnecting terminals & earth studs. All terminations in DB shall be complete with feruling, dressing with lugs & all circuits shall be properly labeled with PVC strip (sticker type) having identification as per the final approval of the Consultant.				
2.1	SITC Mains DB,				
	i) 6 way VTPN - MCCB DB,	Nos.	1.00		-
	ii) 80/100 A - TP MCCB, 16kA	Nos.	1.00		-
	iii) 25 A - TP MCB outgoing (LDB)	Nos.	2.00		-
	iv) 63 A - TP MCB outgoing (AC DB & Spare)	Nos.	2.00		-
	v) 25/32 A - SP MCB outgoing (UPS Input / Inverter DB, Signage / ATM DB)	Nos.	3.00		-
	vi) Blanking plates	Nos.	8.00		-
2.2	SITC LIGHTING DB				
	i) 6 way TPN - MCB DB,	Nos.	1.00		-
	ii) 63 A - FP MCB, as incomer	Nos.	1.00		-
	iii) 25 A - DP 30mA <u>RCCB</u> / <u>ELCB</u>, as sub-incomer	Nos.	3.00		-
	iv) 6/10 A - SP MCB outgoing	Nos.	12.00		-
2.3	SITC RAW POWER & AC DB				
	i) 6 way TPN - MCB DB,	Nos.	1.00		-
	ii) 63 A - TPN MCB	Nos.	1.00		-

SOQ FOR ELECTRICAL WORK AT KISRUL BRANCH, (DP CODE- 1905)					
SR. NO.	ITEM	UNIT	QTY	RATE	AMOUNT
iii)	40 A - DP 100mA <u>RCCB</u> / <u>ELCB</u> , as sub-incomer	Nos.	3.00		-
iv)	16/20/25/32 A - SP MCB outgoing	Nos.	12.00		-
2.4 SITC UPS Output DB					
i)	6 way SPN - MCB DB,	Nos.	1.00		-
ii)	32 A - DP MCB as incomer	Nos.	1.00		-
iii)	32A - SP MCB outgoing, for Branch UPS DB	Nos.	2.00		-
iv)	16A - SP MCB outgoing, for CCTV, Network rack, Security alarm system etc	Nos.	2.00		-
2.5 SITC BRANCH UPS DB					
i)	12 way SPN - MCB DB,	Nos.	1.00		-
ii)	32 A - DP MCB as incomer	Nos.	2.00		-
iii)	16/20A - SP MCB outgoing	Nos.	10.00		-
2.6 SITC INVERTER Lighting DB					
i)	8 way SPN - MCB DB,	Nos.	1.00		-
ii)	25 A - DP MCB as incomer	Nos.	1.00		-
iii)	6/10A - SP MCB outgoing	Nos.	6.00		-
2.7 SITC ATM LDB / AC DB					
i)	6 way SPN - MCB DB,	Nos.	1.00		-
ii)	32 A - DP MCB as incomer	Nos.	1.00		-
iii)	10/16/20A - SP MCB outgoing	Nos.	2.00		-
2.8 SITC ATM UPS Output DB					
i)	6 way SPN - MCB DB,	Nos.	1.00		-
ii)	16/20 A - DP MCB as incomer	Nos.	1.00		-
iii)	10/16A - SP MCB outgoing	Nos.	2.00		-
2.9 MCB BOX					
a.	SITC 4 way - MCB with Box, for switching off the lighting DB near main gate to <u>switch OFF all the light points</u> after office hours				
i)	Sheet steel Enclosure Box for FP MCB	Nos.	1.00		-
ii)	40/32/25 A - FP MCB	Nos.	1.00		-
b.	SITC 4 way - MCB with Box, for switching off the AC DB near main gate to <u>switch OFF all the AC's</u> after office hours				
i)	Sheet steel Enclosure Box for FP MCB	Nos.	1.00		-
ii)	63 A - TPN MCB	Nos.	1.00		-

SOQ FOR ELECTRICAL WORK AT KISRUL BRANCH, (DP CODE- 1905)					
SR. NO.	ITEM	UNIT	QTY	RATE	AMOUNT
d.	SITC 2 way - MCB with Box, for UPS Input / Output and for switching OFF UPS outputs to branch				
i)	Sheet steel Enclosure Box for DP MCB	Nos.	3.00		-
ii)	32/25 A - DP MCB	Nos.	3.00		-
e.	SITC 2 way - MCB with Box, for Signage and for switching OFF Inverter outputs to branch				
i)	Sheet steel Enclosure Box for DP MCB	Nos.	2.00		-
ii)	20/25 A - DP MCB	Nos.	2.00		-
4.0 a)	Supplying & Installing 10/20 A Modular Power Socket points complete with MS concealed box, Modular Switch plate, 20A Modular Socket, controlled by a Modular 20 / 25A SP MCB with necessary screws, nylon plug, Saddles, hardware etc. including cost of 3 x 4.0 sqmm PVC insulated FRLS copper Wires and 25mm/20 mm PVC conduit, <i>For ATM UPS & Inverter Input & Output connections</i>	Nos.	1.00		-
	Rate in words :-				
b)	Supplying & Installing 20 A Power Socket points complete with MS concealed box, 20A Modular Socket, without local switch (<i>directly controlled by a 20 / 25A SP MCB in AC DB</i>) with necessary screws, nylon plug, Saddles, hardware etc. <i>For High Wall Split AC Units</i>	Nos.	4.00		-
	including cost of 2x4.0 sqmm + 1x2.5 sqmm PVC insulated FRLS copper Wires and 25mm/20 mm PVC conduit, <i>For High Wall Split AC Units</i>				
	Rate in words :-				
c)	Supplying & laying circuit wiring for 20 A Power Socket points (without any socket / switch (<i>directly controlled by a 20 / 25A SP MCB in AC DB</i>) with necessary screws, nylon plug, saddles, hardware etc. by laying 2x4.0 sqmm + 1x2.5 sqmm PVC insulated FRLS copper Wires through 25mm/20 mm PVC conduits, <i>For Cassette AC Units</i>	Nos.	0.00		-

SOQ FOR ELECTRICAL WORK AT KISRUL BRANCH, (DP CODE- 1905)					
SR. NO.	ITEM	UNIT	QTY	RATE	AMOUNT
	including cost of 2x4.0 sqmm + 1x2.5 sqmm PVC insulated FRLS copper Wires and 25mm/20 mm PVC conduit, <i>For Cassette AC Units</i>				
	Rate in words :-				
	Strong Room Power Point				
d)	Supplying & Installing 20 A Power Socket points complete MS concealed box, Modular Switch plate, 20A Modular Socket, controlled by a Modular 20A SP MCB with necessary screws, nylon plug, Saddles, hardware etc. including cost of 2x2.5.0 sqmm + 1x1.5 sqmm PVC insulated FRLS copper Wires and 25mm/20 mm PVC conduit, <i>For Strong Room / Cash room Entrance as It's Lighting circuit control from outside. Lighting switch board inside the Strong room / Cash room to be connected using, 2 mets of 3 core 1.5 sq mm flexible copper cable with 15 A plug top from this power socket installed outside the room (rate should be given inclusive of flexible cable, plug top and circuit)</i>	Nos.	1.00		-
	Rate in words :-				
	A. TOTAL OF MAIN PANEL / DB's / MCCBs :-				-
B	CABLES & TERMINATIONS				
	Supply and Laying of following LT cables confirming to IS 1554 (part 1) with necessary M.S. clamps. All such cables shall be provided with temporary labeling at every 20 mtr. & then finally with metal identification tags showing the size & the location from/to the specific panel/DB at both the ends. The cost shall include terminations of all the armoured cables using Siemens type single compression, chrome plated brass cable glands & crimp type tin copper lugs, Bimetallic lugs are to be provided wherever two different type conductors are present, Insulation tape etc. as required complete with earthing of glands.				
1	Aluminium Armoured Cables				
1	Aluminium Armoured Cables				

SOQ FOR ELECTRICAL WORK AT KISRUL BRANCH, (DP CODE- 1905)					
SR. NO.	ITEM	UNIT	QTY	RATE	AMOUNT
a.	4 C x 35 Sq.mm Aluminium AYFY Armoured Cables, <i>from MSEB Meter to Main Power DB</i>	Rmt	40.00		-
	Rate in words :-				
2	Copper Flexible Cables				
a.	3 C x 4 Sq.mm Copper Flexible Cables, <i>from UPS Output to UPS o/p DB to Main MCB near Entrance to Branch UPS DB & for Inverter. Also for the stabilizers.</i>	Rmt	50.00		-
	Rate in words :-				
b.	3 C x 6 Sq.mm Copper Flexible Cables, <i>for UPS Input from Main Power DB</i>	Rmt	45.00		-
	Rate in words :-				
d.	4C x 4 Sq.mm Copper Flexible Cables, <i>from Main DB to Main MCB near Entrance to Lighting DB</i>	Rmt	20.00		-
	Rate in words :-				
e.	4C x 6 Sq.mm Copper Flexible Cables, <i>from Mains DB to AC Main MCB near Entrance to AC Power DB .</i>	Rmt	25.00		-
	Rate in words :-				
f.	3 C x 2.5 sq.mm. Cu flexible cables, <i>for Signage</i>	Rmt	15.00		-
	Rate in words :-				
	B. TOTAL OF CABLES & TERMINATIONS				-
C	POINT WIRING				
1	POWER POINTS				
	SITC of following concealed Power Point Wiring using 1100V grade 3C x 2.5 sq.mm. PVC insulated, PVC Sheathed Colored flexible copper FRLS wire, laid through 20mm / 25mm size MMS Grade, PVC conduits. All cabling / conduiting below false ceiling shall be concealed. Each circuit feeding not more than 3 Tables / Work Stations). The rate shall include cabling including conduit cost from DB to mentioned Power Points. <i>(No seperate measurements for circuit wiring & PVC Conduits)</i>				
a.	Primary UPS points	No	8.00		-
	Rate in words :-				

SOQ FOR ELECTRICAL WORK AT KISRUL BRANCH, (DP CODE- 1905)					
SR. NO.	ITEM	UNIT	QTY	RATE	AMOUNT
	Supplying & Installing Primary UPS or Stabilized Power points on workstations / tables for computers using 3C x 2.5 Sq.mm PVC sheathed color flexible copper FRLS wires pulled through 25mm size MMS Grade PVC conduites , laid on surface above false ceiling and taken upto table top using 25/20 mm size MMS Grade PVC rigid or flexible conduits run within wooden or metal partitions.				
	Each point consisting of 2 Nos of 6A, 5 Pin Modular sockets and 1 No. of 6/16A, 6 pin socket controlled by 1 No 20A Modular switch , wired together forming one point. Earth wire to be of Green colour only. Switch should be above table top & sockets should be below table top				
	Only 3 tables served by one circuit from UPS DB. The Rate should be including the cost of Conduits, wires, Switch boards, internal looping wires, necessary Gang Box, PVC box, Modular Plates of other color, Modular Switches, Sockets, Compete Job with necessary screws, nylon plug, Saddles, hardware. Etc. All Switch Boards should be Properly numbered for identifications.				
	b. Secondary UPS points	No	8.00		-
	Rate in words :-				
	Supplying & Installing Secondary UPS or Stabilized Power points on workstations / table for computers using 3C x 2.5 Sq.mm PVC sheathed color flexible FRLS copper wires pulled through 25mm size MMS Grade PVC conduites, laid on surface above false ceiling and taken upto table top using 25/20 mm size MMS Grade PVC rigid or flexible conduits run within wooden or metal partitions.				
	Each point consisting of 3Nos of 10A, 5 Pin Modular sockets and 1 No. of 6/16A, 6 pin socket controlled by 1 No 20A Modular switch , wired together forming one point. Earth wire to be of Green colour only. Switch should be above table top & sockets should be below table top				

SOQ FOR ELECTRICAL WORK AT KISRUL BRANCH, (DP CODE- 1905)					
SR. NO.	ITEM	UNIT	QTY	RATE	AMOUNT
	for 2 table served by the same circuit from adjacent Primary point. The Rate should be including cost of wire, Switch board internal looping wires, necessary Gang Box, PVC box, Modular Plate of other color , Modular Switches, Sockets, Complete Job with necessary screws, nylon plug, Saddles, hardware. Etc. All Switch Boards should be Properly numbered for identifications.				
	c. Primary 10/20 A power points, for Printers / Pantry / Hot Plate / Water cooler etc	No	3.00		-
	Rate in words :-				
	Supplying & Installing Primary 10/20 A Power Socket points using 2 X 4.0 Sq.mm. + 1 X 1.0 Sq.mm. PVC insulated multistanded FRLS Grade flexible copper wires (with proper color code) pulled through haevy gauge PVC conduits.				
	Each point consisting of 1 Nos of 10/20 A Modular sockets controlled by 1 Nos of 20A Modular switch , wired together forming a point. Earth wire to be of Green colour only.				
	Only 2 Sockets served by one circuit taken from Raw Power & ACDB				
	d. Secondary 5/15 A power points, for Printers / Pantry / Hot Plate / Water cooler	No	2.00		-
	Rate in words :-				
	Supplying & Installing Secondary 10/20 A Power Socket points using 2 X 2.5 Sq.mm + 1 X 1.0 Sq.mm PVC insulated multistanded FRLS Grade flexible copper wires (with proper color code) pulled through haevy gauge PVC conduits.				
	Each point consisting of 1 Nos of 6/16 A Modular sockets controlled by 1 Nos of 20A Modular switch , wired together forming a point. Switch should be above table top & sockets should be below table top				
	The circuit should be taken from another Primary 15 A Power Socket Point only, whose circuit taken from Raw Power & ACDB				
2	LIGHT POINT WIRING				

SOQ FOR ELECTRICAL WORK AT KISRUL BRANCH, (DP CODE- 1905)					
SR. NO.	ITEM	UNIT	QTY	RATE	AMOUNT
	SITC of following concealed point wiring using 1100V grade 3C x 1.5 sq.mm. copper conductor PVC insulated FRLS wires (with proper R,Y,B colour code) pulled through 25mm / 20mm Size, MMS Grade PVC conduits. All wiring below false ceiling shall be concealed. The wires from ceiling junction to light points shall be drawn in flexible PVC conduit with adaptor & cover for junction box & crimp type lugs at both ends. Each circuit feeding not more than average 12 points (800 watts). The rate shall include circuit wiring (2C x 2.5 sq.mm. + 1C x 1.0 sq.mm.) from Lighting DB to switchboard and to the fixtures. (No seperate measurements for circuit wiring & PVC Conduits)				
a.	Primary Light points	No	20.00		-
	Rate in words :-				
	SITC 5A Primary light points including MS concealed box, grid plate, 6A switch & circuit wiring.				
b.	Primary Light points on Inverter	No	12.00		-
	Rate in words :-				
	SITC 5A Primary light points including MS concealed box, grid plate, 6A switch & circuit wiring.				
	(No seperate measurements for Inverter circuit wiring & PVC Conduits, as it's wiring costs needs to be considered in the Light Point wiring)				
c.	Secondary Light points	No	6.00		-
	Rate in words :-				
	SITC 5A Secondary light points looped from primary light point. All MCB controlled light points will be considered as secondary light points.				
c.	Primary 5 A socket points	No	2.00		-
	Rate in words :-				
	SITC Primary 5 A Socket points using circuit wiring (with proper color code) pulled through medium gauge PVC conduits.				
	Each point consisting of 1 Nos of 5 A sockets controlled by 1 Nos of 6A switch , wired together forming a point with Green colour Earth wire.				
d.	Secondary / Separate 5 A socket points (other than on Board plug points)	No	2.00		-

Name and Address of the Contrcator with Sign and Seal

SOQ FOR ELECTRICAL WORK AT KISRUL BRANCH, (DP CODE- 1905)					
SR. NO.	ITEM	UNIT	QTY	RATE	AMOUNT
	Rate in words :-				
	SITC Separate Secondary 5 A Socket points using circuit wiring (with proper color code) pulled through medium gauge PVC conduits. These points should be looped from the nearest Lighting Switch Board or from Primary 5A Socket Points.				
	Each point consisting of 1 Nos of 5 A sockets controlled by 1 Nos of 6A switch , wired together forming a point with Green colour Earth wire.				
e.	Primary 5 A socket points (on Board plug points)	No	12.00		-
	Rate in words :-				
	SITC Secondary 5 A Socket points using circuit wiring (with proper color code) pulled through heavy gauge PVC conduits. These points are installed on the Lighting Switch Board.				
	Each point consisting of 1 Nos of 5 A sockets controlled by 1 Nos of 6A switch , wired together forming a point. Earth wire to be of Green colour only.				
f.	Exhaust fan/Wall Fan points	No	10.00		-
	Rate in words :-				
	SITC of concealed point wiring for Exhaust fan and Wall fan using 1100V grade 3C x 1.5 sq.mm. copper conductor PVC insulated FRLS wires (with proper R,Y,B colour code) pulled through 25mm / 20mm Size, MMS Grade PVC conduits. All wiring below false ceiling shall be concealed. The wires from ceiling junction to fan points shall be drawn in flexible PVC conduit with adaptor & cover for junction box & crimp type lugs at both ends. The rate shall include circuit wiring (2C x 2.5 sq.mm. + 1C x 1.0 sq.mm.) from Lighting DB to switchboard and to the Exhaust fan and Wall fan. (No separate measurements for circuit wiring & PVC Conduits)				
	Each Exhaust Fan and wall fan will be operated on separate switch, Rate should be including the cost of 5 A switch, 4 way closed 5A connector & Mounting Plates				
g.	Ceiling fan points	No	5.00		-
	Rate in words :-				

SOQ FOR ELECTRICAL WORK AT KISRUL BRANCH, (DP CODE- 1905)					
SR. NO.	ITEM	UNIT	QTY	RATE	AMOUNT
	SITC Ceiling Fan point operated on seperate switch shall be Controlled by 2 Module, Step type Fan regulator, Rate should be including the cost of Fan hook, Suspending suitable fan rod, Connecting cord and Step type Fan Regulator				
h.	Bell points Including Bell	No	2.00		-
	Rate in words :-				
	SITC Bell point consisting of 5A Modular Bell switch & Suitable Bell, (Bell switch to be installed in Manager Cabin and in Strong room . The Sound of both the bells should be different)				
j.	Indicator Light points	No	4.00		-
	R-Y-B Indicator Light point from Main Power DB to Banking area, for indication of Mains power supply with wiring, indicator lamps etc., easily visible from the Exit / Entrance Door, so that the Last Person to leave the Branch / office should Turn OFF the Power Supply (MCB) Located in Power DB's to switch Off the Lighting, fans, AC's etc.				
	Each Indicator Light Point Wiring to be done with 3 X 1.5 Sq.mm. PVC insulated multistanded FRLS Grade flexible copper wires / 3 core 1.5 sq.mm flexible cable drawn through Heavy gauge PVC conduit from Respective DB Power to the Respective Colored Indicator Lamp.				
	Raw Power to be written / Identified on the respective DB with Red Colour				
	UPS Power to be written / Identified on the respective DB with Yellow Colour				
	Lighting Power to be written / Identified on the respective DB with Blue Colour				
	Inverter Power to be written / Identified on the respective DB with Green Colour				
	C. TOTAL OF POINT WIRING				-
D	FIXTURES				

SOQ FOR ELECTRICAL WORK AT KISRUL BRANCH, (DP CODE- 1905)					
SR. NO.	ITEM	UNIT	QTY	RATE	AMOUNT
	SITC of following concealed / surface mounted fixtures of makes as specified with all fixture accessories like suitable tubes/ bulbs/ ballast & internal wiring etc. The contractor has to assemble & install the said fixtures at position with necessary hardware required for installation like S-hook, chain link etc. as per requirement.				
1	LED tube lights 4'	No	9.00		-
	Rate in words :-				
	SITC 1200 mm Long Surface/Wall Mounted extruded Aluminium channels, with 20 w LED Tube light fixtures complete. Rate should be including the cost of Fixture, Suspending suitable rods, other accessories & hardware etc.				
	Model : BN021 LED25S 6500 PSU GR S1,				
	Make : Crompton Model : Linea LDLL20-CDL, LDLL20-WW				
	Make : Wipro, Model : Garnet D532065, D552065				
	Make : Havells Model : E-Lite LED Pride Pus LHEXBLP7PN1W020				
2	LED tube lights 2'	No	2.00		-
	Rate in words :-				
	SITC 600 mm Long Surface/Wall Mounted extruded Aluminium channels, with 10 w LED Tube light fixtures complete. Rate should be including the cost of Fixture, Suspending suitable rods, other accessories & hardware etc.				
3	15 w Down lighter with LED	No	10.00		-
	Rate in words :-				
	SITC 15 w White Powder Coated Housing LED Round / Square Down Lighter with High Efficiency LEDs & Ballasts				
	Make : Philips, Model : DN193B LED12S-6500 PSU WH S1				
	Make : Crompton, Model : Star Dura LSDRSD-18W-CDL/ NW/ WW,				
	Make : Wipro, Model : Garnet Wave D541565, Infinity Wave DG11565, DG12065				
	Make : Havells, Model : Fazer Neo LHEBMCP7IW1W015, LHEBMCP7IW1W020				
4	600 x 600 mm square LED panel fittings	No	17.00		-
	Rate in words :-				

SOQ FOR ELECTRICAL WORK AT KISRUL BRANCH, (DP CODE- 1905)					
SR. NO.	ITEM	UNIT	QTY	RATE	AMOUNT
	SITC 36 / 40 w LED Panel of 600mm X 600mm size, Square, Powder coated Recess mounting LED Light Fitting				
	Make: Philips, Model: RC380B G2 LED28S / RC140B G2 LED31S-6500 PSE OD WH				
	Make: Crompton, Model : LCTLR-36-CDL 36 w, LCPL-36-TL(2X2)				
	Make: Wipro, Model : Gartnet D424065, D414065 CRCO10R038HP57				

SOQ FOR ELECTRICAL WORK AT KISRUL BRANCH, (DP CODE- 1905)					
SR. NO.	ITEM	UNIT	QTY	RATE	AMOUNT
	Make : Havells, Model : Venus Neo PLR36WLED865PO, Plano PLR42WLED865S				
5	Fans				
	Supplying & Installing following mentioned Aluminum, medium duty, powder coated with glossy color Ceiling Fans / Wall Fans / Exhaust Fans with necessary clamps hook, bracket, hardware etc				
	a. SITC 1200 mm sweep Ceiling fans Complete with Mounting rod, Clamps, Locking pin etc. (Color -White / Ivory / Brown)	No	5.00		-
	Rate in words : -				
	b. SITC 250mm sweep Exhaust fan of metal body & blade on the outside	No	3.00		-
	Rate in words : -				
	c. SITC 400mm sweep Wall fan of 1350 RPM. Oscillating type, metal blades chrome plated guard with speed regulator and moisture proof treatment to winding and with 'E' class insulation.	No	6.00		-
	Rate in words : -				
	D. TOTAL OF FIXTURES				-
E	EARTHING SYSTEM				
1	Plate Earthing				
	S & I of Earthing Earth Electrode Station into the true ground level by earthing electrode material refer IS 3043-1987. The rod should be 50 mm diameter and 2 meter in length. The chemical earthing compound should be used.				
	a. Chemical earthing.Each one Dedicated Earthing for UPS, Raw Power and ATM	No	3.00		-
	Rate in words : -				
2	Earthing Wires				
	SITC of insulated copper earthing wire laid through 20 mm PVC conduits from separately made earth pit to the equipment in following sizes				
	c. Single core, 6 sqmm FRLS PVC insulated multi threaded, flexible copper wire laid through 20 mm size, MMS Grade PVC Conduites	Rmt	160.00		-
	Rate in words : -				

SOQ FOR ELECTRICAL WORK AT KISRUL BRANCH, (DP CODE- 1905)					
SR. NO.	ITEM	UNIT	QTY	RATE	AMOUNT
3	Main Earth Bus	No	2.00		-
	Supplying & Installing of Main bus for isolated earth comprising of 200mm x 40mm x 6mm thick copper bar fixed on insulated support and having 20 nos of holes and nut bolts studs for clamping the earth leads,all contained in MS/PVCbox of size 300mm x 200mm x 50mm deep and having transparent acrylic inspection cover as approved by Bank / Architect.				
	Rate in words :-				
	E. TOTAL OF EARTHING SYSTEM				-
F.	TELEPHONE / VOICE CABLING AND OUTLETS				
1	Telephone points compulsory	No	1.00		-
	Rate in words :-				
	Providing and laying 2 Pair Grey Color 0.5mm Tinned Cu , PVC insulated cable for Telephone / Voice, laid through 20 / 25 mm size, MMS Grade PVC Conduites and Supplying & terminating with RJ-11 Telephone Jack / Outlet with face plates in suitable modular PVC / MS box from EPABX / Krone Tag Box to the work stations and terminate the other on a 10 pair Krone module installed in a Krone Tag box, complete with numbering of each cable with Ferule and Telephone Connection Chart <i>(No seperate measurements for PVC Conduits)</i>				
	F. TOTAL OF TELEPHONE SYSTEM				-
G	DATA CABLING SYSTEM				
1	Data points	No	12.00		-
	Rate in words :-				
	Supplying and laying D-Link / Molex / Awaya / Amps make, Cat 6 cable for Data, laid through 20/25 mm size, MMS Grade PVC conduites and providing & terminating with RJ-45 Information Outlet Ports with face plates in suitable modular PVC / MS box from Server Rack/ Patch Panel/ Data Switch to individual work stations & terminating other end with RJ-45 connector including numbering with ferule <i>(No seperate measurements for PVC Conduits)</i>				
2	Supplying & laying Cat-6, RJ-45, 1 m. length Data Patch Cords,	No	12.00		-
	Make : D-Link / Molex / Awaya				

SOQ FOR ELECTRICAL WORK AT KISRUL BRANCH, (DP CODE- 1905)					
SR. NO.	ITEM	UNIT	QTY	RATE	AMOUNT
	Rate in words :-				
3	Supplying & laying Cat-6, RJ-45, 2 met length Data Patch Cords,	No	7.00		-
	Make : D-Link / Molex / Awaya				
	Rate in words :-				
4	Patch panel				
a.	Supplying and Installing D-Link make, preloaded, Cat-6, RJ-45, 16 Port Patch Panel, complete with terminations & numbering with ferule	No	1.00		-
	Rate in words :-				
5	Supplying & Installing D-Link / HCL / iBall make 12-U Networking Wall mounting rack , complete with following mentioned accessories	No	1.00		-
	* 2U Horizontal Cable Manager				
	* Power Distribution Unit / Power Strip of 6 Sockets				
	* Cooling Fans				
	* Cantilever Trays / Shelves				
	* Hardware Packet				
	Rate in words :-				
	G. TOTAL OF DATA CABLING SYSTEM				-
H	MISCELLANEOUS WORKS				
1	Temperory Lightning supply & data connectivity & Shifting of Network Rack				
1	Arranging temporary Power, data supply & Lighting & Fan fixation for all agencies and for staff PCs at work place . The rate shall include statutory aproval from Local MSEDCL / Electrical Inspectorate & other required satatutory bodies, preparation of AS-BUILT drawings, Testing of the installation & preparaition of test report as required by statutory bodies. Note: The rate to include cost of suitable temporary Lighting for all areas as per requirement during work.	Job	1.00		-
	H. TOTAL MISCELLANEOUS WORKS				-

SOQ FOR ELECTRICAL WORK AT KISRUL BRANCH, (DP CODE- 1905)					
SR. NO.	ITEM	UNIT	QTY	RATE	AMOUNT
J	BUY BACK of ITEMS Minimum Amount of Rs. 5,000/- + GST				
	The Lightning fixtures, Fans and other unused electrical fittings, wires etc under Buy back including Dismantling of old wiring,Data ,telephone, Fitting fixtures & DB's Etc and disposing away from the site. The minimum reserve price is Rs. 5,000/- + applicible GST.	No	-1.00		-
	TOTAL BUY BACK of ITEMS				-
	TOTAL FOR ELECTRICAL WORKS				-
	GST		CGST 9%		-
			SGST 9%		-
	GRAND TOTAL				-
			Say		-
	(Rs. only.)				