

**SOQ for Interior Furnishing Works at Shrigonda branch for Canara Bank**

**ABSTRACT SHEET**

S.No	Description	Qty.	Unit	Rate	Amount
<b>A</b>	<b>INTERIOR FURNISHING WORK</b>				
	<b>GENERAL NOTES: -</b>				
	<b>WOOD WORK:</b>				
	All internal woodwork / Plywood shall be treated with antitermite preservative. All internal framework shall be of Aluminium unless otherwise specified as Teakwood. All exposed edges of Plywood shall be fixed with C.P. Teak Lipping of size as directed by Architect. All Plywood shall be of MR GRADE IS 303 Commercial ply unless otherwise specified. The skinning shall be in 12 mm thk ply MR GRADE IS 303 unless otherwise specified. All exposed 1.0mm thk. laminate surfaces shall be finished. The thickness of the laminate shall be 1.00mm However no extra charges are payable for the additional thickness. The approved laminate shall be finished with bidding patti with polish finish where ever required.				
	Rate for high partition to include the cost of framework above false ceiling as required to fix the same to the ceiling slab. Measurement of Partition & Panelling shall be limited upto 6" above False ceiling & no separate payment shall be made for the work above 6". The item if executed for AC purpose shall be measured in the relevant item. <b><u>The partition shall be measured including the door &amp; the door frame &amp; no seperate payment for door shall be made.</u></b> The rate shall be all inclusive of the necessary hardware, fittings, fixtures, floor spring, door closers, hinges, handles (1 pair of 300mm long S. S. (H Shape)), locks for the door (Godrej or approved equivalent) & including glass & finishing for the same. The rate shall be also inclusive of pattas & bands including the necessary framing/ openings for Electrical, Telephone & AC outlets. The door should be provided as per the specifications provided. The amount for door needs to be included in the respective partition item.				
	<b>PARTITIONS / PANELLING</b>				
	General Specification for partition :-				
	Main frame -Aluminium sections of 16 Gauge mentioned are out of size 2"x2" Aluminium section verticals at minimum 2'-0" Centre-Centre spacing approx. and 2" X 1" size Aluminium sections horizontal at 2'-0" Centre-Centre spacing approx. Extra frame below slab soffit for conduit to run above. All verticals shall be secured to the ceiling.				
	SKIN: -12mm ply shall be screwed to frame work on both sides with joints as shown or directed.				
	SKIRTING : In the same alignment, 3" high in 12mm thk ply with a groove finished with laminate as the case maybe, or as directed by the Architect.				
	Finishing :-				
	LAMINATE:- Approved laminate shall be of 1.0 mm thick.				
	Laminate shall be fixed on plywood skins with glue having grooves as shown or directed. Internal surfaces at specified places shall be 1.0 mm thick as directed by Architect.				
<b>1</b>	<b>PARTITIONS</b>				
<b>(i)</b>	<b>FULL HEIGHT PARTITIONS (SOLID)</b>				

**SOQ for Interior Furnishing Works at Shrigonda branch for Canara Bank  
ABSTRACT SHEET**

S.No	Description	Qty.	Unit	Rate	Amount
	Providing and fixing Full ht.Both side laminate Partitions as per specifications including skirting, complete as per the drawings and instructions complete in all respects.				
	Main frame -2"x2" Aluminium section of 16 Gauge verticals at minimum 2'-0" Centre spacing approx and 2" X 2" size Aluminium sections horizontal at 2'-0" Centre spacing approx extra frame below slab soffit for conduit to run above. All verticals secured to ceiling.				
	Skin:- Both side with 12mm thk ply screwed to frame work on both sides with joints as shown or directed.				
	SKIRTING : In the same alignment, 3" high in 12mm thk ply with a groove finished with laminate as the case maybe, or as directed by the Architect.				
<b>a</b>	Finishing : <b>Both side Laminate</b> finished in 1.0 mm thk as shown in drawing or as directed by Architect.	85.00	Sft		0.00
<b>c</b>	<b>One side laminate and one side Calcium silicate board</b>				
	Same as above but with ply on one side of the main frame to be finished with 1.0mm thk approved laminate finish and the other side of the main frame to be finished with calcium silicate board, 12mm thk to be finished with approved acrylic emulsion paint as shown or directed by Architect including necessary grooves, skirting etc complete.	150.00	Sft		0.00
<b>d</b>	<b>One side laminate and one side ACP sheet</b>				
	Same as above but with ply on one side of the main frame to be finished with 1.0mm thk approved laminate finish and the other side of the main frame to be finished with ACP sheet as shown or directed by Architect including necessary grooves, skirting etc complete.	25.00	Sft		0.00
<b>2</b>	<b>FULL HEIGHT SEMI-GLAZED PARTITION</b>				
	Providing & Fixing full height Semi-Glazed partition with following specifications				
	Main frame - 2"x2" Aluminium section of 16 Gauge verticals, not exceed 2'-0" centres and 2" X 2" size Aluminium sections horizontal at floor level / skirting ht, 3'-0" level and door height at 7'-0" level.				
	Skin:- Both sides of the main frame shall be finished with 12mm thk ply screwed to the frame with joints as directed upto 3'0" level and from 7'0" level to the top upto false ceiling level and 3'0" level and from 7'0" top upto false ceiling level, also from 7'0" provide top upto 6mm thk. clear glass Straight / segmented with bevelled edges including frosted film of approved make & design and drawing to be fixed with t.w moulding all around of approved size & design including grooves, mouldings etc complete as directed by Architect & as shown in the drawing.				
	SKIRTING : In the same alignment, 3" high in 12mm thk ply with a groove finished with laminate as the case maybe, or as directed by the Architect.				
	Finishing : both side finished in 1.0mm thk approved laminate finished with polish as shown or directed by Architect.	315.00	Sft		0.00
<b>3</b>	<b>LOW HEIGHT PARTITION</b>				

**SOQ for Interior Furnishing Works at Shrigonda branch for Canara Bank  
ABSTRACT SHEET**

S.No	Description	Qty.	Unit	Rate	Amount
	Providing & Fixing <b>Low height Partition</b> of about height 4'-0" To 4'-6" height to be erected in 2" X 2" Aluminium section of 16 Gauge verticals, not exceeding 2' 0" centres and <b>2" X 2" size Aluminium sections</b> horizontal at floor level / skirting ht, intermediate level & 3'-0" level with 12mm. thk ply skin on both sides of the frame to be screwed to the frame with joints as directed, including 12mm glass with chamfered edges of 1'0" to 1'6" height, including approved frosted film of approved make & design on the glass including soft board panel & White board with felt cloth on one side of the partition. The ply skin to be finished with 1.0mm thk. approved laminate with t.w. beading all throughout the exposed edges & periphery including fixing the glass, sealing all the joints, grooves in laminate, polish to the mouldings & t.w members, complete as per the directions of Architect Note:-actual mesurment as per site.	255.00	Sft		0.00
<b>4</b>	<b>FULL HEIGHT FULLY GLAZED PARTITION INCLUDING DOOR</b>				
	Providing and fixing partition framing consisting of Heavy duty Aluminium Box Sections 50mm x 50mm @ 600mm c/c Horizontally and Vertically . The vertical alternate frames to be fixed to the ceiling with necessary fixtures. The framing shall be finished with 12 mm thk. ply on both side and finished with 1.00 mm thk. Laminate finish and beading patti around glass finished with polish. The shade of laminate and polishing finish to be got approved from Bank / Architect. Approved make 12mm thick toughened glass to be fixed from skirting level to 2100mm level ( in the top line of Door) The skirting should be as per approved laminate as per drawing and direction. Rate shall be inclusive of necessary hardware items, etc. Complete. The edge beadings with steam beach wood and finished with melamine.All damages to the floor work to be reinstated without any extra cost as per directions of Architect.(Toughened glass partition to be provided and will be measured upto 7' height and above that partition quantity will be considered in solid partition). <b>The rate is inclusive of door as per the specifications provide below. No additional payments for door will be made.</b>	155.00	Sft		0.00
	Fully glazed Door- Providing and fixing frameless fully glazed 12mm thk toughened glass door fixed with necessary patch fittings (Dorma or equivalent make) including cutting, making holes, cutouts in the glass of required shape and size to accommodate fittings and fixing the fittings in floors, soffits, jambs including necessary fixtures, screws, sealant wherever required and SS cover over patch fittings. Rate shall include necessary etching film / , approved patch fitting locking systems, 1 pair of 600mm long S. S. (H Shape) Handles of approved make, floor springs, and any necessary hardware items.( DORMA MAKE Top Pivot - PT 24, Top Patch Fittings - PT 20, Bottom Patch fittings - PT 10, Floor Spring - BTS 75 V, Corner lock with strike plate and Euro Profile Cylinder - US 10, Handle - TG DIH600 - 600mm length) complete as per the directions of Architect Note:-actual mesurment as per site.				
<b>5</b>	<b>PANELLING : -</b>				

**SOQ for Interior Furnishing Works at Shrigonda branch for Canara Bank**

**ABSTRACT SHEET**

S.No	Description	Qty.	Unit	Rate	Amount
a	Providing and fixing Wall & Column Panelling for the existing surfaces to be made out of 16 gauge Aluminium framework backing of size 2" X 1" at 1'6" to 2' c/c to be covered with 12mm thk ply and finished with approved 1.0 mm thk laminate including skirting & band at top in the same alignment with a groove of approved size as shown in detailed drawing or as directed by Architect	580.00	Sft		0.00
<b>b</b>	<b>ACP Plywood and Aluminium section including rolling shutter box (3 mm ACP thickness)</b>				
	Providing and fixing Wall & Column Panelling for the existing surfaces to be made out of 16 gauge Aluminium framework backing of size 2" X 1" at 1'6" to 2' c/c to be covered with 12mm thk ply and finished with approved interior grade ACP including skirting & band at top in the same alignment with a groove and including teakwood moulding of approved size including the necessary ply backing to match the level of other finishes such as 1.0mm thk. laminate in required areas as shown in detailed drawing or as directed by Architect. Whenever the item needs to be executed for Aluminium box section, the provision to be made for the servicing of the rolling shutter.	530.00	Sft		0.00
<b>c</b>	<b>ACP and Aluminium section (3 mm thickness)</b>				
	Providing and fixing Wall & Column Panelling for the existing surfaces to be made out of 16 gauge Aluminium framework backing of size 2" X 1" at 1'6" to 2' c/c and finished with approved interior grade ACP including skirting & band at top in the same alignment with a groove and including teakwood moulding of approved size including the necessary ply backing to match the level of other finishes such as 1.0mm thk. laminate in required areas as shown in detailed drawing or as directed by Architect	0.00	Sft		0.00
<b>e</b>	Providing & Fixing Soft Board panelling over framework of 25 mm x 18 mm T.W. Frame at 600 mm c/c with 6mm ply skinning on top & 12mm thk. soft board with fabric finishing over ply. Complete as per drawings & directions of the Competent Authority, 25 mm x 12 mm T. W. Moulding on edges (Basic Price of fabric Rs.250/- meter).	25.00	Sft		0.00
<b>6</b>	<b>FALSE CEILING WORK</b>				
	General :				
	The filler, paper tapes, finishes and primers suitable for Gypsum boards, shall be as per recommended practises of India Gypsum.				
	Framework grid and suspenders shall be fixed to avoid fouling with services such as ducting, sprinklers, electricals fixtures, etc				
	T.W. framing may be allowed in certain areas for the Gypsum Board ceiling with the approval of the Architect. The same should have three coats of fire resistant paint.				
	Note: All the hardware such as fastners, hangers, suspenders, etc. required for erection of the false ceiling shall be of INDIA GYPSUM make. And approved by the Architect.				
<b>a</b>	Metal frame <b>False Ceiling</b> of 12 mm thk. <b>Gypsum Board</b> including vertical drop panels.	540.00	Sft		0.00

**SOQ for Interior Furnishing Works at Shrigonda branch for Canara Bank**

**ABSTRACT SHEET**

S.No	Description	Qty.	Unit	Rate	Amount
	Providing and Fixing 12 mm Thk. Gypsum board on metallic grid, conforming to IS: 2095: :1982. The metallic grid shall consists of the following :				
	GI Perimeter channels of size 27mm and 0.5mm thk. having one flange of 20mm and another flange of 30mm.				
	GI intermediate channel of size 45mm 0.5mm thk. With two flange of 15mm each at 4'-0" centre to centre.				
	GI Hanger of size 1"x1", 0.5mm thk. A 4'-0" centre to centre distance.				
	GI Cleat and Steel Expansion Fasteners.				
	Ceiling section of 0.5mm thickness having curled wedge of 51.5 mm and two flanges of 26mm each with lips of 10.5mm at 450mm center to center. Connecting clips & 12.5 mm dry wall screws at 230 mm center to center.				
	The metallic grid shall be installed as follows :				
	The perimeter channel along the perimeter of the ceiling with screw fixed to brickwall / partition with the help of rawlplugs and screws.				
	The intermediate channels shall be suspended from the ceiling with steel GI hanger fixed to the slab soffit with GI cleat and steel expansion fasteners.The intermediate channels shall be at 4'-0" centre to centre distance.				
	The ceiling section placed in a direction perpendicular to the intermediate channel at 1'-6" C/C distance shall be fixed to the intermediate channel with the help of connecting clips and 12.5 mm dry wall screws at 230 mm centre to centre distance.				
	Finally, the 12mm thk. Gypsum boards shall be fixed to the metal frames and the tapered/square edges of the boards shall be finished to a flush joint with requisite filler, paper tapes, finisher and primer suitable for Gypsum plaster boards, (as per recommendations of manufacturers, Indian Gypsum or equivalent) <b><u>including 3 coats of Acrylic Emulsion Paint of approved make and shade and colour.</u></b>				
	The rate shall include the cut-outs to be made for light fittings, grills, diffusers, speakers, smoke detectors, sprinklers etc. with provision of the frame along perimeter of the cut outs/ opening with channels/ ply to support the ceiling adequately as per the directions of Architect. The rate shall include necessary shapes, designs, patterns in curvature, sloping, dome, oval& elliptical shaped etc including the necessary provisions of coved lighting scheme etc including finished complete as per the designs, drawings and instructions of the Architect.				
<b>b</b>	<b>Armstrong 2'x2'Grid Ceiling</b>	1,040.00	Sft		0.00

**SOQ for Interior Furnishing Works at Shrigonda branch for Canara Bank**

**ABSTRACT SHEET**

S.No	Description	Qty.	Unit	Rate	Amount
	Providing and fixing of Armstrong make Mineral fibre Ceiling Boards in true horizontal level suspended on inter locking Grid system made of Hot Dip Galvanized steel sections powder coated XL-15 mm as per manufacturers specification including Armstrong tiles 24"X24"laid on <u>Armstrong Silhouette profile grid system with 12 mm white flanges incorporating a 6mm central reveal in black as per design</u> as per manufacturers specification making opening for electrical and air conditioning fitting complete as directed. The tiles and grid system FRAMEWORK XL-15 mm Main Runner of 3000mm spaced at 1200mm center fixed to soffit by approved hangers at 1200mm distance.				
	First and last hanger should not be at a distance more than 450mm from the adjacent wall.XL-15 mm 1200mm cross Tee to be interlocked between Main Runner at 600mm center to form 1200x600mm module 600mmx600mm module to be formed by fixing XL-15mm 600mm Cross Tee between center of 1200mm Cross Tees.19X19 mm Wall Angle to be secured to wall at 450mm centers Suspension to be done by using 2mm pre-straightened GI wire using anchor fasteners.				
	All supported on 40x80mm horizontal MS pipe to reduce the double height portion as per instructions by Architect & Bank incharge. Make - Armstrong - ANS Micro & Supra fine XL frame work. Note: Where RCC Slab is old and concrete is weak, the GI suspended channel shall be fixed with epoxy chemical and necessary load test to be carried out before fixing Gypsum board fixing. Rate shall be inclusive of epoxy chemical and fixing of suspenders with chemical				
<b>7</b>	<b><u>TABLES</u></b>				
<b>a</b>	<b>Table for (B.M) ( 3'-0" Wide X 2'-6" High)</b>				
	Providing and supplying table for the BM to be made out of 19mm MR GRADE IS 303 Commercial ply d finished with approved 1.0mm thk. laminate with polish for the top &1.0 mm thk laminate for all other exposed areas. The top of the table to have t.w. moulding all around. The rate shall be inclusive of providing a keyboard tray on sliding telescopic channels & a pedestal drawer unit made out of 16mm thk ply on side with 2 nos of equal sized drawers on sliding channels & openable shutter below. The side credenza shall be on the other side & shall be paid for seperately in the relevant item.	13.00	RFT		0.00
	All internal surfaces to be finished in approved 0.8mm thk laminate. All the external surfaces shall be finished with 1.0mm thk. laminate with polish including the drawer unit. The table shall have 12 mm. thk clear glass on top with bevelled edges. The rate shall also keyboard trays as per the approved makes which shall be heavy duty. The necessary hardware such as automatic locking, ball catches, wire managers etc. to be provided as per the instructions of the Architect. The rate shall also include providing stand-alone foot rest to the table in the lnght of counter of projection width as directed to be finished with approved laminate etc complete for the entire length of the table. The Elevation of the table shall be as directed by Architect on site.				

**SOQ for Interior Furnishing Works at Shrigonda branch for Canara Bank  
ABSTRACT SHEET**

S.No	Description	Qty.	Unit	Rate	Amount
<b>b</b>	<b>WORK STATION SWO's &amp; CASH ( Nominal Size: 2'-6" Wide X2'-6" High )</b>				
	Providing and erecting in position linear work station as per the instructions and drawings to be made out of 19mm . BWR ( IS - 303 ) Plywood for work top and verticals finished with 1.0mm thk approved laminate externally for all the exposed surfaces & 0.8mm thk approved laminate internally. The top of the table to have t.w. moulding all around. The rate shall be inclusive of providing a keyboard tray on sliding channels & a drawer unit on side with 2 nos of equal sized drawers on channels with internal seperations in ply for keeping temporary cash & openable shutter below.	55.00	Rrft		0.00
	The side credenza however shall be paid for seperately in the relevant item. The rate shall be inclusive of CPU trolley of approved make, necessary fittings, fixtures, hardware such as channels, hinges, ball catches, automatic locking arrangment, wire managers, foot rest etc including providing the necessary openings for electrical/computer wiring complete as per the instructions of Architect. Elevation of the table shall be as directed by Architect on site.				
<b>c</b>	<b>Cash counter and Single Window counter with additional working Top: Description similar to item no a i) including additional Customer top couter at 4'0" high and 9" wide made of 19 mm thick plywood finished with 1 mm thick laminate. <u>The cashier should have additional drawers at left and Right sides as per the site requirement. The drawers should have the partitions inside.</u> The tray should be provided in the cashier partition. The side glass needs to be cut at the center so that the AC air will be circulated in the cash cabin.</b>	10.00	Rft		0.00
<b>8</b>	<b><u>PATTA &amp; BANDS:</u></b>				
	Providing and fixing 75mm wide Patta on the wall with 12mm Thk. BWR (IS-303) ply including 12 mm t.w beading with polishing etc complete as per the instructions.	40.00	Sft		0.00
	Finished in 1.0mm thk approved laminate.polish				
<b>9</b>	<b>Glass dividers fixed in wooden frame</b>	0.00	Sq.ft		0.00
	Providing & Erecting in position, bevelled Glass dividers out of 12mm thk glass between the two workstations admeasuring approx 2'-6" X 1'-6" to be placed in position by fixing in wooden frames with the D-brackets including edging of the glass, etching / frosted film etc complete				
<b>10</b>	<b>Counting Plank</b>	5.00	Rft		0.00
	Providing counting plank of 2 foot width and with drawers as per the specifications provided as per running counter.				
<b>11</b>	<b>12MM THK GLASS RAILING ABOVE CASH COUNTER</b>	30.00	Sq.ft		0.00
	Providing and fixing 12mm thick glass above counter fixed with D brackets to wall/partition.( slits and opening to be provided in the glass as per banks requirement)				

**SOQ for Interior Furnishing Works at Shrigonda branch for Canara Bank  
ABSTRACT SHEET**

S.No	Description	Qty.	Unit	Rate	Amount
12	<b>FRONT GLASS ABOVE WORKING COUNTER</b>	65.00	Sqft		0.00
	Providing and fixing 12mm thick, 2' 0" high glass of Tata / Modi / Saint Gobain make, matching with the counter shape with machine polished edges to be fixed with matt finished steel patch fittings as per design above counter fixed to wall/ side glass partition including 2" wide slits and 4-1/2" half round opening in the glass as per detail complete.				
13	<b>CENTER TABLE ( 2'-0" x3'-0" )- Design</b>	1.00	No.		0.00
	Providing and supplying in position center table to be made out of 2" x 2" t.w. frame with 12mm thk. clear glass top with bevelled edges and etching with polish etc. complete as instructed by Architect.				
14	<b>WRITING DESK</b>	1.00	No.		0.00
	Writing desk at entrance area in 19mm MR GRADE IS 303 Commercial ply and 1.00mm laminate finish surface 12 mm clear glass on top with shelves/partition (at 6 inches centre to center) in glass to keep slip books including acid etching / frosting of approved design and exposed edges in machine polished.and bank's printed brochures for public complete as per Architect's design and instructions. Size: 3'-0" x 1'-6" x 1 no.				
15	<b>Full Height Storage with shutters in two parts</b>	195.00	Sft		0.00
	Providing and fixing <b>Full height Storage</b> upto ceiling hight <b>or as per the site</b> and 1'-6" depth as specified in the drawings as per specification below.				
	Skeleton - made out of 19mm MR GRADE IS 303 Commercial ply at end verticals, top and bottom and verticals 450mm to 600mm Centres as shown in drawing and 6 mm thk back MR GRADE IS 303 Commercial ply				
	SHELVES - 19mm MR GRADE IS 303 Commercial Plywood top and edges finished in 0.8mm thk. Laminate to accommodate file height removable and supported on pins.				
	SHUTTERS-made out of 19mm MR GRADE IS 303 Commercial ply externally finished in 1.0mm thk. Laminate and Internally finished in 0.8 mm thk. Laminate as shown or directed. To be made in two parts.				
	HINGES - Each shutter shall have 100mm long oxidised brass butt hinges. Mimimum 4 nos. hinges for each of the shutter for Full height Storage and 3 Nos. hinges for each of the shutter for Low Height Storage to be provided.				
	BOLTS - Flush tower bolts from inside at top and bottom to the shutters and magnetic catch fixed top and bottom.				
	LOCKS - of approved make 4 -lever brass body dead lock with S.S. Key.				
	HANDLES - 100mm wide handles of c.p. brass as approved by the Architect.				
	SKIRTING -As instructed by Architect, in 18mm MR GRADE IS 303 Commercial plyfinished in Laminate.				
	BACK - Back side of storage to have 6mm thk. ply with laminate finish.				

**SOQ for Interior Furnishing Works at Shrigonda branch for Canara Bank  
ABSTRACT SHEET**

S.No	Description	Qty.	Unit	Rate	Amount
	Finishing :- All external surface finish with 1.00 mm thk Laminate. All the exposed woodsurfaces shall be finished in polish. In side visible surface complete with 0.8mm thk Laminate. Top to have tw moulding as instructed. All internal wood-work to have coat of anti termite of approved make before polishing. <b><u>The magnet lockes to be provided for all the shutters. The chain tobe provided for all the shutters.</u></b>				
<b>16</b>	<b>LOW HEIGHT STORAGE</b>	40.00	Sft		0.00
	Providing and fixing Low height Storage of ht. 4'-0" and depth of 18" or as specified in the drawings as per specification below.				
	Skeleton - made out of 19mm MR GRADE IS 303 Commercial ply at end verticals, top and bottom and verticals 450mm to 600mm Centres as shown in drawing and 6 mm thk back MR GRADE IS 303 Commercial ply				
	SHELVES - 19mm Thk. Plywood top and edges finished in 0.8mm thk. Laminate to accommodate file height removable and supported on pins.				
	SHUTTERS-made out of 19mm MR GRADE IS 303 Commercial ply externally finished in 1.0mm thk. Laminate and Internally finished in 0.8 mm thk. Laminate as shown or directed.				
	HINGES - Each shutter shall have 100mm long oxidised brass butt hinges. Mimimum 4 nos. hinges for each of the shutter for Full height Storage and 3 Nos. hinges for each of the shutter for Low Height Storage to be provided.				
	BOLTS - Flush tower bolts from inside at top and bottom to the shutters and magnetic catch fixed top and bottom.				
	LOCKS - of approved make 4 -lever brass body dead lock with S.S. Key.				
	HANDLES - 100mm wide handles of c.p. brass as approved by the Architect.				
	SKIRTING -As instructed by Architect, 18 plywood finished in Laminate.				
	BACK - Back side of storage to have 6mm thk. MR GRADE IS 303 Commercial ply.				
	Finishing :- All external surface finish with 1.0 mm thk Laminate. All the exposed woodsurfaces shall be finished in melamine polish. In side visible surface complete with 0.8mm thk Laminate. Top to have tw moulding as instructed. <b><u>The magnet lockes to be provided for all the shutters. The chain tobe provided for all the shutters.</u></b>				
<b>17</b>	<b>TABLE SIDE CREDENZA</b>	10.00	RFT		0.00

**SOQ for Interior Furnishing Works at Shrigonda branch for Canara Bank**

**ABSTRACT SHEET**

S.No	Description	Qty.	Unit	Rate	Amount
	Providing and erecting in position Credenza for the tables of 750mm height and 450mm deep or as instructed by the Architect to be made out of 19mm MR GRADE IS 303 Commercial ply & having t.w. moulding all round with 2 nos of drawers on top and openable or sliding shutters below. The openable shutters and shelves (to accommodate file height removable and supported on pins) to be made out of 19mm tk. MR GRADE IS 303 Commercial plyply with all internal surfaces to be finished in 0.8 mm thk approved laminate and externally with 1.0mm thk laminate including brass hinges, ball catches, 100mm brass handles, brass locks etc. complete as per the instruction of the Architect. Finished with approved laminate (1.0 mm externally & 0.8 mm internally)				
<b>18</b>	<b>WICKET GATE</b>	40.00	Sft		0.00
	P & F wicket gate wherever required with required SS hinges, SS tower bolts, magnet locks two numbers, and stoppers etc. Rubber wood capping made out of sect. 65 x 15 mm fixed at edges inclusive of natural polish / painting etc. complete as directed				
<b>19</b>	<b>ROLLER BLINDS</b>				
	The Duplex blinds (Zebra Blind) consisting best quality fabric with matching colour cassettes. The assembly shall be aesthetically made to match with room and shall be sleek, compact and fitted with best workmanship manner. The duplex blinds shall reduce glare and UV rays. This shall be maintenance free product only vacuuming required. Fabric shall have specialized properties such as fire retardant, no harmful VOC or hazardous substances will be released to the environment in quantities that are recognized as potentially dangerous to occupants of building. Duplex blinds (Zebra Blind) shall be manually operated. The basic operation shall involves a beaded chain, when pulled, fabric rolls neatly onto the roller tube, accumulating the fabric in one single linear tube.				
<b>a</b>	The fabric shall be selected from best quality fabric. The fabric shall have properties such as acoustic control, anti-fungal and anti-microbial. Sheer fabrics shall allow in maximum amount of light (20-100% light transmission), whilst still preserving privacy and Dimout (Privacy fabrics) (1 - 19% light transmission) allow in restricted amount of light, whilst ensuring complete privacy, even in the evening. Blackout fabric shall completely blocks out sunlight, for complete privacy, room darkening and temperature regulation (0% light transmission).				
<b>b</b>	<b>ROLLER BLINDS</b>	130.00	Sft.		0.00
	The fabric shall be of brown colour or equivalent as approved by NPCIL. The weighted composition of fabric shall be made of 100% Polyester woven fabric with a openness factor of 3%. The fabric shall have a weight of 168GSM (+5 GSM). The solid depth of fabric shall be 75mm and sheer depth shall be 50mm. Light fastness shall be 4-5 Grade tested in accordance with BS EN ISO 105- B01:1999.				
<b>20</b>	<b>NOTICE BOARD</b>	1.00	Nos.		0.00
	Providing and fixing notice board 4'-0" X 2'-0" to be made out of 19mm thk. ply with 3" deep with front glass shutter, 10mm thk. ply back covered with soft board and felt cloth including polishing locks etc. finished as per instruction of the Architect.				

**SOQ for Interior Furnishing Works at Shrigonda branch for Canara Bank  
ABSTRACT SHEET**

S.No	Description	Qty.	Unit	Rate	Amount
<b>21</b>	<b>WHITE BOARD</b>	1.00	Nos		0.00
	Providing and fixing White board with ceramic coating including soft board with fabric of approved shade and design complete as per the specifications and directions of the competent authority.size 3'-0"X 3'-0" 2 Nos.				
<b>22</b>	<b>PAINTING :</b>				
	<b>Note :</b> The Rates for the Painting works shall be inclusive of three coats. The paint should be free from lead and Arsenic.				
<b>a</b>	<b>Painting of wall</b>	590.00	Sft		0.00
	Painting of wall with minimum of 3 coats of Flat Oil Paint of approved shade & make on the rolling shutter and grill/ collapsible gate surface to apply paint. As per the directions / to the satisfaction of the Architect.				
<b>b</b>	<b>Acrylic Emulsion Paint</b>	3,915.0	Sft		0.00
	Providing and applying Acrylic Emulsion Paint in minimum of three coats of approved make and shade on Walls, Ceiling, plywood, gypsum board, surfaces etc including all the necessary surfaces preparation. The wall shall be cleaned, filled with putty & applied with one coat of primer so as to achieve a even surface to apply paint. As per the directions / to the satisfaction of the Architect.				
<b>23</b>	<b>CABINET FOR ELECTRIC PANEL:</b>	55.00	Sq.ft		0.00
	Providing, making and placing in position cabinet with openable shutter around the electric panel. Cabinet and shutter made of 18mm thick exterior grade MR commercial plywood All visible surfaces shall be laminated with 1.00 mm thick laminate on external surfaces of approved shades painting the internal surfaces with two or more coats of synthetic enamel paint including providing teakwood lipping of size 20 x 6 mm on edges. Horizontal slots (approx. 10 mm wide) to be cut in the shutter at top & bottom for ventilation. Rate to include for necessary hardware fixture like providing with 3 nos. of 75mm long SS hinges for each shutter, two nos of 75 mm tower bolt (one top and bottom), SS handles to shutters, magnetic catchers for each shutter and multipurpose Godrej or Ebco lock.				
<b>24</b>	<b>CHEQUE DROP BOX:</b>	1.00	No		0.00
	Providing and fixing Cheque drop box of size 1' 6"x1' 6"x 6" with all sides and back with 18mm thick MR grade comm. Ply wood and lockable shutters in 18mm ply with 5 mm glass . Top of the box to be provide with slot of size 6" x 1" wide for dropping cheques/ suggestions. All exposed areas and inside to be finished with 1 mm thick laminate of approved shade. The edges of shutter and box to be lipped with steam beach beading polished with melamine. Rate shall be inclusive of all necessary approved fittings like hinges, godrej cabinet lock or approved etc. and any necessary hardware items. The glass needs to be provided for the cheque drop box.				
<b>25</b>	<b>SUGGESTION BOX:</b>	1.00	No		0.00

**SOQ for Interior Furnishing Works at Shrigonda branch for Canara Bank**

**ABSTRACT SHEET**

<b>S.No</b>	<b>Description</b>	<b>Qty.</b>	<b>Unit</b>	<b>Rate</b>	<b>Amount</b>
	Providing and fixing suggestion box of size 1' 6"x1' 6"x 6" with all sides and back with 18mm thick comm. Ply wood and lockable glass shutters in 18mm ply , with 5 mm glass. All exposed areas and inside to be finished with 1 mm thick laminate of approved shade. The edges of shutter and box to be lipped with steam beach beading polished with melamine. Rate shall be inclusive of all necessary approved fittings like hinges, Godrej cabinet lock or approved equivalent, etc. and any necessary hardware items. The galss needs to be provided for the suggestion box.				
<b>26</b>	<b>GLASS SHELF</b>	10.00	sft		0.00
	Providing and fixing 12 mm thick polished edge glass shelf on D-Brackets				
<b>27</b>	<b>Push pull stickers</b>	10.00	No.		0.00
	Proving and fixing push pull stickers on the doors				
<b>28</b>	<b>Rearranging Items</b>	1.00	job		0.00

**SOQ for Interior Furnishing Works at Shrigonda branch for Canara Bank**

**ABSTRACT SHEET**

S.No	Description	Qty.	Unit	Rate	Amount
	Rearranging the existing counters in the branch premises till the new counters will be in the position. Rearranging the existing items like books,, racks, records etc. for making the partions, painting and iother activities required to finsh the work. After work completion items must be kept to its original position. During the paiting the sam needs to be rearranged.				
<b>29</b>	<b>L G Rubber Mat- 16 mm thickness</b>	12.00	Sq.Ft.		0.00
	Proving and fixing the Rubber mat approved make wherever required. 3X 3, 2 X2				
<b>30</b>	<b>sparkler frosted Film with logo</b>	70.00	Sq.Ft.		0.00
	Proving and fixing frosted film on the glass door for height of 3 foot or as per drawing provided by the Bank				
<b>31</b>	<b>Exhaust fan frame</b>	2.00	Nos.		0.00
	Proving and fixing exhaust fan frame mad up of 19 mm plywood nad provision to be made for exhaust fan. The rates are inclusive of all .				
<b>32</b>	<b>cover for Meter room box and Main switch</b>	15.00	sft		0.00
	The meter room box and main switch to be covered with the plywood, ACP. The glass to be provided as slit to take the reading. The rate is inclusive of all.				
<b>33</b>	<b>Mirror</b>	6.00	Sq.Ft.		-
	Providing and fixing Mirror ( Modiguard or Saint globain) 6mm thick of required size above wash basin. Mirror of approved make shall be fixed with 2" long S.S. Studs, 4 Nos. complete as directed.including frame work if necerrasy at any height with scaffolding etc complete.				
<b>34</b>	<b>PVC Tactile</b>	140.00	Sq.Ft.		-
	Providing and Fixing <b>PVC Tactile</b> Size of 300mmX600mm Installation With Adhesive backed etc complete as directed. Note Coloured, pattern etc will be approved by Architect Bank by considering basic rate for the tiles.				
<b>40</b>	<b>Loft shutters</b>	190.00	sft		-
	Providing and fixing 19 mm thk. Ply (MR grade IS 303) shutters with ply frame, skirting gap as shown in the drawing shall be maintained in case of counters. Division of shutters shall be made equally according to the length of the counter/loft.				
	Shutters shall be hinged to the framework and finished with 1.0 mm thk. Laminate of approved shade from outside, applied with approved shade of 0.8 mm thk. laminate from the inside and edges of shutters with T.W. lipping. Rate shall be inclusive of all necessary approved fittings like hinges, ball catch, handle, and any necessary hardware items.				
<b>41</b>	<b>Buy-back items ( Minimum Reserve price is Rs. 2,80,000/- + Applicable GST)</b>	-1.00	job		0.00

**SOQ for Interior Furnishing Works at Shrigonda branch for Canara Bank****ABSTRACT SHEET**

<b>S.No</b>	<b>Description</b>	<b>Qty.</b>	<b>Unit</b>	<b>Rate</b>	<b>Amount</b>
	Disposing all furnishing items like partitions, panellings, doors, false ceiling, furnitures, counters items etc. as permitted by the BM and as per project plan. The existing Steel tables, sofas should not be taken outside the branch. The contractor should not quote below the minimum reserve price. This price will be quoted as reserve price.				
<b>Total Interior Work</b>					<b>0.0</b>
<b>GST will be payable Extra by the Bank</b>					