

ARTCON DESIGN CONSULTANTS Architects, Engineers, Interior Designers Computer Aided Design					
Amit Kumar B.Arch, AIIA		G-04 ,Laxmi Palace ,Mitra Compound ,Boring Road, Patna - 1 Mobile: 9386717726, 9931723771 E-mail: - artcondesign@consultant.com amitkumar73@gmail.com Website:- artcondesignconsultant.com			
REF: AC/CB/0/ESTB.B./25-26					
<b>CONFIDENTIAL</b>			Date:-	4/5/2025	
<b>ESTIMATE OF CIVIL WORKS FOR CANARA BANK, BISCOMAUN BHAWAN PATNA , DIST:-PATNA, BIHAR.</b>					
<b>BRANCH</b>					
Sl. No.	DESCRIPTION	UNIT	QTY.	RATE	AMOUNT
1	Providing and laying in position cement concrete of specified grade exluding the cost of centring and shuttering-all work upto plinth level. 1:1.5:3(1 Cement: 1.5 coarse sand:3 graded stone aggregate 20 mm nominal size), Reinforcement for RCC work including straightening, cutting, bending, placing in position and bonding all complete.TMTC-500 12mm dia , And <b>TMTC-500 20mm dia top net complete</b> as per detail drg. & instructions of engg./ bank (Strong room =400.0SQFT)	C.FT.	1430.00		
2	VITRIFIED TILE FLOORING (bank approved Colour) Providing & Laying 2'-0" X 4'-0" X 8mm thick to 10mm thick Italian marble finish vitrified tiles of FIRST quality(ORIENT , SOMANY , KAJARIA) in approved colors to floor in required position fixed with bed of Cement Mortar (1:4) about 2" to 3" thick including 4mm thick to 5mm thick float of cement, filling the joints with neat matching color cement slurry, rubbing, washing etc. complete as per the instructions of Architect. Cost to be inclusive of taping on all the joints & covered the entire flooring with good quality plastic (300 microns) & POP above. Cover & Tape to be removed before final cleaning etc. complete as per detail drg. & instructions of Architect/ bank. (Basic Cost Of Vitrified Tile Not Less Then Rs.75/- Per SFT)	S.FT.	3300.00		
3	Demolishing brick work includingstackingof serviceablematerial and disposal of unserviceable material within 50 meters lead: Removing mortar form bricks and cleaning bricks including stackingwithina leadof 50m(stacksof cleanedbricksshall be measured):	LS	1		
4	Painting:- scratch the old paint surface and apply two layer of wall putty with primer and paint with plastic emulsion paint three coat over the wall putty of approved brand and manufacturer( Asian and Nerolac) of required colour to give smooth/silky look surface on wall,as per approved design and direction of the bank/Architect	SQ.FT.	4200.00		
<b>TOTAL BRANCH</b>					
<b>G.S.T(Extra as applicable)</b>					