

# **CANARA BANK**

## **INVITATION TO TENDER**

**ONLY FOR EMPANELLED CONTRACTORS**

**OF**

**CIRCLE OFFICE KOLKATA**

TENDER FROM ANY OTHER CONTRACTOR WILL BE SUMMARILY REJECTED

**INSTRUCTION TO BIDERS**

**AND**

**GENERAL CONDITIONS OF CONTRACT**

**FOR**

**FURNISHING WORKS**

**AT**

**CANARA BANK – RAMNAGAR BRANCH**

TENDER NO.: 117/25-26/BDS

**NAME OF THE CONTRACTOR:** .....

.....

**ADDRESS:** .....

.....

**SEAL & SIGNATURE OF TENDERER**

## **NOTICE INVITING THE TENDER**

To,

M/s .....

Sealed tenders on item rate basis are invited from panel Contractors for **Interior furnishing Works at premises of Ramnagar Branch.**

Tender Documents may be obtained at free of cost from the Premises & Estate Section, Circle Office Canara Bank, Kolkata during working hours from **17.11.2025** till **24.11.2025**.

**Earnest Money Deposit : NIL**

**Period of completion : 21 days**

**Last date, time and place for Submission of tender : On or before 3:00 pm, 24.11.2025 to  
The Assistant General Manager,  
General Administration Section  
Canara Bank, Circle Office  
Kolkata**

**Time and date of opening of tender : 3.30 pm on 24.11.2025**

The Bank will not be bound to accept the lowest tender and reserves the right to accept or reject any or all the tenders without assigning any reason whatsoever.

**Assistant General Manager  
Premises & Estate Section  
Canara Bank, Circle Office  
Kolkata**

.....

Date: 17.11.2025

SEAL & SIGNATURE OF TENDERER

## **GENERAL RULES & INSTRUCTIONS TO TENDERERS**

### **Name of the work: Furnishing Works to be carried out at premises of Ramnagar Branch & ATM**

The rates quoted shall also be inclusive of materials, labour charges, work contract tax, surcharge and all the taxes except GST.

**GST WILL BE PAID EXTRA.**

The rates quoted by the tenderer shall hold good till the completion of the work from the date of issue of the "WORK ORDER" and no enhancement in the rates are allowed during the period of execution of the work under any circumstances. The rates quoted shall also cover for the work to be executed before and after office hours and also on holidays.

The time stipulated for the completion of the work is 20 days from the date of issue of the WORK ORDER and the work is to be carried out as per the convenience of occupants without disturbing other occupants of the building.

### **TENDERS:**

The entire set of tender paper issued to the tenderer should be submitted fully priced and also signed on the last page together with initials on every page. Initials / signatures will indicate the acceptance of tender papers by the tenderers.

The schedule of quantities shall be filled in as follows:

- The "rate" column to be legibly filled in ink in both English figures and words.
- 'Amount' column to be filled in for each item and the amount for each sub-head as detailed in the "schedule of quantities".
- All corrections to be initialed.
- The "Rate" column for all the items shall be filled up.
- The "Amount" column for the items for which the quantities are not mentioned shall not be filled up.
- In case of any errors / omissions in the quoted rates, the rates mentioned in the tender in words shall be taken as correct rates.

No modifications, over-writings or corrections can be made in the tender papers by the tenderer, but may at his option offer his comment or modifications in a separate sheet of paper attached to the original tender papers.

The Bank reserves the right to reject the lowest or any tender or all of the tenders for each section or to split up and distribute any item of work to any specialist firm or firms, without assigning any reason.

The tenderers should note that tender is strictly on the item rate basis and their attention is drawn to the fact that the rates for each and every item should be correct, workable and self – supporting. If called upon by the bank, detailed analysis of any or all the rates shall be submitted. The architects/bank shall not be bound to accept the contractor's analysis.

The Quantity mentioned in the BOQ is approximate measurements. The works will be paid for as "measured work" on the basis of actual work done and not as "lump sum" contract.

All the items of work described in the schedule of quantities are to be deemed and paid as complete works in all respects and details including preparatory and finishing works involved, directly, related to and reasonably detectable from the drawings, specifications and schedule of quantities and no further extra charges will be allowed in this connection. In the case of lump-sum charges in the tender in respect of an item of works, the payment of such items of work will be made for the actual work done on the basis of lump-sum charges as assessed to be payable by the architects/bank.

SEAL & SIGNATURE OF TENDERER

The bank has power to add or delete any work or described in specifications or included in schedule of quantities and intimates the same in writing but no addition, omissions or variation shall be made by the contractor without authorization from the bank. No variation shall vitiate the contract. The bank reserves the right to delete any of the items in the tender without assigning any reasons whatsoever.

The tenderer shall note that his tender shall remain open for consideration for a period of 90 days from the date of opening of tender.

#### **AGREEMENT**

The successful contractor is required to sign agreement as may be drawn up to suit the local conditions and shall pay for all the stamps and legal expenses incidental thereto. The original will be kept with the Bank and duplicate with contractor.

#### **EARNEST MONEY AND SECURITY DEPOSIT:**

There is NO Earnest Money Required to deposit/ submit along with the bids. Retention Money shall be deducted from the final bill at 5% of the gross value of bill. The Retention amount will be refunded to the contractor 15 days after the end of defects liability period provided he has satisfactorily carried out all the work and attended to the entire defect in accordance with the condition of the contract. No interest is allowed on Retention Money.

A part of the Security Deposit if and as decided by the constituent bank can also be furnished in the form of a Bank Guarantee on the bank other than that of the constituent bank.

#### **CONTRACTOR TO PROVIDE EVERYTHING NECESSARY:**

The contractor shall provide everything necessary for the proper execution of the work according to the intent and meaning of the drawings, schedule of the quantities and specifications taken together weather the same may or may not be particularly shown or described therein provided that the same can reasonably be inferred there from and if the contractor finds any discrepancies therein he shall immediately and in writing, refer the same to the Architects/Bank whose decision shall be final and binding.

The rates quoted against individual items will be inclusive of everything necessary to complete the said items of works within the contemplation of the contract, and beyond the unit price. No extra payments will be allowed for incidental or contingent labour and/or materials inclusive of all taxes and duties whatsoever except for specific items, if any, stipulated in tender documents

The contractor shall supply, fix and maintain at his own cost, for the execution of any work, all tools, tackles, machineries and equipment and all necessary scaffolding, staging and lighting by night as well as by day required not only for proper execution and protection of the said work.

The contractor shall take down and remove any or all such scaffoldings as occasion shall be required or when ordered to do so, and shall fully reinstate and make good all matters and things disturbed during the execution of work to the satisfaction of architect/bank.

The contractor shall all times give access to workers employed by the bank or any men employed at site and to provide such parties with proper sufficient and if required, special scaffolding and ladder and provide them lighting as may be required to enable such workmen to inspect the work, lay or fix pipes, Civil & furnishing wiring, special fittings etc. The quoted rates of tenderers shall accordingly include all these above-mentioned contingent works.

#### **LIQUIDATED DAMAGES:**

Should the work be not completed to the satisfaction of bank within the stipulated period, the contractor shall be bound pay the bank a sum calculated as given below by way of Liquidated Damages after the expiry of completion date

**.1.00% of the estimated amount shown in the tender per week subject to a ceiling of 10% of the accepted contract sum.**

<b>TIME PERIOD FOR COMPLETION: 20 days from the date of award of work.</b>
--

SEAL & SIGNATURE OF TENDERER

### **FINAL PAYMENTS**

The final bill shall be accompanied by a certificate of completion from the Occupant/Bank Officials. Payments of the final bill shall be made after deduction of retention money as specified in clause 9 of these conditions which sums shall be refunded after the completion of the defects liability period after receiving the banks certificate that the contractor has rectified all defects to the satisfaction of the banks. The acceptance of payments of the final bill by the contractor would indicate that he would have no further claims in respect of the work executed.

### **ESCALATION:**

The rates quoted shall be firm throughout the tenure of the contract [including extension of time, if any granted] and will not be subject to any fluctuation due to increase in cost of materials, labour, sales tax, octroi etc, unless specifically provided in these documents.

### **CONTRACTORS EMPLOYEES:**

The contractor shall employ technically qualify and competent supervisors for the work who shall be available [by turn] throughout the working hours to receive and comply with the instructions of the bank officials. The contractor shall engage at least one experienced engineer, as site in-charge for the execution of the work the contractor shall employ in connection with the work persons having appropriate skill or ability to perform their job efficiently. The contractor shall employ local labours on the work as far as possible. No laborers below age of 16 and who is not an Indian national shall be employed on the work. Any laborers supplied by the contractor to be engaged on the work on day-work basis either wholly or partly under the direct order or control of bank or its representative shall be deemed to a person employed by the contractor.

The contractor shall comply with provision of all labour legislation including the requirements of

- a. Payments of minimum wages act
- b. Employers liabilities
- c. Workmen's compensation act
- d. Contract labour (regulation and abolition) act, 1970 and central rules 1971
- e. Apprentices act 1961
- f. Any other act or enactment relating thereto and rules framed there under from time to time

The contractor shall keep the bank saved harmless and indemnified against claims if any of the workmen and all costs and expenses as may be incurred by the bank in connection with any claim that may be made by any workmen.

The contractor shall comply at his own cost with the order of requirement of any health officer of state or any local authority or of the bank regarding the maintenance of proper environmental sanitary condition of the area.

The contractor shall arrange to provide first aid treatment to the laborers engaged on the works. He shall within 24 hrs of occurrence of any accident at or about the site or in connection with execution of work, report such accidents to the bank and also the competent authority where such report is required by law.

The contractor shall obtain all Risk Insurance Policy at their cost within 7 days of commencement of work, for the laborers/workmen working at the site including the work till the work is completed. The policy shall be in the joint name of the Bank and contractor and Bank's name shall appear First.

### **PAYMENTS:**

The contractor, in the form prescribed by the bank shall prepare all the bills and submit the same to Bank with measurement of work. Normally one interim bill shall be prepared each month. Bank may release payment within 15 days of receipt of bills/after check measurement, after deduction of retention money, Income Tax etc. The contractor shall have a competent engineer at site for the supervision of the work.

The contractor shall have to make his own arrangements for watch and ward of the work/building, till the work is handed over to the bank.

The decision of the bank will be final and binding with regard to the quality of work is concerned.

SEAL & SIGNATURE OF TENDERER

The contractor is responsible for procuring the required materials for the work and stores the same at site at his cost and risk.

The amount stated in the interim certificate shall be the 75% of total value of the work executed up to date of the bill, less the amount to be retained by the bank as retention money. If the bank has supplied any materials or goods to the contractors, the cost of such materials will be progressively deducted from the amount due to the contractor on accordance with the quantities consumed in the work. All the interim payments shall be regarded as payments by way of advance against the final payment only and not as payments for works actually done and completed and shall not preclude the requiring of bad, unsound or imperfect or unskilled work to be removed and taken away and reconstructed or re-erected or be considered as an admission of the due performance of the contract or any part there of if any respect or accruing of any claim nor shall it conclude, determine of effect in any way the power if the bank under conditions or any of them add to the final settlement and adjustment of the accounts or otherwise or in any other way or affect the contract.

The contractor shall submit the final bill within one month from the date of completion of the work. A certificate of completion from the bank shall accompany the final bill. The payment of the final bill shall be made after deduction of retention money as specified elsewhere in these documents.

#### **ARBITRATION:**

All disputes or differences of any kind whatsoever which shall at any time arise between the parties here to touching or concerning the works or the execution or maintenance thereof of this contract or the rights touching or concerning the works or the execution of maintenance thereof of this contractor or the construction remaining operation or effect thereof or to the rights or liabilities of the parties are arising out of or in relation thereto whether during or after determination foreclosure or branch of the contract[other than those in respect of which the decision of any person is by the contract expressed to be final and binding] shall after written notice by either party to the contract to the other of them and to the employer hereinafter mention to deal referred for adjudication to a sour arbitrator to be appointed as hereinafter provided.

For the purpose of appointing the sole arbitrator referred to above, the employer will send within 30 days of receipt of the notice, to the contractor a panel of 3 names of persons who shall be presently unconnected with the organization for which the work is executed.

The contractor shall on receipt of the names as aforesaid, select, anyone of the person's name to be appointed as a sole arbitrator and communicate his name to the employer within 30 days of the receipt of the names. The employer shall thereupon without any delay appoint the person as the sole arbitrator. If the contractor fails to communicate such selection as provided above within the period specified, the competent authority shall make the selection and appoint the selected person as the sole arbitrator.

If the employer fails to send to the contractor the panel of 3 names as a foresaid within the period specified, the contractor shall send to the employer a panel of 3 names of persons who shall be unconnected with either party. The employer shall on receipt of the name as a foresaid select anyone of the person's names and appoint him sole arbitrator. If the employer fails to select the person and appoint him as a sole arbitrator within 30 days of the receipt of the panel and inform the contractor accordingly, the contractor shall be entitled to appoint one of the persons from the panel as the sole arbitrator and communicate his name to the employer.

If the arbitrator as appointed is unable or unwilling to act or resigns his appointment or vacates his office due to any reason whatsoever another sole arbitrator shall be appointed as aforesaid.

The work under contract shall, however, continue during arbitration proceedings and payment due or payable to the contractor shall be withheld on account of such proceedings.

SEAL & SIGNATURE OF TENDERER

The arbitrator shall be deemed to have entered on the reference the data he issued notice to both the parties fixing the date of the first hearing.

The arbitrator may from time to time, with the consent of parties, enlarge the time or making and publishing the award.

The arbitrator shall give a separate award of each disputes or difference referred to him. The arbitrator shall decide each dispute in accordance with the terms of the contract and give a reasonable award. The venue of arbitration shall be such place as may be fixed by the arbitrator in his sole discretion.

The fee, if any, of the arbitrator shall, if required to be paid before the award is made and published, be half and half by each of the parties. The cost of the reference and of the award including the fees, if any, of the arbitrator who may direct to and by whom and in what manner, such costs or any part thereof shall be paid and may fix or settle the amount of costs to be so paid.

The award of the arbitrator shall be final and binding on both the parties.

Subject to aforesaid the provision of the arbitration act 1940 or any statutory modification or re-enactment thereof and the rules made there under, and for the time being in force, shall apply to the arbitration proceeding under this clause.

The employer and the contractor hereby also agree that arbitration under the clause shall be a condition precedent to action under the contract with regard to the matters hereby expressly agreed to be so referred to arbitration.

**Date:**

**Signature of the Contractor  
With seal and address**

SCHEDULE OF INTERIOR FURNISHING WORKS AT RAMNAGAR BRANCH					
SI	PARTICULARS	QTY	UNIT	RATE (Rs.)	AMOUNT (Rs.)
1.	FALSE CEILING (Gypsum board and 2'x2' grid ceiling)				
a	FALSE CEILING (GYPSUM BOARD) : Providing & Fixing gypsum board false ceiling system in 2 steps / In combination the grid ceiling Armstrong tiles ceiling vertical profile using 12.5mm gypsum plaster board on G.I.metal frame work. The frame work made up of perimeter channels of 20 x 27 x 30 x 3657mm fixed on wall & partitions and ceiling sections of 80 x 26 x 0.5x 3657mm as a cross member provided at 457mm c/c and the intermediate channel of 15x 45x.09 x 3657mm as a main runner at 1220mm c/c suspended by means of G.I.angle 25 x 25 x .05 mm from the existing ceiling by means of M.S. rawl plug with bolts/screws at 1200 mm c/c max. The joints of gypsum board to be taped 3 times and sealed with jointing compound. Finished with one coat of primer and min 3 coats colour or matching spectrum colour complete as per detail and specifications in drawing incl. all lights, diffuser cuttings complete.	340	sft		
b	Drop ceiling	48	sft		
c	FALSE CEILING (GRID) : Providing & fixing Grid false ceiling (Armstrong ) with 12mm thick mineral fibre acoustic tiles with crisp finely granulated surface in bright colour Prima regular Fine Fissured RH 99 with Armstrong TL 24mm exposed grid Tee section, exposed face shall be powder coated (white), main runner shall be Tee-shape section with single rotary stitching of size 24 x 38mm , 3.6m long with cross runner of tee shape section with single rotary stitching of size 24x30mm @1.2m with 24 x 25mm runner @ 0.60m c/c, with Armstornng suspenders, perimeter channel of size 22 x 22mm (white) all complete in all respect as per manufacturer's specifications.	500	sft		
2 .	PARTITION				

SEAL & SIGNATURE OF TENDERER

	<p>Providing and fixing partition in position as per design with 2"x 1.5"sal wood finished section frame work @ 2'-0" c/c both ways screwed to the floor and ceiling with M.S. Cleats and to be treated with anti termite oil. The frame work will be cladded with 6 mm thk. BWP and termiteproof plywood both side and to be finished with approved 1.0 mm laminate (with vertical grain and groove in between the laminate portion) as per design with approved band adhesive, extra frame work to be fixed for fixing glass. In the glazed partition 10 mm thk. Modiguard/Saint Gobain clear float glass with film sheet on top to be provided, duly fixed with white beach/white ceader lipping 50 mm x 25 mm all complete duly reddish brown/ rose wood colour polish with melamine finish or stainless steel glass clips on both sides of the wooden support to fix up the glasses . The work should be completed as per specification, design &amp; approval of the Architect. For the door 32 mm solid core bwp Flush door with a frame work of white beach/ white ceader size 75 mm x 62.5 mm with necessary hold fast fixed to the wall/partition, finished with 1.0 mm laminate and lipping in all sides and 1.5" x 1.5" white beach/ white ceader wooden moulding to be provided along the periphery of the door frame. supplying and fixing door accessories as door closure, brass hinges, Cylindrical / Night latch locks and s.s handle. Laminated skirting of 4" ht. as per approved colour to be placed all around the partition as per direction and colour code of CANARA BANK</p>				
2.A.	Partly glazed partition				
a	PARTLY GLAZED PARTITION upto 4' ht	70	sft		
b	PARTLY GLAZED PARTITION upto 8'-6" with 7' ht. door for CASH CABINS and MANAGER'S ROOM ,	450	sft		
c	BLOCK PARTITION --- upto ceiling ht ./ sofit of beam and the side portion of main entrance, including the ceiling	440	sft		
d	10 mm th.. TOUGHEND GLASS at cash counter at front with 3"dia central gap for communication and 2.5" gap throughout at the bottom of the glass . And at the front of all open counters upto 1'-0" ht.	12	sft		
3 .	Main Entrance Door				
	Providing and fixing glass door -2 way - 5' x 7'-1 no for main entrance. .A white beach wood	35	sft		

	frame size- 6" x 2" as top and bottom rail with a decorative handle of 600 mm of approved brand, floor spring , locks, etc all complete. 12 mm thk. toughened glass with glass films on top as directed and CANARA BANK logo to be provided and edge should be machine beveled polished. The work to be completed as per design and specification of the architect all complete. the wooden portion to be duly melamine polished.				
	TABLE				
4	Providing and fixing tables made out of 18 mmth. blockboard of approved make cladded with 1.0mm laminate (color with vertical grain ) as per design in all visible areas. All the exposed edges to be covered with wooden lippings and mouldings to be reddish brown or rosewood colour polish with melamine finish. The drawers are to be made out of 18 mm thk. plywood duly 1.0 thk. laminated in the front, sides to be made out of 18 mm blockboard and bottom to be made out of 6 mm BWP and termiteproof plywood and it should play in drawer telescopic sliding channels. The inside of the drawer and the table to be duly polished. A legrest to be provided duly polished made out of 18mm thk.blockboard. A shutter to be made by 18mm th. blockboard cladded with 1.0mm laminate. The necessary locks handles to be provided in each drawers and shutters. The table should have wooden key board tray and ups trolley. The necessary wire managers to be provided on the tables and provision for lights to be kept in the front of the table. CPU to be fixed with the table at the bottom and it should not be placed on the floor or on the trolley.The work to be completed as per design and approval of the Architect. 12 mm th. clear glass on top of branch manager table .100 mm skirting of approved colour code to be fixed at 750mm level below the table top and at the bottom of the table as per direction of Architect.				
a	Manager ---6'-0" x 3'-0" ---1 no.	18	sft		
b	Officer -- 5'-0" x 2'-6" -- 2 no	25	sft		
5 .	Cash / Open Counter				
	Providing and fixing top, front & side of cash counter made out of 18 mm BWP and termite proof blockboard as per design cladded with 1.0	10.75	rft		

	<p>mm thk. Laminated on side and front &amp; the edges to be finished with necessary white beach or white ceader lippings, mouldings, etc. Special 6" drawer to be made for the cash with dividers of 12 mm plywood. the front of the drawer made out of 18mm blockboard finished with 1.0 mm laminate, sides 12 mm th. plywood and bottom to be made of 6 mm plywood. the inside and sides of the drawer to be duly polished. The drawers and shutters to be provided with necessary drawer sliding channels, hinges, locks etc. A leg rest to be provided made out of 18 mm thk. blockboard duly polished. Inside of the unit to be polished in the matching tone. All visible areas to be covered with beach or ceader lippings, mouldings with reddish brown colour polish. Wire manager, CPU trolley, keyboard tray to be provided. 4" ht. laminated skirting to be provided in all visible ares and 12 mm thk. x 18" wide Plain Glass to be provided at counter top customer face horizontally at 3'-10" lvl. The work should be completed as per specification. Cash counter --- 10.75 rft x 3' width Open counter - - 9.00 rft x 2'-6" width (spec. same as above).</p>	9	rft		
6 .	Side Units : Low ht. Cabinet				
	<p>Providing and fixing Side Unit/Back Unit made out of 18 mm th. blockboard finished with 1.0mm laminate in all exposed areas. The drawers to be made out of 18 mm blockboard in the front cladded with 1.0 mm laminate, side to be made out of 12 mm plywood and bottom made out of 6mm plywood duly painted in matching tone and it should play on drawer sliding channels. The shutters to be made out of 18mm blockboard and should play on drawer sliding castors on powder coated channels. The necessary locks, handles, etc to be provided. 4" laminated skirting to be provided all along the visible areas. Inside of the unit to be enamel painted in matching tone. All the exposed edges of the boards/plywoods to be covered with wooden lippings/mouldings duly polished all complete. The work to be completed as per approval and specification of the Architect.</p> <p>low ht. . cabinet -- ( 17'+ 9'+ 6'+ 5' ) x 3'-6" ht. + low ht. cabinet --- ( 3' x 3 nos ) x 2'-6" ht. + full ht. cabinet -- ( 10' + 6' ) x 8'-0" ht Electrical panel board --- 3' x 4' ht</p>	292	sft		

7 .	Standing Writing Ledge				
	Providing and fixing writing ledge with 10" wide as per design made out 18mm blockboard with necessary groove patterns 1.0mm laminate (color, vertical grain ) to be cladded. 12 mm thk. machine polished glass to be provided on top of the writing ledge. Small boxes to be made out of 18 mm th. blockboard to be made on top of the writing ledge finished with 1.0 mm laminate , inside enamel painted. The ledge finished with 1.0mm laminate, inside enamel painted. The work to be completed as per design and approval of the Architect. - 5 ' x 1 no.	5	rft		
8	Venetian Blinds				
	Providing and fixing venetian blinds of approved shade. The rate shall include necessary scoch guard treatment on both side. The work to be completed as par specification and approval of the Architect.	120	sft		
9	Synthetic Door Mat				
	Providing and fixing synthetic door mat 6 mm thk. As per approval of the Architect.	6	sft		
10	Notice board				
	Providing and fixing soft board with necessary frame work with 12 mm bwr plywood on top jolly board to be fixed finished with fabric @ Rs. 100, with necessary moulding duly polished along the periphery.	24	sft		
11	Complain and Cheque drop box				
	Providing & fixing Sal wood frame, fixing of 12 mm plywood with 1 mm thk. laminate finish, openable shutter for outside area. 8"wide x 18" length x 15"ht x 2 nos	4	sft		
12	FIREPROOF PARTITION FOR UPS ROOM				
	Providing and fixing partition with aluminium frame of section 50 mm x25mm x1.5mm with a grid of 600 mm x 600 mm. The frames are to be filled up with 12 mm th. Cement boards ( EVEREST / CHARMINAR / BISAKA ) to be fixed on both sides and screwed to the frame . All exposed surfaces to be finished with putty, primer and two or more coats acrylic emulsion paint.The Aluminium channels are to be fixed on the floor and screws rigidly as per instruction.The grid shall be framed using suitable screws, angle sections . This work to	102	sft		

	be done for UPS room . Rate to include supply and fixing the door also with all necessary hardware fittings and fixtures as per site dimension.				
13	Wall panelling -- upto 4' ht.				
	Providing and fixing wall paneling for Branch , upto 4' ht. as per design with 2" x 1.5" sal wood frame work fixed to the column and wall. The frame work will be clad with 6 mm thk. BWP and termite proof plywood and to be finished with approved 1.0 mm laminate as per design with approved brand adhesive .	300	sft		
14	Dismantling the present set up of the branch , as this is a running branch	L.S			
	ATM				
15	Front wall Aluminium Frame fully glazed Main Door	80	sft		
	Providing and fixing Aluminium frame with 12mm glass at the front wall comprising of appropriate 83.5 mm vertical members, approximate 85-90 mm top & bottom , approximate 83.5mm middle member, Black powder coated. . 6 mm clear polycarbonate sheet with scratch free film on both sides. Wool pile / Weather strip on one vertical member. Overall area of front wall is 80 Sq.Ft .The job also includes dismantling the present set up consisting of one glass door and rest portion fixed glass embedded into aluminium frame.				
16	ACP sheet for Rolling Shutter hood and side channels:				
	Providing and fixing ACP sheet on rolling shutter cover hood and the side channels , of approved colour as per colour code of the bank .	70	SFT		
17	FALSE CEILING ( 2' x 2' grid ceiling )	60	SFT		
	Providing and fixing combination of grid false ceiling -2 ' x 2' (Armstrong or equivalent) with 12mm thick mineral fibre acoustic tiles with crisp.				
18	PAINTING WORK	80	SFT		
	Supplying, applying putty , scrapping the surface and supplying and applying one coat of oil bound primer and two coats of Oil paint on the walls ,including all labour charges, for the UPS room.				
19	NOTICE BOARD				

	Supplying, fitting and fixing notice board of frameless double acrylic transparent sheet -2' x2'	4	SFT		
20	Supplying and laying true to line and level double charge Vitrified Tiles of approved brand conforming to IS 15622: 2006 (Group B I a) and tested as per IS 13630:2006 (relevant parts) [Non-modular sizes for tiles with Water absorption (av.) ≤ 0.08 %] in floor, skirting etc. using polymerised adhesive of 6mm thick layer applied directly over finished artificial stone floor/Mosaic etc. without any backing course and polishing the tiles using soft and dry cloth upto mirror finish complete including the cost of materials,labour and all other incidental charges complete as per direction of Architect. Floor Tiles : 600 x 600 mm	900	SFT		
21	Providing and fixing Tactile Tiles Anti Skid, Direction, PU 300 x 300 mm	25	SFT		
22	Applying white cement based wall putty 1.5 mm. thk. Over plastered surface.	3000	sft		
23	Wall painting with 2 coats of Acrylic Emulsion Paint, of approved brand and manufacture, including applying additional coats wherever required, to achieve even shade and colour, after thoroughly scrapping the surface and applying two coat of primer.	3000	sft		
A	TOTAL EXCLUSIVE OF GST				
B	DISCOUNT IF ANY				
C	TOTAL AFTER DISCOUNT (C=A-B)				
D	GST				
E	TOTAL INCLUSIVE OF GST (E= C+D)				

### APPROVED MAKE OF MATERIALS

1	False Ceiling / Channels	India Gypsum / Armstrong / Saint Gobain
2	Wood Frame Work / Wood Section : All Wood, Must be well seasoned, free from knots, other defects decay and defects due to handling and Transportation. Wherever necessary, provide with anti – termite Treatment.	Malaysian Sal / Kapoor
3	Wood Skirting / Moulding / Lipping / Bidding	White Beach / White Cedar / CP Teak
4	Wood Preservative	STP Pentaphene Pale / Termiseal by PCI / Bison by British Paint
5	Fire Reterdant Paint	Industrial grads of Noble / Viper
6	BWP Ply (IS : 710)	Century (excl. Sainik) / Globe BWP/ Sylvan / Green (excl. Ecotec)/ Kitply/ Apollo
7	Flush Door / BWP Block board (IS : 1659)	Century (excl. Sainik) / Globe BWP/ Sylvan / Green (excl. Ecotec)/ Kitply/ Apollo

SEAL & SIGNATURE OF TENDERER

8	Laminate (1.0 mm thk.) (IS : 2046)	Green lam / Century mica / Sunmica
9	Door Closure ( Heavy Duty )	Godrej / Archi / Sterling ( DC 2000)
10	Floor Spring ( Heavy Duty )	Godrej / Archi / Sterling ( FS 3000 )
11	Door Lock ( Dead )	Godrej / Hafele /Hettich / Kich / Doorset / Yale
12	Door Handles	Godrej / Hafele /Hettich / Kich / Doorset
13	Drawer / Storage Handle	Godrej / Hafele /Hettich / Kich / Doorset
14	Drawer / Storage Lock ( Multipurpose )	Hafele /Hettich /Doorset
15	Night latch	Godrej / 4C Acme
16	Screws	GKW / Nettle fold
17	Hinges	CIEF / Hettich
18	Sliding Telescopic Drawer Channel	Ebco / Earl Behari / Efficient Gadjets
19	Cable Organiser	Ebco / Innofitt Systems ( CM 63.C )
20	Adhesive	Fevicol SH / Fevimate TL
21	Soft Board	Jolly Board
22	Vertical Blinds	Mac / Annums / Window Fashion
23	Glass	Modi /AIS / Saint Gobain
24	Paints (Synthetic Enamel / Acrylic Emulsion)	Asain Paints / Berger / ICI
25	PVC Flooring	Krishna Vinyl / Armstrong / Birla
26	Texture Paint	Spectrum
27	Glass	Modi / AIS / Saint Gobain
28	European WC / Washbasin	Hindware /Parryware
29	Sanitary Fittings	Jaquar / Kohler
30	G.I. Pipe	Tata ( Medium )
31	Cement	Ultratech / Laferge / ACC
32	Footmat	Birla 3M / Approved Equivalent
33	Vitrified Tiles	Johnson / Kajaria
34	Ceramic Tiles	Johnson / Kajaria
35	All other items not covered above	As per sample approved by Employer/Consultant

SEAL & SIGNATURE OF TENDERER