

**PROPOSED REFURBISHING WORK FOR BOINCHI BRANCH
CANARA BANK CIRCLE OFFICE KOLKATA
I. SCHEDULE OF QUANTITIES FOR FURNISHING AND ALLIED CIVIL WORKS**

ITEM NO.	DESCRIPTION	QNTY.	UNIT	RATE RS. P.	AMOUNT RS. P.
1	<p>LOW HEIGHT SOLID/PARTLY GLAZED WOODEN PARTITIONS IN COUNTER FRONT & SIDE PARTITIONS & UPS BATTERY RM. Supplying and erecting low height opaque partitions (from 1'-6" - 4FT/5FT high) as per drawing and conforming to the following specifications : <u>Basic Framework</u> : Well seasoned Malaysian sal wood sections, treated with two coats of wood preservatives, 50mm x 50mm (minimum) at maximum 600 mm horizontal or vertical spacing as per site conditions. Vertical Members shall be suitably anchored and at ceiling level to ensure rigidity. <u>Skin Membrane</u> : 4 mm thick BWR grade plywood on each face with 4 mm grooves formed as per drawings/instructions. <u>Finishing</u> : 1.0mm thick laminate sheet of combination shades as per instructions on both sides. Quoted rates shall include all necessary materials, accessories and also allow provisions for electrical/telephone/computer wiring conduits and switch boxes, etc (Materials of wiring conduits and switch boxes shall be separately paid for.)</p>	90	sqft.		
2 A	<p>FULL HEIGHT PARTLY GLAZED WOODEN PARTITIONS in BM's ROOM Supplying and erecting full height partlyglazed partition (varying from 8'6" to 10ft high) as per drawing and conforming to the following specifications : <u>Basic Framework</u> : Well seasoned Malaysian sal wood sections, treated with two coats of wood preservatives, 50mm x 50mm (minimum) at maximum 600 mm horizontal or vertical spacing as per site conditions. <u>Skin Membrane</u> : (Opaque portion upto 900mm from floor level with 1x6 mm thick BWR grade plywood on each face with 4x4mm grooves formed at the top layer as per drawings/instructions. <u>Glazing</u> : 8mm thick clear float glass fixed with continuous White or Steam Beech wood glazing beads of approved shape (finished 35x25 mm) all around, polished & coated with NC lacquer finish. The rate should also include cost of decorative etching on one side of the glass. <u>Finishing</u> : 1.0mm thick laminate sheet of same or combination shades on both sides as per instructions. <u>Edge Moulds</u> : All free top/end surfaces shall have polished white or steam beech wood moulds of approved shape (from 80x 25mm sections) with LC lacquer in mat finish. <u>Skirting</u> : 100mm high x 12 mm thick polished white or steam beech wood skirting on both faces with NC lacquer in Matt finish. Quoted rates shall include all necessary materials, accessories and also allow provisions for electrical/telephone/computer wiring conduits and switch boxes, etc (Materials of wiring conduits and switch boxes shall be separately paid for.)</p>	200	Sq.Ft.		
3	<p>FULL HEIGHT SOLID PARTITION WITH BOTH SIDE LAMINATE Supplying and erecting full height opaque partitions (from 8'-6" 10ft. high) as per drawing and conforming to the following specifications : <u>Basic Framework</u> : Well seasoned Malaysian sal wood sections, treated with two coats of wood preservatives, 50mm x 50mm (minimum) at maximum 600 mm horizontal or vertical spacing as per site conditions. Vertical Members shall be suitably anchored and at ceiling level to ensure rigidity. <u>Skin Membrane</u> : 4 mm thick BWR grade plywood on each face with 4 mm grooves formed as per drawings/instructions. <u>Finishing</u> : 1.0mm thick laminate sheet of combination shades as per instructions on both sides. <u>Skirting</u> : 100mm high plywood skirting finished in 1mm thk. Laminate of combination shades as per instruction and drawing. Quoted rates shall include all necessary materials, accessories and also allow provisions for electrical/telephone/computer wiring conduits and switch boxes, etc (Materials of wiring conduits and switch boxes shall be separately paid for.)</p>	320	sqft.		

<p>4 WORKSTATIONS</p> <p>Providing, fixing and fitting in position free standing work station made of 19 mm thk. BWP Ply + 1.0 mm. Laminate of approved make and colour for the table top, sides & front apron. The table is supported on the left side by a 1'-6" wide & 2'-0" deep drawer unit consisting of a tea tray, one drawer & a shuttered cabinet on 1.0 mm thk. laminate finish and Ply partition on the right side. The table is provided with a readymade metallic CPU Holder with swivel facility, (CPU HL SW / INNORIT systems or similar) & readymade key board drawer of engineering Plastics (KD 575 P MT/ INNORIT System or similar) shall be suspended below the table top. Quoted rates shall also include cost of polished white or steam beech wood moulding (finished 40x20 mm section) to edges of table top; polished white or steam beech wood lipping (6mm thick) to free edges of black board/ plywood surfaces; approved drawer - slides, concealed type auto-closing shutter hinges and locks with keys in duplicate; other necessary hardware and accessories including satin finish S.S. handles, knobs and wire - managers etc. of approved quality & the table top is finished with 10 mm thick glass.</p> <p>A) Approx. size of 1800 x 900 x 750 mm B) Approx. size of 1500 x 750 x 750 mm D) Approx. size of 1200 x 750 x 750 mm</p>	<p>1 1 3</p>	<p>No. No. No.</p>	
<p>5 Providing, fitting & fixing the Cash counters & Cabin along with partitions all complete: Internal Size of the cash cabin: 5'-0" (w) x 7'-0" (l) x 7'-0" (h)</p> <p>5A Providing fixing & fitting 2'-6" wide & 2'-6" high staff working top made of 18mm thick BWP block board of approved make finished with 1.0 mm laminate of approved make & shade. The customer transaction top shall be 1'-6" wide projecting 6" on the customer side at a height of 1' above the staff working counter thus making a total height of 3'-6". The customer top is made of 3/4" thk. Granite top (Black galaxy) placed on 18mm thick BWP blockboard which is cut & shaped with edges round polished. Below the working top/counter will be 1'-4" wide drawer cum shuttered cabinet unit on one side & metallic CPU trolley on the other side with key board tray with slide channels & foot rest in between for each of the cash counters specs same as Banking Counters. All the specification of the drawer unit/CPU trolley is same as that of Work station in item no 4. Below the Transaction top the partition which is overlapping with the working counter of 10" deep will be covered by 2 sets of sliding shutters with a intermediate shelf with all locking arrangement for keeping currency notes. Both the staff working top & the transaction top is rested & supported together by a front Apron or Double skin partition which is similar in design and specification as that of Banking counters. There will be necessary grooves between the two different decorative laminates as shown in the detail drawing & as directed. The counter will be provided with wire manager. The front portion of cash cage above the transaction top (from 3'-6" to 7'-0" height) will be provided with 2 nos. of 12 mm thick float glass leaving a gap of 2" between the two glass panes so as to allow conversation between the customer & the cashier & a cut out of 8" x 4" of the central bottom part of each of the transaction top.</p> <p>5B Cash Cage Side, Intermediate & rear Partitions with door The intermediate/side/rear partition with doors between Cash Cabins as Partly glazed Wooden Partition upto 7'-0" height with the following specification: <u>Basic Framework</u>: Well seasoned Malaysian sal wood sections, treated with two coats of wood preservatives, 50 mm x 50mm (minimum) of maximum 600 mm horizontal or vertical spacing as per site conditions. Vertical Members shall be suitably anchored at floor level to ensure rigidity. Exposed frame members in the glazed portions shall have wider spacing (approx. 1800 mm clear) as per instructions. Exposed members shall be finished with 1.0mm thick laminate sheet of same or combination shades, over 6 mm BWR grade plywood including 4 mm grooves at locations as per instruction. <u>Skin Membrane</u>: Opaque portion upto 1050 mm(3'-6") from floor level with 6 mm thick BWR grade plywood on each face with 44mm grooves formed as per drawings/ instructions. <u>Finishing</u>: 1.0mm thick laminate sheet of combination shades as per instruction and drawing.</p>	<p>4.5</p>	<p>Rft.</p>	

5B	<p>Skirting: 100mm high plywood skirting finished in 1mm thk. Laminate of combination shades as per instruction and drawing.</p> <p>Glazing: Strips of 8 mm thick clear float glass fixed with continuous White or Steam Beech wood glazing beads of approved shape (finished 35x25 mm) all around, polished & coated with NC lacquer finish. The rate should also include cost of decorative etching on one side of the glass.</p> <p>Quoted rates shall include all necessary materials, accessories and also allow provisions for electrical/telephone/computer wiring conduits and switch boxes, etc (Materials of wiring conduits and switch boxes shall be separately paid for.)</p> <p>All exposed edges of the BWP ply & blockboard are to be finished with 12 mm thk. Rubber wood lipping which are to be polished as directed. Provision for extra wooden frame work of same section for intermediate glazing to be included in the rate.</p> <p>There will be provision for small trays/windows for transferring of small copy either from the banking area to the cash cabins or between the cash cabins as directed by the architect.</p> <p>The cost of all fittings of the door :handle locks,aldrop handles, hydraulic door closer, night latch all of approved make of the doors wherever required in the cash section to be included.</p>	145	SQFT.		
6	<p>SIDE CREDENZO</p> <p>consisting of a top row of two sets of 4" high drawers with cabinets below with sliding shutters, made of 19mm thick BWR grade block boards all finished in 1.0mm thk.laminate. Exposed block board surfaces shall be finished with 1.00mm laminate sheet of approved shade and make. Inner faces of sliding shutters shall be polished in approved color. Free edges of block board shall have polished white or steam beech wood half round moulds (out of 20 x 20 mm sections). Inner faces of cabinet units shall be polished in approved shade quoted rates shall include cost of necessary hardware . Viz handles, locks with keys in duplicate, etc.</p>	3	Nos.		
7	<p>P/F/F Full height /Low height filling cabinet/Over head Cabinet 1'-6" deep</p> <p>made of 18mm BWP blockboard with intermediate shelves.The back of the cabinet to be made of 6mm thk.BWP ply fixed on the wall. There will be one horizontal division and vertical dividers of same block board at approx. 3ft.apart with sliding shutters for Low height & overhead cabinet. All exposed surfaces & the shutters are finished with 1.0 mm thk. decorative laminate of approved make & shade. Cost of all fittings like brass hinges, godrej locks, magnetic hinges, godrej locks, magnetic catches, steel matt finish "D" type handles shall be inclusive.</p>	25	Sqft		
8	<p>FLUSH DOOR</p> <p>Supplying and fixing in position overall 37mm thick solid core hot pressed phenol formaldehyde bonded approved flush door shutter finished door shutter finished with 1.0mm thick laminate sheet of approved shade and quality on both sides of the door shutter including cost of hardware fittings e.g. mortice locks, brass hinges, hydraulic door closer, door handles etc. of approved make and quality.</p>	3	No.		
a	Average size of shutter (D1) : 3' 0" x 7'-0"	3	No.		
b	Average size of shutter (D2) : 2' 6" x 7'-0"	3	No.		
9	<p>GLAZED DOOR SHUTTER</p>				
9A	<p>Providing, fixing & fitting in position Partly Glazed Door shutters made of specification similar to that of item (8) hinged on 3 nos. brass hinges as required with the exception that the wooden frame is of section 2" x 1.5". The cost of all fittings:handle locks, aldrop handles door closer, night latch all of approved make to be included.The glazed portion will be between 3'-0" to 6'-8" of 6 mm thk. glasspanes of approved quality. Average size of shutter (D3) : 3'-0"x 7'-0" (Branch Head's Cabin)</p>	2	Nos.		
9B	<p>MAIN ENTRANCE DOOR FOR BRANCH</p> <p>Providing & fixing in position Full glass 3'-6" wide Single leaf door cum fixed glazing . The door shutter & fixed glazing is made of 12mm thk. SGG impact resistance glass (toughened glass) with pencil polish edges all around. Etching design for glass door as per design. Door & fixed glazing shall be fixed with PATCH FITTING assembly inclusive of top and bottom patches, Floor spring, Bottom lock, SS brushed handle of 2'0" long 1" dia on both sides.</p>				
1	Glazed Door Shutters	25	SQFT.		
2	Glazed Fixed Glass Partition	35	SQFT.		

10	Door Frames: P/F/F Door frames made out of 4" x 3" /3" x 1.5" clear Steam Beech wood free of knots and proper rebates and grooves be made before fixing to the wall & finished with melamine polish with necessary approved M.S holdfast with split ends fixed with G.S.screws including grouting with 1:2:4 concrete in brick work and/or with rawl plug in RCC construction and/or properly screwed and fixed in Partition as directed etc complete.	0.20	CUMMT		
11	PIN-UP NOTICE BOARD Providing, fitting in position pin-up board made of soft cork board finished with the fabric as approved, matching with the colour scheme of the banking hall with a R.W. moulding all around the edges.	20	Sqft.		
12	PANELLING ON THE WALLS & PILLARS WITH LAMINATE FINISH Wall Panelling / column encasing (upto False ceiling height) works as per Branch Ambience Standardised manual of the Bank conforming to the following specifications : Shall be made up of 2"x1" salwood framework with 12mm thk ply back up. The framing shall be fixed at intervals of 2'0" c/c horizontally and vertically. Shall be made up of 19mm thk plywood as per site conditions. The framing shall be fixed with 6mm thick ply to form 4mm grooves finished with 1mm thick approved color laminate of approved make at every 1ft interval. The skirting shall be finished with 3" wide 1.00mm approved bi color laminate of approved make. Quoted rates shall include all necessary materials, accessories and labour and also allow provisions for electrical/telephone/computer wiring conduits & switch boxes etc. complete with necessary jacking /thickening of panels to accommodate conduits/ switch boxes. (Materials for wiring conduits and switch boxes shall be separately paid for).	140	Sqft.		
13	TRAP DOOR & BOXING FOR ROLLING SHUTTERS & COLLAPSIBLE GATE WITH ACP FINISH Providing and fixing trap doors consisting of 1/4" thk. Marine ply shutters with a clear opening of 4.5" opening for smooth operation of shutters and rest is closed with mirror screws (for opening for servicing). The shutters shall be finished with approved ACP finish with all materials and frame of 2"x1 1/2" teak wood sections shall be provided for proper support and strength. Rate shall be inclusive of necessary fittings like hinges(hafele/ebco make), ball catches, tower bolts, etc.	80	SQFT		
14	WOODEN SHUTTERS WITH FRAME FOR ELECTRICAL PANELS Providing and fixing 18mm thk. Com ply shutters with same ply frame. Division of shutters shall be made equally according to the length. Shutters shall be hinged to the framework and finished with 1.0mm thk. Laminate of approved colour and shade on outer side and inside finished with 2 coats of enamel paint of app colour and shade. Rate shall be inclusive of all necessary approved fittings like hinges, ball catch, 150 mm long SS Brush Finish handle, tower bolts, locks, Aluminium powder coated air vent grills and necessary hardware fittings complete, etc.	40	SQFT		
15	Writing Ledge FOR BRANCH Providing & fixing Writing ledge of size 750mm x 500 mm x 150mm with pigeon hole type box below the top made out of 19mm block board finished with 1mm laminate fixed/ mounted on the wall with Angle Support. With a 12mm thick machine polished clear glass top fitted to the main structure with 4 nos. 75mm high stainless steel studs.	1	NO.		
16	Suggestion Box & Cheque Drop Box FOR BRANCH Providing & fixing Suggestion box of size (450mm x 150mm x 300mm) made out of 12mm block board finished with 1mm laminate and openable shutter with locking arrangement.	2	NO.		
17	WOODEN LUNCH TABLE IN LAMINATE FINISH Providing and laying Lunch Table 2FT Depth made of approved BWR ply wood 19mm thick supported on wooden legs. The table shall be finished with 1mm laminate and with polished T.W. edge moulding.	0	RFT		

18	WINDOW SCREEN Providing, fitting in position 100mm Vertical blinds made of best quality PVC coated polyester fabric of approved make & shade & to be tailored to the size of the window.	170	SQft		
19	GYPSTUM BOARD FALSE CEILING (INCLUDING DROP) Providing and fixing in position dropped ceiling in two levels including vertical surfaces in between two level of ceiling surface with 12.5mm thick tapered edge gypsum board conforming to IS 2095 including providing and fixing of framework made of special sections power pressed from MS Sheet and galvanised in accordance with Zinc coating 600 as per IS 277 and costing of angle cleats of size 25mm wide x 16mm thick with flanges of 22mm and 37mm at 1200mm center to center one flange fixed to the ceiling with dash fastner 12.5mm dia with flanges of 22mm and 37mm at 1200mm center to center one flange fixed to the ceiling with dash fastner 12.5mm dia x 40mm long with 6mm dia bolts to the angle hangers of 25x25x5 mm of required length and other end of angle hanger being fixed with nut and bolts to G.I. Channels 45mm x 15mm x 0.9mm running at the rate of 12mm centre to centre to which the ceiling section 0.5mm thick bolton wedge of 08mm with tapered flanges of 26mm each having clips of 10.5mm at 450mm center to centre shall be fixed in a direction perpendicular to G.I. Channel with connecting clips made out of 2.64 mm dia x 230mm long G.I. Wire at every junction including fixing the gypsum board with ceiling section and perimeter channel. The perimeter of ceiling fixed to wall/partition with the help of rawl plugs at 450 mm center to center with 25mm long drive all screws @ 230mm interval including jointing and fixing to a flush finish of tapered and square edges of the gypsum board with recommended filler, paper tapes, finisher and two coats of primer suitable for gypsum board as per manufactures specification and also include the cost of making openings for light fittings grills, diffusers, cutouts made with frame of perimeter channels of the Engineer-in-Charge . Rates to include cost of making openings for ceiling mounted electrical fittings/air-conditioning accessories and also making of openings of size 2'x2' with door for electrical servicing as per instructions.	428	Sqft.		
20	FALSE CEILING (Armstrong) Providing & fixing in position false ceiling in Armstrong Make 600 x600 mm x 15/16 mm Dune Microlook tile with Regular Black reveal framework as specified by Armstrong Co. with suspenders wherever required. Making necessary framework for A.C ducting, if any and necessary cutouts for diffusers and light fittings, taping and finishing to proper line & level, including making grooves and trap doors for A.C. unit in 18mm thick M.R. Grade Plywood with Stainless Steel hinges & locks with moulding 1" x 1" for edges including finishing with White Plastic Emulsion Paint etc. complete in all respects. (Note- Only the plan area will be measured for payment. No extra payment will be made for cutouts, grooves mouldings etc.)	288	SQFT		
21	PLASTIC EMULSION PAINT WORK IN THE AC AREA Providing & applying minimum two coats of acrylic emulsion paint of approved shade & make on a base coat of necessary primer including necessary scrapping of old surface & new surface preparation in the walls under false ceiling. Providing & laying 1mm thk.(avg.) White Cement Putty on the wall area to prepare the surface before Plastice Emulsion paint , as directed by architect.	1400	SQFT		
22	SYNTHETIC ENAMEL PAINT ON STEEL WINDOWS/WOODWORK/ROLLING SHUTTER Providing and painting on wooden, steel or plastered surfaces with two coats of Synthetic Enamel paint of approved shade & brand over a coat of primer of approved quality after sand papering the old/new surface to give an even uniform shade.	800	SQFT		
23	DITEMPER PAINT WORK IN THE NON AC AREA Providing and applying minimum two coats of Distemper paint of approved shade & make on a base coat of necessary primer including necessary scrapping of old surface & new surface preparation in the walls under ceiling.	1700	SQFT		
24	STAINLESS STEEL SINK 18 " x 18 " S. S. Nirali sink without drain board (medium) or equivalent make. A flexible pipe from sink to the nahani trap shall be provided. Rate shall also include one jaguar continental C P SWAN NECK TAP with swinging casted spout.	0	NOS.		
25	Granite Work of Counter Top Grade Providing and fixing 18mm thick polished black color and shade of Granite with moulding at edges in Pantry & Utility area. The width of the black stone slab is as per site condition. This also includes preparing the base surface, applying neat cement slurry @ 2.75 kg. of cement per sq. mtr. of area to receive the mortar bed, jointing each slab with neat cement paste/ grout with white cement mixed with pigment (conforming, to IS:2114, Table-1) to match the colour of the granite.	0	Sqft		
26	Providing & fixing Counter number plate with hanging arrangement from ceiling with required size and coloured pvc sheet.	6	unit		
27	Providing & fixing Name plate with required size and coloured pvc sheet.	6	unit		
28	Providing & fixing Table / Counter front Logo to be printed over 300 x 300 mm. x 8 mm. thk. Rounded white pvc sheet , fixed to table front with 4 no. 50 mm. long SS studs complete as directed	6	unit		
29	Dismantling of existing banking counters, Cash Counters and all existing partitions, false ceiling, Panelling as directed removing them from the premises, shifting of climichs from old position to the designated areas in the premises & removing of the rubbish from site as per local Municipality rules.	1	JOB		
1	BRICK WORK WITH RED BRICK : Providing & fixing 125 mm. thick brick work with 1st class bricks in cement mortar (1:4). To separate ladies toilet with gents toilet	120	Sqft		
2	PLASTER : Providing 12mm plaster to Newly constructed brick surface, with 1:6 cement sand (fine sand) mortar ratio as per direction of Architect.	240	Sqft		

3A	VITRIFIED FLOORING (Skirting included) Size 600mm x 600mm: in Banking Hall Providing and Laying Vitrified Tiles of approved colour /shade. Glossy Double charged Vitrified Tile Flooring of 1st quality(with 3mm spacer on floor) with water absorption less than0.08% and confirming to IS- 15622. Ivory colour shade fixed on bed of cement mortar 1:4 Mx. The Vitrified Tile shall be fixed with neat cement float filling joints neat matching colour cement slurry. Rubbing, Cleaning etc. as per instruction. Skirting 4" will be included and measured in Sq ft. Note: After the flooring work, the vitrified flooring will be protected by laying a plastic sheet and POP layer on top of the sheet for protection till the modular furniture work begins. At that stage the plastic sheet with the POP layer will be removed neatly and carefully and disposed off as scrap.(Tile brand will be Kajaria, Euro Vitrified, Somany, Nitco, Simpolo or Varmora). (Cement - Ultratech, Ambuja, Ramco, JK Cement, India Cements)	590	Sqft		
3B	VITRIFIED TACTILE FLOORING Size 300mm x 300mmX 15mm: Providing and Laying Vitrified Matt finish Tactile Tiles of approved colour /design in the area marked in plan. The Vitrified TactileTile Flooring of 1st quality with water absorption less than0.08% and confirming to IS- 15622. All other specs same as item no. 3A	70	Sqft		
4	CERAMIC TILES Supplying & fitting & fixing 1st quality Anti skid Ceramic tiles (Rectified-joint free) plain coloured, anti-skid, anti-wear and mat finish of size 600 x600 mm in floors including borders, set in sand mortar(4:1) including backing concrete(1:2:4) & 4 Nos.of key stones(10mm) fixed with araldite at the each tile & finishing the joints with White cement mixed with coloring oxide of required to match colour of tiles. The size of ceramic wall dado shall be 600 x 300 mm. The cost also includes the rate for removal of the rubbish from the site as per KMC rules. Basic rate of Tiles:Rs. 600/sqm				
a.	Ceramic Tiles Flooring in the Non Banking Area	0	SQFT		
b.	Ceramic Tiles Dado in the toilet & pantry.	0	SQFT		
5	PLUMBING & SANITARY FITTINGS				
A	15mm DIA C.P.V.C. PIPE Providing & fixing 15mm dia CPVC pipes for distribution in toilets / pantry including chase cutting, chase filling. The rate shall include all accessories like tees, unions, elbows, bends etc. required to make the system operational and complete.	20	R.FT.		
B	32mm DIA C.P.V.C PIPE Providing & fixing 32 mm C.P.V.C pipes for distribution in toilets / pantry including chase cutting, chase filling. The rate shall include all accessories like tees, unions, elbows, bends etc. required to make the system operational & complete.	30	R.FT.		
C	DRAINAGE PIPE Providing & fixing PVC pipes of supreme/prince make or equivalent in position of required size with special fittings, traps, bends, ys, floor & nahni traps etc. Including chemical sealed joints as required at site making necessary connections with existing lines for w.c. & waste water lines, chambers to be constructed wherever necessary, unused lines for w.c. & waste water to be removed, the rate shall include all incidental work, cutting & making good walls & floors etc. Complete. Please visit the site for inspection.				
1	3"	20	RFT		
2	4"	15	RFT		
3	GULLY TRAP	2	Nos		
6	P & F Snow White vitreous handwash basin with Half Pedestal and waste coupling & all accessories complete. SIZE : 550X 410X 150 MM OF CERA/ HINDWARE / PARRYWARE make	1	Each		
7	P/F/F E.P.W.C. with 'S' /'P' Trap with Twin Flush Flushing Cisten of Snow white vitreous ware with Seat Cover. /C of joining materials etc. all complete. SIZE : 710 X 370 X 770 MM OF CERA/JACQUAR/ HINDWARE / PARRYWARE make	1	Set		
8	P/F/F following Toilet taps & cocks of CERA/HINDWARE / PARRYWARE make with				
A	15mm dia. Brass C.P. Pillar Cock with Aerator. Model No : (VINE)F1020101	1	Each		
B	15mm dia brass C.P. Two way Bib cock Model No : (VINE)F1020161	1	Each		
C	15mm dia brass C.P. Angular cock/concealed stop cock with wall flange	2	Each		
D	15mm dia brass C.P. connector upto 600mm long	2	Each		
9	TOILET REQUISITES & ACCESSORIES				
A	5.5 MM THK BEVELLED EDGED MODIGUARD MIRROR WITH SILVER RED FIXED ON 6 MM THK ASBESTOS BACKING FIXED WITH S.S. STUDS (size: 2'6 x 2'0")	2	NO.		
B	HEALTH FAUCET JET SPRAY FOR WC IN THE TOILETS JACQUAR/CERA/ HINDWARE / PARRYWARE make	2	NOS.		
10	DISMANTLING TOILET FIXTURES ALONG WITH WALL & FLOOR TILES IN THE EXISTING 2 TOILET BLOCK.	0	JOB		
GROSS TOTAL (Rs.) GST Extra as applicable					