

CANARA BANK

INVITATION TO TENDER

ONLY FOR EMPANELLED CONTRACTORS

OF

CIRCLE OFFICE KOLKATA

TENDER FROM ANY OTHER CONTRACTOR WILL BE SUMMARILY REJECTED

INSTRUCTION TO BIDERS

AND

GENERAL CONDITIONS OF CONTRACT

FOR

FURNISHING WORKS

AT

CANARA BANK – RAIGANJ II BRANCH

TENDER NO.: 134/25-26/BDS

NAME OF THE CONTRACTOR:

.....

ADDRESS:

.....

SEAL & SIGNATURE OF TENDERER

NOTICE INVITING THE TENDER

To,

M/s

Sealed tenders on item rate basis are invited from panel Contractors for **Interior furnishing Works at premises of Raiganj II Branch.**

Tender Documents may be obtained at free of cost from the Premises & Estate Section, Circle Office Canara Bank, Kolkata during working hours from **09.01.2026 till 15.01.2026.**

Earnest Money Deposit : NIL

Period of completion : 21 days

**Last date, time and place for Submission of tender : On or before 3:00 pm, 15.01.2026 to
The Assistant General Manager,
General Administration Section
Canara Bank, Circle Office
Kolkata**

Time and date of opening of tender : 3.30 pm on 15.01.2026

The Bank will not be bound to accept the lowest tender and reserves the right to accept or reject any or all the tenders without assigning any reason whatsoever.

**Assistant General Manager
Premises & Estate Section
Canara Bank, Circle Office
Kolkata**

.....

Date: 09.01.2026

SEAL & SIGNATURE OF TENDERER

GENERAL RULES & INSTRUCTIONS TO TENDERERS

Name of the work: Furnishing Works to be carried out at premises of Raiganj II Branch & ATM

The rates quoted shall also be inclusive of materials, labour charges, work contract tax, surcharge and all the taxes except GST.

GST WILL BE PAID EXTRA.

The rates quoted by the tenderer shall hold good till the completion of the work from the date of issue of the "WORK ORDER" and no enhancement in the rates are allowed during the period of execution of the work under any circumstances. The rates quoted shall also cover for the work to be executed before and after office hours and also on holidays.

The time stipulated for the completion of the work is 21 days from the date of issue of the WORK ORDER and the work is to be carried out as per the convenience of occupants without disturbing other occupants of the building.

TENDERS:

The entire set of tender paper issued to the tenderer should be submitted fully priced and also signed on the last page together with initials on every page. Initials / signatures will indicate the acceptance of tender papers by the tenderers.

The schedule of quantities shall be filled in as follows:

- The "rate" column to be legibly filled in ink in both English figures and words.
- 'Amount' column to be filled in for each item and the amount for each sub-head as detailed in the "schedule of quantities".
- All corrections to be initialed.
- The "Rate" column for all the items shall be filled up.
- The "Amount" column for the items for which the quantities are not mentioned shall not be filled up.
- In case of any errors / omissions in the quoted rates, the rates mentioned in the tender in words shall be taken as correct rates.

No modifications, over-writings or corrections can be made in the tender papers by the tenderer, but may at his option offer his comment or modifications in a separate sheet of paper attached to the original tender papers.

The Bank reserves the right to reject the lowest or any tender or all of the tenders for each section or to split up and distribute any item of work to any specialist firm or firms, without assigning any reason.

The tenderers should note that tender is strictly on the item rate basis and their attention is drawn to the fact that the rates for each and every item should be correct, workable and self – supporting. If called upon by the bank, detailed analysis of any or all the rates shall be submitted. The architects/bank shall not be bound to accept the contractor's analysis.

The Quantity mentioned in the BOQ is approximate measurements. The works will be paid for as "measured work" on the basis of actual work done and not as "lump sum" contract.

All the items of work described in the schedule of quantities are to be deemed and paid as complete works in all respects and details including preparatory and finishing works involved, directly, related to and reasonably detectable from the drawings, specifications and schedule of quantities and no further extra charges will be allowed in this connection. In the case of lump-sum charges in the tender in respect of an item of works, the payment of such items of work will be made for the actual work done on the basis of lump-sum charges as assessed to be payable by the architects/bank.

SEAL & SIGNATURE OF TENDERER

The bank has power to add or delete any work or described in specifications or included in schedule of quantities and intimates the same in writing but no addition, omissions or variation shall be made by the contractor without authorization from the bank. No variation shall vitiate the contract. The bank reserves the right to delete any of the items in the tender without assigning any reasons whatsoever.

The tenderer shall note that his tender shall remain open for consideration for a period of 90 days from the date of opening of tender.

AGREEMENT

The successful contractor is required to sign agreement as may be drawn up to suit the local conditions and shall pay for all the stamps and legal expenses incidental thereto. The original will be kept with the Bank and duplicate with contractor.

EARNEST MONEY AND SECURITY DEPOSIT:

There is NO Earnest Money Required to deposit/ submit along with the bids. Retention Money shall be deducted from the final bill at 5% of the gross value of bill. The Retention amount will be refunded to the contractor 15 days after the end of defects liability period provided he has satisfactorily carried out all the work and attended to the entire defect in accordance with the condition of the contract. No interest is allowed on Retention Money.

A part of the Security Deposit if and as decided by the constituent bank can also be furnished in the form of a Bank Guarantee on the bank other than that of the constituent bank.

CONTRACTOR TO PROVIDE EVERYTHING NECESSARY:

The contractor shall provide everything necessary for the proper execution of the work according to the intent and meaning of the drawings, schedule of the quantities and specifications taken together weather the same may or may not be particularly shown or described therein provided that the same can reasonably be inferred there from and if the contractor finds any discrepancies therein he shall immediately and in writing, refer the same to the Architects/Bank whose decision shall be final and binding.

The rates quoted against individual items will be inclusive of everything necessary to complete the said items of works within the contemplation of the contract, and beyond the unit price. No extra payments will be allowed for incidental or contingent labour and/or materials inclusive of all taxes and duties whatsoever except for specific items, if any, stipulated in tender documents

The contractor shall supply, fix and maintain at his own cost, for the execution of any work, all tools, tackles, machineries and equipment and all necessary scaffolding, staging and lighting by night as well as by day required not only for proper execution and protection of the said work.

The contractor shall take down and remove any or all such scaffoldings as occasion shall be required or when ordered to do so, and shall fully reinstate and make good all matters and things disturbed during the execution of work to the satisfaction of architect/bank.

The contractor shall all times give access to workers employed by the bank or any men employed at site and to provide such parties with proper sufficient and if required, special scaffolding and ladder and provide them lighting as may be required to enable such workmen to inspect the work, lay or fix pipes, Civil & furnishing wiring, special fittings etc. The quoted rates of tenderers shall accordingly include all these above-mentioned contingent works.

LIQUIDATED DAMAGES:

Should the work be not completed to the satisfaction of bank within the stipulated period, the contractor shall be bound pay the bank a sum calculated as given below by way of Liquidated Damages after the expiry of completion date

.1.00% of the estimated amount shown in the tender per week subject to a ceiling of 10% of the accepted contract sum.

TIME PERIOD FOR COMPLETION: 21 days from the date of award of work.
--

SEAL & SIGNATURE OF TENDERER

FINAL PAYMENTS

The final bill shall be accompanied by a certificate of completion from the Occupant/Bank Officials. Payments of the final bill shall be made after deduction of retention money as specified in clause 9 of these conditions which sums shall be refunded after the completion of the defects liability period after receiving the banks certificate that the contractor has rectified all defects to the satisfaction of the banks. The acceptance of payments of the final bill by the contractor would indicate that he would have no further claims in respect of the work executed.

ESCALATION:

The rates quoted shall be firm throughout the tenure of the contract [including extension of time, if any granted] and will not be subject to any fluctuation due to increase in cost of materials, labour, sales tax, octroi etc, unless specifically provided in these documents.

CONTRACTORS EMPLOYEES:

The contractor shall employ technically qualify and competent supervisors for the work who shall be available [by turn] throughout the working hours to receive and comply with the instructions of the bank officials. The contractor shall engage at least one experienced engineer, as site in-charge for the execution of the work the contractor shall employ in connection with the work persons having appropriate skill or ability to perform their job efficiently. The contractor shall employ local labours on the work as far as possible. No laborers below age of 16 and who is not an Indian national shall be employed on the work. Any laborers supplied by the contractor to be engaged on the work on day-work basis either wholly or partly under the direct order or control of bank or its representative shall be deemed to a person employed by the contractor.

The contractor shall comply with provision of all labour legislation including the requirements of

- a. Payments of minimum wages act
- b. Employers liabilities
- c. Workmen's compensation act
- d. Contract labour (regulation and abolition) act, 1970 and central rules 1971
- e. Apprentices act 1961
- f. Any other act or enactment relating thereto and rules framed there under from time to time

The contractor shall keep the bank saved harmless and indemnified against claims if any of the workmen and all costs and expenses as may be incurred by the bank in connection with any claim that may be made by any workmen.

The contractor shall comply at his own cost with the order of requirement of any health officer of state or any local authority or of the bank regarding the maintenance of proper environmental sanitary condition of the area.

The contractor shall arrange to provide first aid treatment to the laborers engaged on the works. He shall within 24 hrs of occurrence of any accident at or about the site or in connection with execution of work, report such accidents to the bank and also the competent authority where such report is required by law.

The contractor shall obtain all Risk Insurance Policy at their cost within 7 days of commencement of work, for the laborers/workmen working at the site including the work till the work is completed. The policy shall be in the joint name of the Bank and contractor and Bank's name shall appear First.

PAYMENTS:

The contractor, in the form prescribed by the bank shall prepare all the bills and submit the same to Bank with measurement of work. Normally one interim bill shall be prepared each month. Bank may release payment within 15 days of receipt of bills/after check measurement, after deduction of retention money, Income Tax etc. The contractor shall have a competent engineer at site for the supervision of the work.

The contractor shall have to make his own arrangements for watch and ward of the work/building, till the work is handed over to the bank.

The decision of the bank will be final and binding with regard to the quality of work is concerned.

SEAL & SIGNATURE OF TENDERER

The contractor is responsible for procuring the required materials for the work and stores the same at site at his cost and risk.

The amount stated in the interim certificate shall be the 75% of total value of the work executed up to date of the bill, less the amount to be retained by the bank as retention money. If the bank has supplied any materials or goods to the contractors, the cost of such materials will be progressively deducted from the amount due to the contractor on accordance with the quantities consumed in the work. All the interim payments shall be regarded as payments by way of advance against the final payment only and not as payments for works actually done and completed and shall not preclude the requiring of bad, unsound or imperfect or unskilled work to be removed and taken away and reconstructed or re-erected or be considered as an admission of the due performance of the contract or any part there of if any respect or accruing of any claim nor shall it conclude, determine of effect in any way the power if the bank under conditions or any of them add to the final settlement and adjustment of the accounts or otherwise or in any other way or affect the contract.

The contractor shall submit the final bill within one month from the date of completion of the work. A certificate of completion from the bank shall accompany the final bill. The payment of the final bill shall be made after deduction of retention money as specified elsewhere in these documents.

ARBITRATION:

All disputes or differences of any kind whatsoever which shall at any time arise between the parties here to touching or concerning the works or the execution or maintenance thereof of this contract or the rights touching or concerning the works or the execution of maintenance thereof of this contractor or the construction remaining operation or effect thereof or to the rights or liabilities of the parties are arising out of or in relation thereto whether during or after determination foreclosure or branch of the contract[other than those in respect of which the decision of any person is by the contract expressed to be final and binding] shall after written notice by either party to the contract to the other of them and to the employer hereinafter mention to deal referred for adjudication to a sour arbitrator to be appointed as hereinafter provided.

For the purpose of appointing the sole arbitrator referred to above, the employer will send within 30 days of receipt of the notice, to the contractor a panel of 3 names of persons who shall be presently unconnected with the organization for which the work is executed.

The contractor shall on receipt of the names as aforesaid, select, anyone of the person's name to be appointed as a sole arbitrator and communicate his name to the employer within 30 days of the receipt of the names. The employer shall thereupon without any delay appoint the person as the sole arbitrator. If the contractor fails to communicate such selection as provided above within the period specified, the competent authority shall make the selection and appoint the selected person as the sole arbitrator.

If the employer fails to send to the contractor the panel of 3 names as a foresaid within the period specified, the contractor shall send to the employer a panel of 3 names of persons who shall be unconnected with either party. The employer shall on receipt of the name as a foresaid select anyone of the person's names and appoint him sole arbitrator. If the employer fails to select the person and appoint him as a sole arbitrator within 30 days of the receipt of the panel and inform the contractor accordingly, the contractor shall be entitled to appoint one of the persons from the panel as the sole arbitrator and communicate his name to the employer.

If the arbitrator as appointed is unable or unwilling to act or resigns his appointment or vacates his office due to any reason whatsoever another sole arbitrator shall be appointed as aforesaid.

The work under contract shall, however, continue during arbitration proceedings and payment due or payable to the contractor shall be withheld on account of such proceedings.

SEAL & SIGNATURE OF TENDERER

The arbitrator shall be deemed to have entered on the reference the data he issued notice to both the parties fixing the date of the first hearing.

The arbitrator may from time to time, with the consent of parties, enlarge the time or making and publishing the award.

The arbitrator shall give a separate award of each disputes or difference referred to him. The arbitrator shall decide each dispute in accordance with the terms of the contract and give a reasonable award. The venue of arbitration shall be such place as may be fixed by the arbitrator in his sole discretion.

The fee, if any, of the arbitrator shall, if required to be paid before the award is made and published, be half and half by each of the parties. The cost of the reference and of the award including the fees, if any, of the arbitrator who may direct to and by whom and in what manner, such costs or any part thereof shall be paid and may fix or settle the amount of costs to be so paid.

The award of the arbitrator shall be final and binding on both the parties.

Subject to aforesaid the provision of the arbitration act 1940 or any statutory modification or re-enactment thereof and the rules made there under, and for the time being in force, shall apply to the arbitration proceeding under this clause.

The employer and the contractor hereby also agree that arbitration under the clause shall be a condition precedent to action under the contract with regard to the matters hereby expressly agreed to be so referred to arbitration.

Date:

**Signature of the Contractor
With seal and address**

SCHEDULE OF INTERIOR FURNISHING WORKS AT RAIGANJ II BRANCH					
SL NO	DESCRIPTION	Qty	Unit	Rate	Amount
1	REMOVING PAINT				
	Removal of existing paint from the plastered surfaces with coir brush,sand paper etc. and preparing the surfaces by rendering the same with cement sand mortar to receive plaster of paris punning, complete as directed.	2666.00	Sqft		
2	CEMENT BASED WHITE PUTTY				
	Providing & laying 1.5 mm thk. Cement based White putty (make : J.K or birla) punning on the walls as per manufacturer's specification (on wall upto 6" high above false ceiling in false ceiling area & Putty to be applied on full ht. walls and ceilings of the area where false ceiling is not to be done) (MEASUREMENT TAKEN UP TO FALSE CEILING HT.)	2666.00	Sqft		
3	PLASTIC EMULSION PAINT WORK				
	Providing and applying two coats of Plastic Emulsion paint of approved make & Colour over a coat of primer of approved brand including the surface smoothening by sand-papering to the walls of whole premises except ceiling area whwre false ceiling done. (MEASUREMENT TAKEN UP TO FALSE CEILING HT.)	2666.00	Sqft		
4	SYNTHETIC ENAMEL PAINT ON WALLS/STEELWINDOWS /WOODWORK				
	Painting all the windows, grill, collapsible gate with two coats of Synthetic Enamel Paint over a coat of primer of approved shade, make & color at all heights & levels complete as directed as per manufacturer's specifications. (Before execution take necessary permission from the Architect/Bank)	713.00	Sqft		
5	MAIN ENTRANCE FULLY GLAZED PARTITION				
	Providing and fixing frameless fully glazed 12mm thk toughened float glass partition fixed with necessary patch fittings(Dorma make) including cutting, making holes, cutouts in the glass of required shape and size to accommodate fittings and fixing the fittings in floors, soffits, jams including necessary fixtures, screws, sealent wherever required and SS cover over patch fittings. Rate shall include necessary decarative film / LOGO. (FOR BRANCH & ATM ENTRY)	97.00	Sq.Ft.		
6	MAIN ENTRANCE DOOR				
	Providing & fixing in position Twin stile door made of 12mm thk. Toughen glass with necessary hardware fixtures of approved make & design, viz. patch fittings, on which the shutters are pivoted at the top & bottom,approved decorative tubular handles on both the faces, (Dorset or Godrej equivalent approx. 300mm long) complete as per direction. Rate should include etching of the Bank's logo & emblem on the Glass in the size & design as approved by the architect. (FOR ATM & BRANCH MAIN ENTRY)	59.00	Sq.ft.		
7	DOOR FRAME				

	Wood work in door with 1st. class hard wood frame fitted and fixed in position complete including a protective coat of painting at the contact surface of the frame including cost of concrete, Iron Butt Hinges and M.S clamps as required at site. (FOR BM CABIN, RECORD, SAFE RM, CASH & ATM UPS)	2.00	Cu.ft		
8	WALL/ COLUMN PANELLING				
	Providing & fixing in position wall / column panelling (Height upto False Ceiling Ht.) consisting of 6.0 mm thk. marine grade ply IS:710 with aluminium hat furring channel 22-25 @ 500 mm. both direction. The face of the cladding is to be laminated with 1.0 mm. thk. laminate of approved shade & groove design. The ply surface of the groove is to be melamine polish finished of approved colour. The item is to be completed in all respects as per design & approval of the architect. (FOR BM CABIN SIDE, OFF1,2 & BM CABIN FRONT COLUMN & ATM 2 SIDE WALL)	315.00	Sqft		
9	LOW HEIGHT PARTLY GLAZED PARTITIONS				
	Providing & Fixing double skin low ht. partition (1200 mm. high) with electrical wire management system, 900 mm. solid, then 300 mm. partly glazed (as per drawing), made out of aluminium hollow sections of 50mm x 50mm size 1.5mm thick of JINDAL / INDAL make as internal framed structure spaced not more than 600 mm. c/c bothways, double skin partition fixed to aluminium frame made of 6 mm. thk. approved marine grade ply (IS:710), finished both side with approved laminate with 1.5 mm. groove design, 4" high laminated skirting etc., the vertical support of 50 x 50 mm. frame to be extended upto 1200 mm., side & top faces to be covered with 65 x 15 mm. CP teak wood moulding bead (curved at top) with 6 mm. x 6 mm. polished groove. 300 mm. high x 10 mm. thk. glass to be fixed to partition with 30 x 12 mm. teak wooden bead with 6 mm. groove, all exposed teak wood surface to be completed with natural colour high polishing etc. all complete as per design, direction and approval of the Architect. (FOR OFF1,2,3,4 & MAY I HELP U SIDE)	61.00	Sqft		
10	FULL HEIGHT PARTLY GLAZED PARTITION				
	Specification same as 9 above except for 10mm approved make clear float glass shall be provided above 1' from ffl & false ceiling bottom 1' or as advised by architect with necessary steam beach moulding finished with melamine. Height upto False Ceiling & measurement taken up to false ceiling. (FOR BM CABIN)	188.00	Sqft		
11	FULL/ LOW HT. SOLID PARTITION				
a)	Providing and fixing in position full height (Up to false ceiling HT.) / low height (HT. 4') solid partition 65 mm thk. as indicated in the drawing excluding the door made out of aluminium hollow sections of 50mm x 50mm size 1.5mm thick of JINDAL / INDAL make as internal framed structure placed horizontally & vertically in 550 mm x 550 mm / 600mm x 600 mm center to center or as directed by the Architect. The alternate corner vertical members of the partition shall be taken upto the ceiling level and the same shall be anchored to the ceiling securely with help of suitable cleats. Framework shall be fixed with 6 mm thick marine grade ply (IS - 710) of approved make on both sides finished as per following specifications. The Partition shall be finished with 1.0 mm thick laminate of approved shade and make or equivalent on both the sides. Height upto False Ceiling & measurement taken up to false ceiling. Rate shall be inclusive of provision of pencil groove as directed by the Architect. The item does not include the doors. (FOR CASH BACK SIDE, RECORD & SAFE RM)	314.00	Sqft		

b)	Providing and fixing in position full height (Up to false ceiling HT.)/ low height (HT. 4') solid partition 65 mm thk. (same as above) but finished with one side 6 mm. ply & 1 mm. approved laminate & oter side with 6 mm. thk. Cement bonded particle board finished with necessary primer & distemper paint complete.ups room. (FOR ATM UPS)	61.00	Sqft		
12	CASH, SWO COUNTERS & CABIN				
a)	Providing fitting & fixing the cash counters along with partition all complete Providing fitting & fixing 2'6" wide & 2'6" high staff working top made of 18mm thick BWP block board of approved make finished with 1.0 mm laminate of approved make & shade.The customer transaction top shall be 1' wide projecting 6" on the customer side at a height of 1' above the staff working counter thus making a total height of 3'6". The customer top is made of 18 mm thick BWP block board which is finished with 1mm thick laminate. Both the staff working top & the transaction top is rested & supported together by a front Apron or Double skin partition with a recessed portion in the center of a panel of 1'6" height.				
	To achieve this niche, the Apron is made of aluminium hollow sections of 50mm x 50mm size 1.5mm thick of JINDAL / INDAL make (the spacing of horizontal members are as per shown in the detail design while the vertical members are at a necessary spacing of 2'0"c/c) placed in different orientation in different places to attain the niche. continued. This framework is covered with 6mm BWP ply of approved make & shade which is finished with 1.0 mm metallic laminate on the customer side facial of approved make & shade while the rear of the apron is finished with polish or paint as directed by the architect.There will be necessary grooves between two different decorative laminates as shown in the detail drawing & as directed.				
	Below the working top/counter will be 1'4" wide 3 nos. drawer unit on one side and wooden CPU rack on the other side with wooden key Board tray with slide channels & foot rest in between each of the counter. The front portion of each cash cage above the transaction.top (from 3'-6' to 7'0" height) will be provided with 2 nos. of 12 mm thick Toughned glass leaving a gap of 2" between the two glass panes so as to allow clear conversation between the customer & the cashier. The cut-out of 8"X4" is at the central bottom part of each of the transaction counter with a provision for small lockable latch wooden door.	5.00	Rft		
b)	CASH CAGE SIDE & INTERMEDIATE PARTITIONS				
	The intermediate/side partition between Cash Cabins will be of same specification as Partly-glazed Partition (ITEM NO. 9) up to 7'6" height. There will be provision for small trays windows for transferring of small copy either from the banking area to the cash cabins or between the cash cabins as directed by the architect. (FOR CASH LEFT SIDE)	63.00	Sqft		
13	PARTLY GLAZED FLUSH DOOR				

	Supplying & fixing in position 30 mm. thk solid core hot pressed phenol formaldehyde bonded partly glazed flush door shutter of approved make finished upto 900 mm with 1.0 mm thick laminate sheet of approved quality on both sides of the door shutter. The upper portion of the shutter is to be provided with 10 mm thick glass fixed with rubber wood glazing beads of approved design, complete as per drawing. Rate to include cost of hardware fittings e.g. handle locks, aldrep handles, door closer & night latch all of approved make as by the Architect. The exposed timber surfaces are to be polished in approved colour and finishing the same with N.C. lacquer in mat satin finish. (FOR BM CABIN)	18.00	Sqft		
14	SOLID CORE FLUSH DOOR				
	Providing and fixing Solid Core Flush Door Shutter (IS - 2202) of 30 mm thk. finished both side with 1 mm thk. approved colour laminate (IS : 2046) with 1.5 mm. groove design to be fixed to existing Wooden frame. The rate shall be inclusive of fitting and fixing of hinges, 1 no. Godrej make door closer, 1 no. CP finsh door stopper, screws, 1 no. Godrej cylindrical lock, tower bolt of approved make. All edges of the door to be covered with necessary lipping with polish finish. The work should be completed as per specification, design and approval of Architect.				
a)	Shutter size : 900/750/600 mm. x 2100 mm. with 250 x 125 mm. vision panel of 6 mm. glass(execept toilet door) (FOR RECORD, CASH, SAFE RM & ATM UPS)	136.00	Sqft		
15	WRITING LEDGE				
	Providing & fixing writing ledge 900 mm. long x 300 mm. wide x 150 mm. deep, as per design made out of 19mm BWP block board with necessary groove patterns 1.0mm laminate. A divider made of 19mm block board to be provided. White beach / white ceader lipping with natural polish to be used in all exposed areas, inside of writing ledge to be enamel painted. Top of ledge will be of 12 mm. thk. float glass. The work to be completed as per design and approval of the architect.	1.00	unit		
16	FREE STANDING TABLE				
	Providing & erecting in position free standing table made of 19 mm. thk. BWP grade block board for sides, top & panel, finished with 1 mm. thk. laminate of approved shade & make in outer faces. Inside of the table to be finished with synthetic enamel paint / polish as per matching tone. Drawer cum cabinet unit of approx. overall size of 400 x 600 x 725 mm. (h) of 19 mm. thk. block board. The drawer unit shall comprise of 1 tea tray, 3 drawer with inner faces polished with approved shade with telescopic drawer slides. the drawer unit shall be finished with 1 mm. laminate. The quoted price should include cost of teak wood moulding to edges, wood lipping, multipurpose locks of Godrej make & other necessary hardware accessories including SS handles, pvc wire manager, plywood keyboard tray, mobile CPU trolley, foot rest etc. of approved quality. All the ply edges should be lipped & finished with prescribed shade of polish. The rate also include the cost of hardwares like hinges, tower bolts, handles, magnets, wire manager, BANK LOGO etc.				
A)	Size - 6'X3'X2'6" including 10 mm. thk. Clear Float Glass at Top (FOR BM)	1.00	No.		
B)	Size - 5'X2'6"X2'6" (FOR OFF1, 2, 3 & 4)	4.00	No.		
C)	Size - 4'X2'6"X2'6" (FOR MAY I HELP U)	1.00	No.		
D)	Size - 3'X2'X2'6"	0.00	No.		

17	SIDE CABINET				
	Providing and erecting Side cabinet unit is of size 900 mm length, 450 mm deep & 750 mm high consisting of a 375 mm length of a side unit 3 sets of drawer i) top row of 100mm high drawers ii) 150 mm high drawer at middle & iii) 350 mm high drawer at bottom and 525 mm length cabinets with openable shutters, all finished in 1mm thk. Laminate. (FOR BM & OFF1, 3, 4)	32.50	sft		
18	STORAGE UNIT				
	Providing and fixing Storage Unit made out of 19 mm block board (IS : 1659) for top, sides & 6 mm. for back finished with 1.0mm laminate. The openable shutters to be made out of 19 mm block board finished outside with 1.0 mm laminate (IS : 2046). The cabinet will have shelves of clear ht. approx. 14". The shelves to be made of 19 mm. thk. block board. The necessary godrej multipurpose locks, 4" SS matt finished handles, hinges are to be provided. 4" laminated skirting to be provided. Inside of the unit to be synthetic enamel painted / polished in matching tone. All the exposed edges of the boards/ plywoods to be covered with white beach/ teak wooden lippings/ mouldings (6 x 20 mm.) duly natural polished all complete. The work to be completed as per approval and specification of the architect.				
a)	Low Height Storage (upto 750 mm. high) (FOR BM BACK SIDE)	28.00	Sq.ft		
b)	Full Height Storage (upto 2400 mm. high) (FOR RECORD RM & OFF1, 2 BACK SIDE)	144.00	Sq.ft		
c)	Over Head Storage (upto 750 mm. high)	0.00	Sq.ft		
19	FALSE CEILING WORK				
a)	Plain False Ceiling - Providing and fixing multi layered suspended type (Rawl Plug, M6X12 mm Hex Bolt & Hex Nut 27X37x25X1.6 mm Soffit Cleat Saint Gobin make or othr approved by bank for suspended from RCC ceiling) 12.5 mm thk. moisture resistant Glasroc H board or other approved equivalent make by Bank, coving and for column capitals in different levels firmly fixed on GI frame work section of M/s Saint Gobain or other approved equivalent make as per manufacturer's specifications all as required and directed by Bank's engineer finally boards are to jointed and finished so as to have flush look and leveling the board so as to be in one single plane which includes filling and finishing the board edges with jointing compound, paper tape etc. rate shall also include Painting the false ceiling surface with two or more coats of first quality 100% acrylic emulsion paint of approved make and shade over a coat of oil bound cement primer after adequate surface preparation, 1 or 2 coats of putty work over the entire Glasroc H board surface to get premium finish, etc. All complete as directed by Bank's engineer. Note: Rate shall include making cut out/ openings for fixing light fittings with necessary additional frame work, wastages, finishing etc. all complete. No deduction in area measurement will be made for openings not exceeding 0.4 sqm and no extra measurement will be made for forming such opening. Horizontal plan area and Side Elevation area for vertical drops will be measured for payment. (AS PER DRAWING).	474.00	Sq.ft.		

b)	<p>Grid false ceiling - Providing and fixing soft fiber ceiling solution of approved make with Silhouette frame work to form a module of 600 mm X 600 mm. The tiles shall be of 600mm X600mmX15mm like Armstrong Calassic RH95 Microlook tiles mineral fiber board NRC 0.55 or approved equivalent by Bank with fine fissured texture finish. The suspension system shall be as per the manufacturer (Armstrong or any other approved by Bank) specification. Installation consists of main runners securely fixed to structural soffit approved hanger at 1200 mm c/c (max), long cross 'T's inter locked between main runner at 600 mm c/c to form grid of 600 X 600 mm etc. complete all as per manufacturers' specification and as directed by Bank's Engineer. Note:- Rate shall include providing and erecting the necessary scaffolding at any level and height required during executing the work, cutout /opening to be made for light fittings etc. No deduction in area measurement will be made for openings not exceeding 0.4 sq m and no extra measurement will be made for forming such opening. Exposed area shall only be measured and paid for. (AS PER DRAWING)</p>	1067.00	Sq.ft.		
21	NOTICE BOARD:				
	<p>Providing and fixing soft board/ notice board fabricated out of 12mm BWR ply covered with 12mm soft board padding and upholstery propylene fabric @80/ mtr. Edges of the soft board should have white beach/white cedar moulding with natural polished. NB : where pin up board is in a panelled area, the top of the pin up board should be flushed with the panel, keeping the same level. The work should be completed as per design specification & approval of the architect.</p>	24.00	Sqft		
22	ROLLING SHUTTER ENCASEMENT				
	<p>Providing & fixing rolling shutters encasement with 3mm thick (0.5mm + 2 mm + 0.5mm) ACP in approved colours all complete with approved aluminium sub structure, aluminium brackets, silicon sealants, gaskets, PVDF coating in approved colour etc. all complete including bird/ vermin proof closer at the bottom and flashing at top, complete as per instructions & drawings. (FOR MAIN & ATM ENTRY ROLLING SHUTTER BOX ONLY)</p>	127.00	Sqft		
23	WICKET DOOR				
	<p>Supply fitting and fixing in position Swing Door 4' high with the following specifications: Vertical members - 2 numbers (50x50) mm size Horizontal Members 0-4 numbers (50x50) mm size Both sides of the frame work should be covered with 6 mm BWP grade ply with 1.00 mm laminate with locking arrangement, door stopper door closer etc. all the hardware fittings should be ISI mark etc. complete. (FOR OFF1 & OFF2 MIDDLE)</p>	13.00	Sqft		
24	ADDITIONAL ITEMS				
a)	<p>Providing & fixing synthetic door mats of approved shade from Birla 3M (6mm thk). The work to be completed as per approval of the Architect. (1.5 m. x 0.75 m.). (FOR MAIN ENTRY & TOILET AREA)</p>	2.00	unit		

b)	Providing and fixing Vertical blinds of 100 mm wide (Mac/Annums) of approved shade and pattern having handrail made of high strength alluminium alloyed wll thickness of 1.2 mm thk handrail to have 25mm decorative insert. Control unit shall be of derlin. The runners are also to be a derlin withantiflixtion adeshive. Spacers should be made of stainless steel. Febric should be polyester viscoted/polyester yarn having protective coating with chemicals for stain resistance & soilrepalancy. The rate shall include necessary scoch gurd treatment on both sides. The overlapping should be uniform and adequate. Necessary operative arrangements frames to be provided. The work to be completed asper specification and approval of the Architect. (FOR BM CABIN LEFT SIDE WALL & OFF4 BACK SIDE WINDOW)	173.00	Sqft		
25	CABINET FOR MAIN PANEL				
	Providing and erecting in position Cabinet for Electrical Main Panel made of 19 mm thick BWP garde blockboard as per drawing including intermediate shelves, locable shutter etc.confirming to the following specification: shutter faces shall finished with 1mm thick laminated sheet of same or combination shades as per instruction with polished 1 st class Teak Wood(6mmthick) edge lipping. Inner faces of shutters shall be finished with 1mm thick white laminate sheet. Shutters will be hung by auto-closing hinges of "Ebco" or equivalent. Locks, handles etc. will be approved variety & make. Inner surfaces of cabinet finished with 2 coats of synthetic enamel paint over a coat of approved primer. (Payment shall be on the on the area of cabinet face)	32.00	Sqft		
26	TACTILE PATH				
	Providing and fixing TACTILE Tiles of approved make, shade and pattern as shown in the drwng. / as aproved by Bank/ Architect. In CM 1:4 in proper line and level with out spacers for maintaining the grid lines. Rate shall be inclusive of providing and laying necessary PCC and Cement Mortar for a thickness of 3" and joint filling compound of the same shade of the tiles and including pop covering on the new flooring for the protection of tiles with base covering plastic. 300mm x 300mm type (approx.) (laying with approved tile adhesive) (FOR BRANCH ENTRY TO MAY I HELP U TABLE)	40.00	Sqft		
A	TOTAL EXCLUSIVE OF GST				
B	DISCOUNT IF ANY				
C	TOTAL AFTER DISCOUNT (C=A-B)				
D	GST				
E	TOTAL INCLUSIVE OF GST (E= C+D)				

APPROVED MAKE OF MATERIALS

1	False Ceiling / Channels	India Gypsum / Armstrong / Saint Gobain
2	Wood Frame Work / Wood Section : All Wood, Must be well seasoned, free from knots, other defects decay and defects due to handling and Transportation. Wherever necessary, provide with anti – termite Treatment.	Malaysian Sal / Kapoor
3	Wood Skirting / Moulding / Lipping / Bidding	White Beach / White Cedar / CP Teak
4	Wood Preservative	STP Pentaphene Pale / Termiseal by PCI / Bison by British Paint
5	Fire Reterdant Paint	Industrial grads of Noble / Viper
6	BWP Ply (IS : 710)	Century (excl. Sainik) / Globe BWP/ Sylvan / Green (excl. Ecotec)/ Kitply/ Apollo
7	Flush Door / BWP Block board (IS : 1659)	Century (excl. Sainik) / Globe BWP/ Sylvan / Green (excl. Ecotec) / Kitply/ Apollo
8	Laminate (1.0 mm thk.) (IS : 2046)	Green lam / Century mica / Sunmica/ Intim
9	Door Closure (Heavy Duty)	Godrej / Archi / Sterling (DC 2000)
10	Floor Spring (Heavy Duty)	Godrej / Archi / Sterling (FS 3000)
11	Door Lock (Dead)	Godrej / Hafele /Hettich / Kich / Doorset / Yale
12	Door Handles	Godrej / Hafele /Hettich / Kich / Doorset
13	Drawer / Storage Handle	Godrej / Hafele /Hettich / Kich / Doorset
14	Drawer / Storage Lock (Multipurpose)	Hafele /Hettich /Doorset
15	Night latch	Godrej / 4C Acme
16	Screws	GKW / Nettle fold
17	Hinges	CIEF / Hettich
18	Sliding Telescopic Drawer Channel	Ebco / Earl Behari / Efficient Gadjets
19	Cable Organiser	Ebco / Innofitt Systems (CM 63.C)
20	Adhesive	Fevicol SH / Fevimate TL
21	Soft Board	Jolly Board
22	Vertical Blinds	Mac / Annums / Window Fashion
23	Glass	Modi /AIS / Saint Gobain
24	Paints (Synthetic Enamel / Acrylic Emulsion)	Asain Paints / Berger / ICI
25	PVC Flooring	Krishna Vinyl / Armstrong / Birla
26	Texture Paint	Spectrum
27	Glass	Modi / AIS / Saint Gobain
28	European WC / Washbasin	Hindware /Parryware
29	Sanitary Fittings	Jaquar / Kohler
30	G.I. Pipe	Tata (Medium)
31	Cement	Ultratech / Laferge / ACC
32	Footmat	Birla 3M / Approved Equivalent
33	Vitrified Tiles	Johnson / Kajaria
34	Ceramic Tiles	Johnson / Kajaria
35	All other items not covered above	As per sample approved by Employer/Consultant

SEAL & SIGNATURE OF TENDERER