

BOQ FOR INTERIOR WORKS FOR CANARA BANK AT
RAJAHMUNDRY 2 BRANCH AND ATM

BOQ FOR INTERIORS, ELECTRICAL & DATA CABLING WORK FOR CANARA BANK AT RAJAHMUNDRY BRANCH, RAJAHMUNDRY RO					
S.N O	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
1	GYPSUM FALSE CEILING				
	<p>Providing and fixing suspended false ceiling as per approved design, with 12mm thick Gypsum Board screw-fixed to a G.I. framework, including all necessary hangers, supports, finishing, cut-outs, and painting complete in all respects as directed by the Architect/Bank.</p> <p>The framework shall consist of perimeter channels 0.55mm thick of size 20mm x 30mm fixed along the walls/partitions with nylon sleeves and screws at 600mm centre-to-centre, intermediate channels 0.90mm thick of size 45mm x 15mm suspended from the soffit at maximum 1220mm centre-to-centre, and ceiling sections 0.55mm thick with a web of 51.5mm, flanges of 26mm each and lips of 10.5mm fixed perpendicular to the intermediate channels at 457mm centre-to-centre. Suspension shall be provided using ceiling angles 0.55mm thick x 25mm x 10mm, fixed to the soffit with proprietary G.I. cleats and steel expansion fasteners. Gypsum Boards shall be fixed to the ceiling sections with 25mm drywall screws at 230mm centre-to-centre. Joints shall be finished using manufacturer's jointing tape and jointing compound, and the entire surface shall be sandpapered to achieve a smooth finish. The ceiling shall be finished with two to three coats of wall putty, followed by two to three coats of paint as required to achieve the desired finish. The rate shall include provision of all necessary cut-outs, grooves, mouldings and plain troughs for tube lights, downlighters, diffusers or other fittings as per the design. In cases where the RCC slab is old or of weak concrete, the G.I. suspenders shall be fixed with epoxy chemical anchoring and necessary load tests shall be carried out before fixing of the boards. No extra payment shall be made for epoxy chemical anchoring, vertical members, borders, or finishing works, and the quoted rate shall be deemed to be inclusive of all such requirements.</p>	Sft	1012		
2	GRID FALSE CEILING				
	<p>Providing & Fixing of Armstrong Mineral Fibre Acoustical Suspended Ceiling System with MINATUFF (MICRO LOOK) EDGE TILES WITH ARMSTRONG SILHOUETTE EXPOSED GRID. The tiles should have Humidity Resistance (RH) of 99%, NRC Upto 0.6, Light Reflectance >88%, Thermal Conductivity k = 0.052-0.057 w/m K, Colour White, Fire Performance Class 0/ Class 1 (BS476 Part 6&7) in module size of 600 X 600 X 16 mm with Bio Block coating on the face of the tile, impact resistant and suitable for Green Building application, with Recycled content of 63%.</p>	Sft	1389		
3	FULL HEIGHT PARTITIONS - SOLID				
	<p>Providing and fixing full height partitions made with Aluminium section framework of 2" x 1" x 1.5mm thickness with members placed at 2'-0" x 2'-0" c/c both vertically and horizontally. The frame shall be covered on both sides with 9mm BWR plywood (Century/Greenply/Amul Ply) and finished with 1mm thick laminate (Century/ Heritage/Aica/ Greenply) on both sides of the partition. The framework shall be properly fixed to the floor, and vertical members shall be firmly fixed to the slab and side walls wherever available. Laminate shall be provided in two or three colour combinations as per design. All works shall be executed as per the design suggested at site and instructions of the Engineer. (Framework above false ceiling required for fixity shall not be measured, but the contractor shall factor it in while quoting, as measurements will be taken only up to false ceiling level). Plywood wherever mentioned shall be BWR grade, IS:303, ISI-marked.</p>	Sft	462		
4	FULL HEIGHT PARTITIONS - PARTLY GLAZED				

**BOQ FOR INTERIOR WORKS FOR CANARA BANK AT
RAJAHMUNDRY 2 BRANCH AND ATM**

BOQ FOR INTERIORS, ELECTRICAL & DATA CABLING WORK FOR CANARA BANK AT RAJAHMUNDRY BRANCH, RAJAHMUNDRY RO					
S.N O	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
	Full Height Partitions: Same as Item No. 3, but with 9mm thick glass having etching design or one-way vision film, or as approved by the Bank. The glass shall be provided with 35mm x 12mm Steam Beech moulding, duly melamine polished. Work shall be executed as per the design and instructions of the Engineer. Plywood wherever mentioned shall be BWR grade, IS:303, ISI-marked (for Manager's Cabin).	Sft	329		
5	CASH CABIN PARTITIONS - PARTLY GLAZED				
	Full Height Partitions: Same as Item No. 3, but with 9mm thick glass having etching design or one-way vision film, or as approved by the Bank. The glass shall be provided with 35mm x 12mm Steam Beech moulding, duly melamine polished. All work shall be carried out as per the design and instructions of the Engineer. Plywood wherever mentioned shall be BWR grade, IS:303, ISI-marked. For Cash Cabin, the quoted rate shall include side and front partitions as	Sft	173		
	The door shall be provided with T.W. (teak wood) louvers finished in melamine polish of matching laminate colour. The door shall be fitted with Godrej Night Latch, and two wooden trays shall be provided as per the approved drawings. Necessary cut-outs shall be made in the glass for transaction purposes, and all edges of the cut-outs shall be finished in mirror polish. All exposed teak wood				
6	LOW HEIGHT PARTITIONS - PARTLY GLAZED				
	Low Height / Half Height Solid Partitions: Same as Item No. 3, but constructed to	Sft	128		
7	UPS ROOM - PARTITION				
	UPS Room Partition: Full height double-skin partition (3'-10" ht.) with aluminium	Sft	70		
8	STORAGE				
	Providing & fixing storage units made up 19 mm. thk. plywood framework, 9 mm. thk. plywood back as required as per design. Good quality blockboard shutters should be fixed on SS heavy hinges Storage units. should be finished with 1.0 mm. thk. laminate from external side & oil paint to non laminated surfaces. All exposed edges of plywood should have lipping patti on it. Lipping patti should be finished with French polish on it. The cost should include necessary handles, magnetic catches, Godrej make locks, tower bolts on doors etc. complete as per design. 8'- 0' ht HEIGHT STORAGE (Additinal COVER ALL BACK PORTION SHOULD BE 12MM CEMENT BOARD ADDITINAL)				
A	Full Height Storage	Sft	250		
B	Low Height Storage	Sft	150		
9	SIDE UNIT				
	Providing & fixing side unit made up of 19 mm. thk. plywood framework & 9mm.	Nos	2		
10	MAIN DOOR BRANCH & ATM				
	Providing and fixing main entrance door with fixed partition for Branch and ATM,	Sft	140		0
11	ROLLER BLINDS				
	Providing and fixing roller blinds (Vista make or equivalent) of 100mm louvers in approved shade, zebra type or pattern as suggested by the Bank, for banking hall and cabin windows. The blinds shall be treated with Scotch Guard on both sides, with uniform and adequate overlapping. All necessary operating arrangements and frames shall be provided. The work shall be completed in all respects as per specifications and approval of the Architect.	Sft	180		
12	NOTICE BOARD				
	Providing and fixing 12mm Soft Board display covered with felt and teak wood border of size 5'-0" x 4'-0".	Sft	35		
13	ACP CLADING				
	Providing & fixing in position Aluminium Composite Panel (ACP) with framing of Aluminium Tube sections of min 1.5" x 1" and 20 gauges 2'-0" C/C both ways. Joints to be finished with Silicon based sealant. ACP thickness of 3 mm minimum. Aluminium foil thickness to be min 0.20 mm, 2'-0" C/C both ways. ACP to be in 2' width panels or distributed equally. Alubond, Eurobond, Fujibond, Alcobond or equivalent ISO certified brands to be used. Trap door to be finished with ACP.	Sft	260		
14	SHUTTER BOX				
	Providing and fixing covering to rolling shutter and shutters for covering electrical	Sft	70		
15	COLUMN / WALL PANELLING				

**BOQ FOR INTERIOR WORKS FOR CANARA BANK AT
RAJAHMUNDRY 2 BRANCH AND ATM**

BOQ FOR INTERIORS, ELECTRICAL & DATA CABLING WORK FOR CANARA BANK AT RAJAHMUNDRY BRANCH, RAJAHMUNDRY RO					
S.N O	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
	Providing and fixing wall panelling consisting of 2x2 finished Aluminium section at maximum 2'- 0"C/C both horizontally and vertically treated with Pentapehene pale from STP as antitermite & fire retardent from Viper. To be fixed screwed on the existing walls.The frame work to be claded with 12mm with 1mm laminate of approved colour. The work to be completed in all respect as per drawing,specification and approval of the Architects.	Sft	1995		
16	ALLUMINIUM GRILL (CASH CABIN TOP & STRONG ROOM)				
	Providing and fixing aluminium grill with white or ivory powder coating, to be installed over the cash cabin top and above the strong room partition as per design. The grill shall be fabricated from approved aluminium sections, finished with durable powder coating, and securely fixed in position with necessary supports, screws and fixtures. The work shall be completed in all respects as per the drawings and instructions of the Architect/Bank.	Ls	2		
17	BOX FOR PANEL BOARD				
	Providing and fixing cupboard with shutters for covering electrical panel board, etc., with 19 mm BWR303 PLY with 1mm thick shell finish laminate of approved shade and make on outside including painting of inside with primer and two coats of synthetic enamel paint, and providing teak wood beading to all exposed edges, inside of the entire cupboard is to be fixed with the bison board (Fire Proof) to the existing ply wood including all accessories hinges, handles, ballcatches, etc., complete.	Sft	45		
18	MANAGER / OFFICER TABLE				
	Providing and fixing in position Manager's Table of size 5'-6"x 2'-6" as per drawing no.(6)/ Officer's Table of size 4'-6" x 2'-3" as per drawing no. (5) including Side Storage (Credenza) by using 25mm thick Black Board for top and 18 mm thk303 BWR ply for all other horizontal and vertical members. Telescopic CPU Stand/ ready made Keyboard tray shall be provided of approved model and make. Footrest made with T.W. member of size 4"x 1 ½ " finished with french polish. Side Storage (Credenza) as per drawing shall be provided. Facia of Side Storage (Credenza) shall be finished with 1mm thick laminates as shown in the drawing and all other sides shall be finished with white enamel paint. The Side Storage (Credenza) shall be provided with handles (Stainless Steel finish) and channels as per approval of the Project Consultant / Bank. All exposed Black Board surfaces to be finished with 1mm thk. laminate of approved make & shade, and all exposed edges of table top & ply verticals to have 1" x 1/4" T.W. lipping. All	Nos	1		
19	FRONT OFFICE COUNTER				
	Providing and fixing in position Cash Counter, 2'-9" wide, as per drawings (2-A, 2-B, 2-C, 2-D, 2-E & 2-F), complete in all respects. The working top shall be made with 25mm thick black board finished with 1.0mm thick laminate. The outer edge of the top shall have 1¼" x 1" teak wood moulding finished with melamine polish, while the inner edge shall be finished with ½" x 1" teak wood beading with melamine polish. Below the working top, the fascia (apron) shall be made with 12mm thick BWR IS:303 grade plywood, finished with 1.0mm laminate in two different shades, separated by a 1mm groove. A horizontal band (vertical drop) shall be provided on the fascia, made of 12mm plywood finished with laminate and provision for concealed lighting, with grooves at laminate joints. Above the working top, a glazed partition shall be provided with 12mm thick toughened glass, partly glazed and partly frosted, fixed with concealed stainless steel D-brackets as per drawings. The transaction top shall also be provided with 12mm thick toughened glass fixed horizontally, edges mirror-polished, moulded, and finished. A glazed cut-out of 8" x 4" shall be made in the glass partition for cash transaction, with mirror-polished edges. Further glazed panels of 12mm clear glass shall be fixed above the transaction opening, as per design, with all edges finished in mirror polish. At a height of 5'-11" above finished floor level, a boxing of 7'-7" overall height (10" x 10") shall be made with 19 mmBWR 303 PLY, finished with 1.0mm laminate, including provision of 6mm frosted glass. An additional 1'-9" high boxing (5" x 5") shall also be provided with 12mm thick BWR plywood finished with laminate. Vertical supports shall be made with 12mm thick BWR plywood, finished with white enamel paint. Each counter shall be provided with a telescopic CPU stand and a readymade keyboard tray of approved make. A footrest made of teak wood 4" x 1½" section, French polished, shall also be provided. Drawer units shall be made as per drawing, each fitted with multipurpose Godrej locks and vertical partitions for keeping currency. The facia of drawers shall be finished with 1.0mm laminate and the other surfaces painted with white enamel paint,	Rft	0		

**BOQ FOR INTERIOR WORKS FOR CANARA BANK AT
RAJAHMUNDRY 2 BRANCH AND ATM**

BOQ FOR INTERIORS, ELECTRICAL & DATA CABLING WORK FOR CANARA BANK AT RAJAHMUNDRY BRANCH, RAJAHMUNDRY RO					
S.N O	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
20	QUARTER GLASS (WITH TOUGHENED GLASS)				
	Providing and fixing quarter glass partitions for workstations, 1'-6" in height and 2'-0" in depth, made of 12mm thick toughened clear glass. All exposed edges of the glass shall be machine-polished to achieve a smooth, safe finish. The glass shall be securely fixed to the worktop/partition framework using approved stainless steel brackets or fittings, as per drawings and directions of the Architect/Bank. The work shall be completed in all respects, including fixing,	Rft	27		
21	STAFF TABLE WITH SIDE TABLE				
	Providing and fixing in position Staff Table of size 5'-6" x 2'-3" as per drawing No.				
	All exposed black board surfaces shall be finished with 1.0mm thick laminate of				
	Note: The table should match with concept of Canara bank in finish and color.				
A	Officers Table 5x2.5 Side Table 1.5x3	Nos	7		
B	Clerical Table 4.5x2.5 without Side Table 1.5x3	Nos	2		
22	CASH COUNTER WITH SIDE TABLE				
	Providing and fixing in position Cash Counter 2'-9" wide as per drawing No.(2-A, 2-B, 2-C, 2-D, 2-E, 2-F) comprising of the	Rft	5		
	i)Working top made with 25mm thick Black Board finished with 1mm thick				
	iii)Vertical drop (horizontal band) shall be provided on the facia below the working				
	vi)Glazed partition having height 1'.0" above the transaction top (in facia) shall, be provided with 12 mm thick glass (clear) with cut out of 8"x 4" as per drawing. The edges of cut out and the top edge of glass are to be mirror polished and to be fixed to partition as per fixing details and to boxing with concealed S. S. finished 'D' brackets as shown in the drawing.vii)Glazed partition provided with 12mm thick glass (Clear) above the slit to be fixed to partition as per fixing details and to boxing with concealed S. S. finished 'D' brackets as shown in the drawing. . The exposed edges shall be finished in mirror polish.viii) 7'-7" high Boxing (10"x 10") made with 19 mm thickBWR 303 PLY as per drawing with 1-6" horizontal extension at the top including providing and fixing 6 mm thick square frosted glass at a height of 5"-11" above Finished Floor level.				
	ix) 1'-9" high boxing (5"x 5") made with 12mm thk303 BWR ply with 1 mm thick				
23	FLUSH DOORS				
	Providing and fixing water proof solid core FLUSH DOORS shutters 35mm thk (TW wood beading of 0.5" x 1.25" to be provided all around) of approved make as per ISI specifications and 1mm thk shell finish laminate on both sides with vision hole cutting with 6mm thk plain glass as indicated. The shutter shall be fixed to existing partition frame work, necessary hardware fittings like brass butt hinges,door closers, mortice locks, tower bolts, handles etc.of approved make,	No	4		
24	Providing and fixing CHECK DROP/ SUGGESION BOX (1'-2"X1'- 2"X1'- 6"ht.) in	No	2		
25	Providing and fixing WRITING TABLE in 19mm thick BWR 303 PLY verticals and horizontals with 1.0mm thk shell finish laminate towards exposed side, with 12 mm thk plain glass for partition complete as shown in the drawing. All exposed ply surfaces to be painted with two coats of synthetic enamel paint on Black Board after one coat of primer.	No	1		
	TOTAL				
	DISCOUNT				
	GRAND TOTAL				

Sign & Seal of the Contractor : -

Name & Address of the contractor : -