

Internal

BOQ OF INTERIOR FURNISHING WORKS TO BE CARRY OUT IN THE PREMISES OF PRABHADEVI-II BRANCH RO SOUTH MUMBAI					
SL No.	Description	Qty	Unit	Rate	Amount
	PARTLY GLAZED FULL HEIGHT PARTITION				
1	Providing and fixing in position partly glazed full height partition work including door in frame work at 2' X 2' grid (horizontally and vertically) comprising of 2" X 1 1/2" 16 gauge Aluminum Framing section with 6mm plywood on both sides finished with 1mm thick high gloss laminates of various approved shades and colours. Item to include 6 mm thick glass with etching and frosting as per design to be fixed with 1-1/4" x 3/4" T.W. moulding / laminated beading finished with paint /polish as directed and 2" X 2" 16 gauge Aluminum Framing member for door sides and glass side and T.W. door frame to take 6mm thick glass with etching and frosting. All exposed surfaces to be finished in polish of matching laminate colour as directed including all necessary Stainless Steel finish fittings / hardware, door closers, Godrej locks and wood preservative paint etc. as per list of approved material and as approved by the Project consultant / bank complete in all respects. (Note : In case of false ceiling, the vertical supporting members to be fixed with pucca ceiling but the area of partition payable will be below the false ceiling only).	350	Sq.ft.		
	PARTLY GLAZED PARTITION FOR CASH CABINS				
2	Providing, making & fixing partly glazed partition including door to Cash cubicals with frame work at 2' X 2' grid (horizontally and vertically) comprising of 2" X 1 1/2" 16 gauge Aluminum Framing section and / or as per frame work with 6mm plywood on both sides finished with 1mm thick laminates of approved make and colour as shown in drawings up-to 3'0"/4'0" height and 2" X 2" 16 gauge Aluminum member for door sides. Item to include 6 mm thick glass with etching and frosting as per design above 3'0"/4'0" to be fixed with 1-1/4" x 3/4" T.W. moulding finished with polish as directed including openings for passbook printers, registers etc. all exposed T.W. surfaces to be finished in polish of matching laminate colour as directed including shutters with C.P.T.W. member of size 3" x 1" for styles, 4" x 1" for bottom rails and 5" x 1" for lock rail, including 6mm thick Commercial plywood on both sides for lower panel and 6mm thk clear glass of approved make with etching to be fixed with 1" x3/4" T.W. moulding, shutter to be finished with 1mm thick laminates of approved make and colour and to be fixed to partition with 3 Nos. 4' x 1-1/4" brass hinges, Godrej night latch, handle and wood preservative paint etc. as per list of approved material and as approved by the Project consultant / bank complete in all respects.	60	Sq.ft.		
	SOLID FULL HEIGHT PARTITION				

Internal

Internal

3	Providing and fixing in position solid Full height partition in frame work including door in 2' X 2' grid (horizontally and vertically) comprising of 2" X 1 1/2" 16 gauge Aluminum Framing section with 6mm thick plywood on both sides finished with 1mm thick multi colour high gloss laminates of approved make and colour. Item to include 2" X 2" 16 gauge Aluminum Framing member for door frame. All exposed surfaces to be finished in polish of matching laminate colour as directed including all necessary Stainless steel finish fittings/ hardware, door closers, Godrej locks and wood preservative paint etc. as per list of approved material and as approved by the Project Consultant / Bank complete in all respects. (Note : In case of false ceiling, the vertical supporting members to be fixed with pucca ceiling but the area of partition payable will be below the false ceiling only)	525	Sq.ft.		
PARTLY GLAZED LOW HEIGHT PARTITION.					
4	Providing and fixing in position partly glazed low height partition (2 1/2" thick) in frame work with 16 gauge Aluminum Framing members at 2' c/c and 3 horizontal members at equal distance comprising of 2" X 1 1/2" 16 gauge Aluminum Framing Section with 6mm plywood on both sides finished with 1mm thick multi colour high gloss laminates of approved make and shade including 12mm thick glass (clear/ frosted) to be fixed as shown in drawing. The exposed edges of the glass to be finished in mirror polish. T.W. runner should be polished in matching colour of laminate etc. complete in all respects.	100	Sq.ft.		
FULL HEIGHT 12 MM THK TOUGHNED GLASS PARTITION					
5	Providing and fixing 12mm thick Toughned glass partition upto 8 ft and above solid partition as per design and door fixed with patch fittings of approved make/ brand at top to a support directly suspended from main ceiling (Rate to include necessary support arrangement to erect the clear glass partition) and for bottom on floor with profile ,including floor spring, 'C' shape approved design brush finished S. S. handle,locking arrangement etc. including acid etching / frosting of approved design, on the glass. All exposed edges of glass to be machine polished. Complete as per design and instructions by Architect/ Engineer. (For measurement area, from finished floor level to finished false ceiling level will be considered)	240	Sq.ft.		
12 MM THK GLASS RAILING ABOVE COUNTER					
6	Providing and fixing 12 mm thick glass with etching & edge polish to be fixed with 1 1/4" x 3/4" T.W. moulding / laminated beading finished with paint/ polish as directed above counter fixed to wall/partition including 2 1/2" wide round slits opening in the glass as per detail drawing.	50	Sq.ft.		
MODULAR FRONT OFFICE COUNTER					
7	Providing and fixing in position Modular Front Office Counter 2'-6" wide at 2'6" ht; 12 mm thk. glass with film for customer top 6" wide at 4'0" ht. and vertical 12mm thk. Glass with film 18" high above writing top as per drawing comprising of the following complete in all respects:-	20	R.ft.		
	i) Working top at 2'6" level made with 18mm thick plywood finished with 1mm thick laminates of approved make and shade and all other sides shall be finished with 0.8 mm thk high gloss Laminate. Outside edge of the working top shall be provided with 1 1/4" X 1" Teak wood moulding finished with Laminate. Inside edge will be provided with 1/2" X 3/4" T.W. beading patti with laminate.				
	ii) Customer top at 4'0" level 12" wide made of 12 mm thick glass with machine polish on all sides, supported by 12 mm thk. Glass 1'6" high.				

Internal

Internal

	iii) Vertical facia (Apron) made with 18mm thick plywood boxing finished with 1mm thick laminates of approved make and shade with 1mm thick groove at the joint of laminates of two different shades.			
	iv) Vertical drop (horizontal band) shall be provided on the facia below the working top made with 18mm thick plywood finished with 1mm thick laminates of approved make and shade with plywood finished with 1mm thick laminates of approved make and shade with provision for concealed light 1mm thick groove shall be provided at the joint of two different shades of laminate.			
	v) Vertical supports made with 18mm thick plywood finished with white enamel paint.			
	vi) Telescopic CPU stand / ready made Keyboard tray / wire manager shall be provided of approved model and make			
	vii) Footrest made with T.W. member of size 4" X 1 1/2" finished with French polish.			
	viii) Drawer box unit comprising of three drawers on powder coated channels, one of size 1'4" W x 6" H x 2'0" D and two big drawers as per drawing shall be provided with multipurpose Godrej locks in each drawer. Facia of drawer unit shall be finished with 1mm thick laminates of approved make and shade and all other sides shall be finished with 0.8 mm thk Laminate. The drawers will be provided with handles (Stainless steel finish) and channels as per approval of the project consultant / Bank.			
	ix) Boxing as per drawing made with 12mm thick plywood finished with Synthetic enamel paint shall be provided below the table top for electrical conduiting and at the bottom for the LAN cabling / Telephone wire conduiting.			
	The item to include all necessary hardware and fittings in Stainless steel finish, lipping to all edges and making provision only for electrical fitting behind the front. Vertical drop as shown in the drawing. Necessary beadings with polish for fixing the glass are to be provided.			
	MODULAR CASH COUNTER			
8	Providing and fixing in position Modular Cash Counter 2'-6" wide at 2'6" ht; 12 mm thk. glass with film for customer top 16" wide at 4'0" ht. and vertical 12mm thk. Glass with film 18" high above writing top as per drawing comprising of the following complete in all respects:-	5	R.ft.	
	i) Working top at 2'6" level made with 18mm thick plywood finished with 1mm thick laminates of approved make and shade and all other sides shall be finished with 0.8 mm thk Laminate. Outside edge of the working top shall be provided with 11/4" X 1" Teak wood moulding finished with high gloss laminate. Inside edge will be provided with 1/2" X 3/4" T.W. beading patti with laminate.			
	ii) Customer top at 4'0" level 16" wide made of 12 mm thick glass with machine polish on all sides, supported by 12 mm thk. Glass 1'6" high.			
	iii) Vertical facia (Apron) made with 18mm thick plywood finished with 1mm thick laminates of approved make and shade with 1mm thick groove at the joint of laminates of two different shades.			
	iv) Vertical drop (horizontal band) shall be provided on the facia below the working top made with 18mm thick plywood finished with 1mm thick laminates of approved make and shade with plywood finished with 1mm thick high gloss laminates of approved make and shade with provision for concealed light 1mm thick groove shall be provided at the joint of two different shades of laminate.			
	v) Vertical supports made with 18mm thick plywood finished with white enamel paint.			
	vi) Telescopic CPU stand / ready made Keyboard tray / wire manager shall be provided of approved model and make			

Internal

Internal

	vii) Footrest made with T.W. member of size 4" X 1 1/2" finished with French polish.				
	viii) Drawer box unit comprising of three drawers on powder coated channels, one of size 1'4" W x 6" H x 2'0" D and two big drawers as per drawing shall be provided with multipurpose Godrej locks in each drawer. Facia of drawer unit shall be finished with 1mm thick laminates of approved make and shade and all other sides shall be finished with 0.8 mm thk Laminate. The drawers will be provided with handles (Stainless steel finish) and channels as per approval of the project consultant / Bank.				
	ix) Boxing as per drawing made with 12mm thick plywood finished with Synthetic enamel paint shall be provided below the table top for electrical conduiting and at the bottom for the LAN cabling / Telephone wire conduiting.				
	The item to include all necessary hardware and fittings in Stainless steel finish, lipping to all edges and making provision only for electrical fitting behind the front. Vertical drop as shown in the drawing. Necessary beadings with polish for fixing the glass are to be provided as per drawing / as directed.				
	MODULAR MANAGER'S TABLE WITH SIDE TABLE				
9	Providing and fixing in position Modular Manager's Table of size 6'-0" X 3'-0" as per drawing including side storage (Credenza) by using 25mm thick plywood for top and 18mm thick plywood for top and 18mm thick plywood for all other horizontal and vertical members. Telescopic CPU Stand / ready made keyboard tray shall be provided of approved model and make. Footrest made with T.W. member of size 4" X 1 1/2" finished with Laminate & all exposed plywood of table shall be finished with 1mm thick high gloss laminates of approved make and shades as shown in the drawing and all other sides shall be finished with 0.8 mm thk Laminate.	2	Nos.		
	Drawer units as per drawing shall be provided with multipurpose Godrej locks in each drawer. Facia of drawer unit shall be finished with 1mm thick laminates of approved make and shade and all other sides shall be finished with 0.8 mm thk high gloss Laminate. The drawers will be provided with handles (Stainless steel finish) and channels as per approval of the Project Consultant / Bank.				
	The side Storage (Credenza) shall be provided with handles (Stainless Steel finish) and channels as per approval of the Project consultant / Bank. All exposed plywood surfaces to be finished with 1mm thick laminates of approved make and shade of approved make and shade, and all exposed edges of table top and ply verticals to have 1" and 1/4" T.W. lipping. All exposed T.W. sections to be Laminated and internal surfaces to have 0.8 mm thk high gloss Laminate as directed. Item to include plywood boxing, all necessary hardware and fittings in Stainless Steel finish, lipping to all edges etc. complete in all respects.				
	MODULAR OFFICER TABLE WITH SIDE TABLE				
10	Providing and fixing in position Modular Officer Table of size 4'-6" X 2'-3" as per drawing including side storage (Credenza) by using 25mm thick plywood for top and 18mm thick plywood for top and 18mm thick plywood for all other horizontal and vertical members. Telescopic CPU Stand / ready made keyboard tray shall be provided of approved model and make. Footrest made with T.W. member of size 4" X 1 1/2" finished with French polish & all exposed plywood of table shall be finished with 1mm thick high gloss laminates of approved make and shades as shown in the drawing and all other sides shall be finished with 0.8 mm thk Laminate.	7	Nos.		

Internal

Internal

	Drawer units as per drawing shall be provided with multipurpose Godrej locks in each drawer. Facia of drawer unit shall be finished with 1mm thick laminates of approved make and shade and all other sides shall be finished with 0.8 mm thk high gloss Laminate. The drawers will be provided with handles (Stainless steel finish) and channels as per approval of the Project Consultant / Bank.			
	The side Storage (Credenza) shall be provided with handles (Stainless Steel finish) and channels as per approval of the Project consultant / Bank. All exposed plywood surfaces to be finished with 1mm thick laminates of approved make and shade of approved make and shade, and all exposed edges of table top and ply verticals to have 1" and ¼" T.W. lipping. All exposed T.W. sections to be Laminated and internal surfaces to have 0.8 mm thk high gloss Laminate as directed. Item to include plywood boxing, all necessary hardware and fittings in Stainless Steel finish, lipping to all edges etc. complete in all respects.			
	WICKET GATE			
11	Providing & fixing wicket gate to counter / wall out of 1-1/2" x 1-1/2" C.P.T.W. frame with 6mm thick Commercial plywood on both sides finished with 1mm thick high gloss laminates of approved make and shade, with heavy duty brass hinges, bolt, handle etc. complete as per design.	1	Nos.	
	COUNTING/ RUNNING TABLE			
12	Providing & fixing counting/ running Table 2'0" wide as per layout with 25mm thick plywood for top and 18mm thick plywood for all other horizontal and vertical members as per design including footrest and storage box with 5" high drawer on channel with locking arrangement. All exposed plywood of table shall be finished with 1mm thick high gloss laminates of approved make and shades as shown in drawings and all other sides shall be finished with 0.8 mm thk Laminate as per Architect's instructions.	32	R.ft.	
	FULL HEIGHT STORAGE / LOW HEIGHT STORAGE			
	Providing and fixing in position full height storage / low height storage / back storage (credenza) of different size and depth as shown in drg. using plywood of required thickness finished with 1mm thick High Gloss laminates of approved make and shades as shown in the drawing and all other sides shall be finished with 0.8 mm thk Laminate as detailed therein.			
	The storage units shall be provided with handles (Stainless Steel finish), brass hinges and locking arrangement as per approval of the Project Consultant / Bank.			
	All exposed plywood surfaces to be finished with 1mm thick high gloss laminates of approved make and shade of approved make and shade all exposed edges of plywood to have 1" X ¼" T.W. lipping. All exposed T.W. sections to be polished in matching colour laminate and internal surfaces to have 0.8mm thick laminate as directed. Item to include all necessary hardware and fittings in Stainless Steel finish, Godrej multi purpose locks including magnetic ball catcher etc. complete in all respects.			
13	FULL HEIGHT STORAGE SPECS AS ABOVE	200	Sq.ft.	
14	LOW HEIGHT STORAGE SPECS AS ABOVE	50	Sq.ft.	
	WRITING DESK			
15	Providing & fixing writing desk made out of 19 mm thick commercial ply finished with 1mm thick high gloss laminates of approved make and shade from all exposed sides as per detail drawing including 12 mm thick glass with polished edge fixed on writing top with box. Size 3'0"x 1'6	2	Nos.	
	SOFT BOARD			
16	Providing and fixing 1/2" thick soft board to be fixed on 6mm thick ply & to be covered with woolen felt of approved colour including side lipping patti etc. complete.	40	Sq.ft.	

Internal

Internal

PANELING TO COLUMNS & WALLS					
17	Providing & making paneling with 12 mm thk plywood or 6 mm thk. Plywood & T.W. members at 24" c/c finished with 1mm thick high gloss laminates of approved make and shade as specified by Bank etc. complete.	1000	Sq.ft.		
KEY HANGING CUPBOARD					
18	Providing & making key hanging cupboard with 3/4" thk. Commercial ply and 6mm thk ply for back as per detailed drawing including brass hinges, handles and locking arrangement, all exposed surfaces to be finished with 1mm thick laminates of approved make and shade & 0.8 mm thk Laminate from inside.	1	Nos.		
ENTRANCE DOOR					
19	Prov. & fix.toughned glass partition with Door with 12mm. thk. toughened Glass with matching horizontal etched linings of 1" frost & 1/2" clear as per design. The rate should be inclusive all hard wares like S.S. finished Patch fitting Hinges, Bottom floor Lock, Floor spring Enox, Ozone, Haffele, Dorma make etc.complete, 1'-6" ht. Matt steel handle etc.complete as per the designs and details form the Architects. The Rate shall be inclusive of Horizontal Etched Linings In between 3' to 6' ht.,horizontal etched linings of 1" frost & 1/2" clear as per design & Top/ Bottom Wooden Members with matching Composite sheet of 6" ht if required.	105	Sq.ft.		
Glass on table top					
20	Providing and placing 12mm thk glass on Manager Table including hole for wire manager, machine cut edge polish etc. complete.	1	Nos.		
CHEQUE DROP BOX/ SUGGESTION BOX					
21	Providing & making Cheque drop box/ Suggestion Box with acrylic as per detailed drawing including hinges, handles and locking arrangement.	2	Nos.		
LAMINATE FIXING					
22	Providing and fixing 4mm plywood on partition including doors, storage including shutters & sides finished with 1mm thick high gloss laminates of approved shade and colour. All exposed T.W. surfaces to be finished in polish of matching laminate colour as directed including all necessary Stainless Steel finish fittings / hardware, handles, locks and wood preservative paint etc. as per list of approved material and as approved by the Project consultant / bank complete in all respects.	500	Sq.ft.		
ACP PANELING					
21	Providing, fabricating & fixing in position Aluminium Composite Panel (ACP) with framing of Aluminium Tube sections of min 2" x 1" and 20 gauges 2'-0" C/C both ways. ACP to be in minimum 2' width panels or distributed equally as per the site condition. Panels to be fixed to the frame with adhesives as per standard brands mentioned in Annexure B. Joints shall be finished with Silicon based sealant. ACP shall be of minimum 4mm thickness (0.5mm+3mm+0.5mm). Colour of ACP shall be as per bank's preference. Additional Aluminium Sections to be provided to fix the AC units near the machine area at the highest position.(Unit of measurement shall be in Sqft)	100	Sq.ft.		
B FALSE CEILING WORK					
FALSE CEILING (ARMSTRONG) Shillhoutted typr Grid					

Internal

Internal

1	Providing and fixing in position false ceiling in Armstrong 600 X 600 mm X 15/16 mm Dune Supreme RH 99 Prima tile with Tegular Edge framework having black groove as specified by Armstrong Co. with suspenders wherever required. Making necessary framework for A.C. ducting, if any, and necessary cutouts for diffusers and light fittings, taping and finishing to proper line and level, including making grooves and trap doors for A.C. unit in 18mm thick M.R. Grade Plywood with Stainless Steel hinges and locks with moulding 1" X 1" for edges including finishing with White Plastic Emulsion Paint etc. complete in all respect. (Note :- Only the plan area will be measured for payment. No extra payment will be made for cutouts, grooves, mouldings etc.)	984	Sq.ft.		
FALSE CEILING (GYPSUM BOARDS)					
2	Providing and fixing in position false ceiling in Gypboard 12mm thick for horizontals and verticals fixed over G.I. framework as specified by India Gypsm Co. Ltd. including trap door for A.C. unit in 18mm thick M.R. Grade Plywood with Stainless Steel hinges and locks with moulding 1" X 1" for edges including finishing with White Plastic Emulsion Paint etc. complete in all respects. (Note :- Only the plan area will be measured for payment. No extra payment will be made for cutouts, grooves, moulding, etc.)	2000	Sq.ft.		
GRAND TOTAL (GST EXTRA)					
<p>NOTE: Kindly use only High Gloss Laminate. dismantling works of old furniture items viz. work station, panelling, ceiling, partitions etc and removing of serviceable material will be in the scope of qualified L1 bidder only. The above quantities are approximately taken for estimation purpose they may increase or decrease. Contractor will be paid for actual work executes against each item. Brief specifications are given for each item. Minor verification in design and specification for each item are likely for which no extra payment will be given. Any of these items may be cancelled.</p>					
<p>NOTE: Cost inclusive of all taxes other than GST, Transportation, loading, unloading expenses, Excise Duty etc. without any extra charge. The Contractor estimate shall also include MMC / Local Authorities Permission for smooth functioning the work.</p>					

Internal