

CANARA BANK								
CIRCLE OFFICE TIRUPATI								
BOQ INTERIOR WORKS FOR CANARA BANK AT ALTERNATE PREMISES OF VELGODU BRANCH & ATM								
A	SCHEDULE - 'A' (FURNISHING WORK)				UNIT	QTY.	RATE	AMOUNT
S.NO.	DESCRIPTION				UNIT	QTY.	RATE	AMOUNT
1	<b>SUSPENDED FALSE CEILING</b>							
1.1	<b>FALSE CEILING ( GYPSUM BOARD)</b>				Sq.Ft.	500		
	Providing and fixing Gypsum false ceiling as per drawing including of providing and fixing G.I. Frame work shall comprise of 0.50 mm thick G.I. perimeter channel (MF-6A) having one flange of 19.6mm and other flange shall be of 29.6mm and a web of 26.6mm along with perimeter of ceiling, screw will be fixed to the beam with the required curvature with nylon sleeves. screws will not at exceeding 610mm centers. Then suspending G.I. intermediate channel (MF-7) of size 45mm, 0.9mm thick with two flanges of 15mm each bent at the required curvature by cutting both its flanges. Suitable bracing to be provided where ever the flanges are cut with 0.9mm G.I. Flat and nuts and bolts at specific positions and thereafter at 1220mm centers with ceiling angle of width 25mm x 10mm x 0.50mm thick fixed to soffit with G.I. cleats and steel expansion fasteners as per specification of India gypsum at a distance of 2'0" c/c both ways complete with 12.5mm board and all necessary perimeter channels etc. The joints to be properly mended with paper tapes and gypsum compound all . The boards are to be jointed and finished which includes filling and finishing the tapered and square edges of the boards with jointing compound and fiber tape suitable for Gypsum board. A layer up to of 3.00mm thickness of Veneer Plaster is applied followed by two coats of topcoat (primer) at the face of board to give smooth seamless finish. 2 or more coats of plastic emulsion paint (roller finish) of approved shade and make shall be applied. The rate should include the full completion of the ceiling. At the time of handing over the site all necessary repairing work to be considered if required. The work will be completed as per instructions of the bank. No extra payment will be made for the cutting of light points , stain glass, cove lighting, designs within the area counted etc.							
1.2	<b>FALSE CEILING (ARMSTRONG CEILINGS – FINE FISSURED MICROLOOK EDGE WITH SILHOUETTE GRID (BLACK REVEAL)</b>				Sq.Ft.	1200		
	Providing and fixing false ceiling system manufactured by M/s Armstrong World Industries. Using hot dipped galvanized steel section, rotary stitched main tee of size 15mm x 42 mm web height having 0.36 mm gauge at every 600 mm centre to centre maximum and rotary stitched cross tee of size 15 mm x 42 mm having 0.33 mm gauge at every 600mm c/c and wall angle of size 19 x 19 mm having 0.35 mm gauge fixed to the periphery of the wall. The above grid is suspended at every 600mm c/c in both directions using 2.0 mm thick pre-straightened GI wire laying FINE FISSURED MICROLOOK WITH SILHOUETTE GRID (BLACK REVEAL) ceiling tiles manufactured by M/s Armstrong World Industries, of size 600mmx600mmx15mm having NRC 0.55 Light reflectance of >84% (WT), thermal conductivity k = 0.052-0.057 W/m0K, Humidity Resistance of 99% , having Fire Performance CLASS O / CLASS 1 (BS 476) the grid surface having 3 Fine Fissured coats of white. The back of formed grid tile should have filled with sand and polished with one layer protective paint. (Branch & ATM)							
2	<b>PARTITIONS WORK</b>							
2.1	<b>FULL HEIGHT SOLID PARTITION(Record Room, Strong Room)</b>				Sq.Ft.	320		
	Full height Solid Partition including flush door & strong room partition up to 7' only :- Providing and fixing solid partition the outer framing shall made out of aluminium hollow section of 65mm x 37mm size 1.0 mm thick of JINDAL / INDAL and Internal frame structure will placed at max distance of 2'-0" x 2'-0" center to center horizontally and vertically. Fix 12 mm thick BWR Grade Plywood with 1.0mm thick laminate top on both sides with approved shade in groove pattern as per instructions of architect. The rate will include the cost of providing skirting of 100mm wide lined with 1mm thk laminate and providing & fixing a border at top of 100mm wide lined with 1mm thk laminate complete. Laminate Should be considered up to two or three color combination. The edge beadings with steam beach wood should be finished with melamine polish if required, Frame should be properly fixed to the Floor, Vertical members should be firmly to the Slab and side wall available, frame work above false ceiling done shall not be measured but contractor may factor it while quoting there rates as measurement shall be taken up to false ceiling lvl. <b>The rate inclusive of providing &amp; fixing of required flush door of 37mm thick approx. with 1.0mm th. laminate both side</b> with steem beech wood chowkhat of size 75mm x 65mm approx and Item includes Heavy-duty SS ball bearing butt hinges 100 x 5.5 mm (4 Nos. per shutter) with screws etc. <b>The door should have a automatic door closer, door stopper, SS Handle and lock of the approved make.</b> The shade of laminate finish to be got approved from Bank. Plywood wherever mentioned Must be BWR GRADE AND IS 303, MARKED ISL.. All as per the design and instructions of Bank.							
	Note :- For the purpose of payment partition shall be measured including the area of door/door frames up to false ceiling height only.							
	Framework shall be regidly secured to floor, bottom of slab & existng walls at 2'-0" c/c with dash fasteners. Contractor may factor it while quoting the rates.							
2.3	<b>Partition with one side laminate &amp; other with Cement Board ( UPS room side)</b>				Sq.Ft.	150		
	As of the above, the skin of the partition shall be made out of 10mm thick cement fiber board and finished with 2 coats of ivory white enamel paint after application of PUTTY on the internal side (not visible from the customer lobby) and with 12mm thick BWR grade Plywood with 1mm thick laminate of approved shade and scheme on the customer side (visible to customers). The rate quoted must be inclusive of the providing one pane door for UPS room (Size - 7'-0" x 2'-9") & 2 panes door (Size-7'-0" x 2'-0" for electrical panel) or door sizes as per site requirements in combination of 6mm thk cement fibre board and 19mm thick approved block board pasted / screwed together to form a single entity and finished as per matching scheme. The block board shall be on the outer side and shall be pasted with 1.0 mm thick matt laminate along with matching skirting & top bands as per bank's scheme and the cement fiber side of the door shall be on the inside with 2 coats ivory white enamel paint over a coat of primer. All the painted areas and gaps etc should be properly finished with putty for smooth finish. Exposed edge of door thickness shall be finished with teakwood lipping & melamine polish. All the doors should have proper SS handles and locking system. The doors used for the electrical panel boards should have ss grills min 4 nos for the proper ventilation and passage of air.							
2.4	<b>Full Height Partially Glazed partition (BM Cabin, Discussion Room &amp; Cash Cabin upto 7'Height)</b>				Sq.Ft.	300		
	Same as of Solid ht partition , providing <b>8mm thick toughened glass</b> (Modi/saint Gobin) above 1'-0" / 3'-0" & up to 7'-0" fixed with steam beech wood beading of finished size 1 1/2" X 1" all along the edge. All edge-to-edge glass joint to be machine cut and polished and sealed with silicon sealant. Joint shall be located strictly as shown in the drawing. All exposed woodwork to be malamine polished. Item includes frosted/striped/designer glass film of 3m, Avery Dennison or equivalent ( basic rate of Flim Rs. 50/ Sq.ft. ) on existing glass as per manufacturer's specifications. All as per the design and instruction of Bank.							

CANARA BANK						
CIRCLE OFFICE TIRUPATI						
BOQ INTERIOR WORKS FOR CANARA BANK AT ALTERNATE PREMISES OF VELGODU BRANCH & ATM						
A	SCHEDULE - 'A' (FURNISHING WORK)					
S.NO.	DESCRIPTION	UNIT	QTY.	RATE	AMOUNT	
2.5	<b>Low. Height Semi Glazed Partition</b>	Sq.Ft.	128			
	Same as above but of Low height as per design including 10mm Toughened glass with edges polished to be used. All other specs are same as of above, Edges of the partition to be covered with 3" X 1.5" Steam beech wood duly malamine polished moulding. 38mm thick flush door: wicket gate also shall be included for a measurement. All as per the design and instruction of bank engineer/architect.					
2.6	<b>Glazed Partition(Counter Front Glass)</b>	Sq.Ft.	70			
	Providing & fixing 10mm thick toughened clear glass to shape for front side of the cash counters including cutting the holes and providing & fixing TW beading polished and tinted to approved shade. ( including SWO/Chief Cashier front Glass including the lock for glass opening during close of cash etc).					
2.7	<b>ACP WALL PANELLING (ATM )</b>	Sq.Ft.	250.00			
	Providing & fixing in position ACP (Aluminium Composite Panel) with framing of Aluminium Tube sections of min 1.5"x 1" and 20 gauge 2'-0" C/C both ways. ACP to be in 2' wide panels or distributed equally. Panels to be fixed to the frame with 3M or equi-valent adhesive. Joints to be finished with Silicon based sealant. Minimum ACP thickness-3 mm. Aluminum foil thickness to be min 0.25 mm on both sides. Alubond, Eurobond, Fujibond, Alcobond or equivalent ISO certified or approved brands to be used. White (IVORY) & Blue to be as per bank's approval. Additional Sections to be provided to fix the Indoor AC units. Both AC units to be installed near the machine area at the highest position. The rate shall be included for providing proper access panel for ATM power point and shall have proper locking arrangement for plug point by providing additional framing. ( The measurement shall be made up to falseceiling).					
3	<b>DOOR &amp; ACCESSORIES</b>					
3.1	<b>Main Entrance Door PT Door</b>	Sq.Ft.	63			
	Providing and fixing toughend glass door shutters of 12mm thickness in opening of glazed partitions with stainless steel patch fittings of approved make ( DORMA/ DLINE / GEZE or approved equivalent) including heavy duty double action floor-spring with steel cover plate of approved make, pull handle SS brushed finishes 24" long thick 25mm on both sides of door shutters, locking arrangement of Dorma / D Line or equivalent or better quality as approved by Engineer-in-charge. Exposed edges of glass shall be machine cut & polished. Cost includes cutting and making good the floor, walls, ceiling etc. for fixing floor spring and patch fittings. All complete as per approval of the Architect.					
3.2	<b>Main Entrance Fixed PT Glazing</b>	Sq.Ft.	90			
	Providing and fixing toughend glass partition of 12mm thickness with stainless steel patch fittings of approved make ( DORMA/ DLINE / GEZE or approved equivalent as approved by Engineer-in-charge. Exposed edges of glass shall be machine cut & polished. Cost includes cutting and making the floor, walls, ceiling etc. good for fixing patch fittings. All complete as per approval of the Architect.					
3.5	Supplying and fixing of door stopper SS Grade 304, HESSF-2C hardwvn make.	Nos	0			
4	<b>WORKING COUNTER</b>					
4.1	<b>CASH/STAFF COUNTERS</b>	Rft.	5.0			
	Providing and fixing Chief Cash Counter in split-levels @ 2'-6" (height 750mm) & 18" (1140mm) with 2'-9" & 15" wide each respectively. Each Upper and Lower tier shall be made of 19 mm thick BWR Plywood finished in 1.0mm thick laminate. Exposed edge having steam beech wood edging of size 1 1/2" x 1". Vertical face shall have 19mm thick BWR Plywood Board over pine wood framework as per requirement of design. All exposed surfaces shall be finished with 1.0mm thick laminate of approved shade and colour.					
	1 no. prefabricated metal computer key board tray including drawer slides 12.5" x 22" tray with 14" telescopic slides including L – brackets for securing to the table top. Chest of drawers (size 1'-4" x 2'-0" x 2'-5") made of 19mm thick BWR Plywood Board having three drawers finished with 1.0mm thick Laminate on all sides. Each drawer shall have locking system and 6" long S.S. brushed finished handle, drawer slides etc. of approved make. All exposed edges of BWR Plywood Board sealed with Steam beech wood beading of size 1/4" x 3/4". All beading and exposed wood shall be melamine polished and non-laminate surface to be enamel painted. Item includes readymade metal powder coated CPU trolley, grommet, footrest for each seat. All complete as per approval and instructions of the Architect / employer. The rate also include providing and fixing painting a foot rest using hard wood 100 x 25mm size 1st class seasoned country frame. Payment will be made only on the centerline measurement. The rate shall include the cost of providing skirting of 100mm wide lined with 1.0mm thk laminate and providing & fixing a border at top of 100mm wide lined with 1.0mm thk laminate complete.					
4.2	<b>RUNNING COUNTER</b>	Rft.	32			
	Providing and fixing staff counter/SWO in split-levels @ 2'-6" (750 mm) & 3'1" with 2'-6" (750 mm) & 9" wide each respectively . Each Upper and Lower tier shall be made of 19mm thick BWR Plywood Board and finished in 1.0mm thick laminate. Working top having steam beech wood edging of size 1 1/2" x 1". Vertical face shall have 19 mm thick BWR Plywood Board pine wood framework as per requirement of design. All exposed edges of BWR Plywood Board sealed with Steam beech wood beading of size 1/4" x 3/4". All exposed surfaces shall be finished with 1.0mm thick laminate of approved shade.					

**CANARA BANK  
CIRCLE OFFICE TIRUPATI**

**BOQ INTERIOR WORKS FOR CANARA BANK AT ALTERNATE PREMISES OF VELGODU BRANCH & ATM**

A	SCHEDULE - 'A' (FURNISHING WORK)				
S.NO.	DESCRIPTION	UNIT	QTY.	RATE	AMOUNT
	<p>The item includes Chest of drawers (size 1'-4" x 2'-0" x 2'- 5") made of 19mm thick BWR Plywood Board having One drawers at top and a storage cabinet below having shutters of 19mm thick BWR Plywood Board finished with 1.0mm thick Laminate on all sides. 1 no. prefabricated metal computer key board tray including drawer slides 12.5" x 22" tray with 14" telescopic slides including L – brackets for securing to the table top for each seat. All beading and exposed wood shall be melamine polished and non-laminate surface to be enamel painted. Item includes readymade metal powder coated CPU trolley, grommet, foot rest for each seat. <b>12mm thk plain glass on table top</b> as per shape with hole /cutting for wire manager should be provided. The glass should cover the length of the table. All complete as per approval and instructions of the Architect/employer. The rate also include providing and fixing painting a foot rest using hard wood 100 x 25mm size 1st class seasoned country frame. Payment will be made only on the centerline measurement. The rate shall include the cost of providing skirting of 100mm wide lined with 1.0mm thk laminate and providing &amp; fixing a border at top of 100mm wide lined with 1.0mm thk laminate complete.</p>				

**CANARA BANK  
CIRCLE OFFICE TIRUPATI**

**BOQ INTERIOR WORKS FOR CANARA BANK AT ALTERNATE PREMISES OF VELGODU BRANCH & ATM**

A	SCHEDULE - 'A' (FURNISHING WORK)	UNIT	QTY.	RATE	AMOUNT
S.NO.	DESCRIPTION				
4.3	Providing and Fixing 2' wide <b>running plank / dining ledge</b> made up of 19mm BWR ply board finished with 1mm thick laminate of bank approved colour with good finishing complete with necessary plywood support with atleast one support for every 2.5' to 3' and continous foot rest as per standard quality similar to counters with all required material, labour etc and as directed by the bank / architect, complete for the finished item of work	Rft.	0		
5	<b>TABLE &amp; FURNITURE</b>				
5.1	<b>MANAGER TABLE ( Size:- 6'-0" x 3'-0") ht. 2'-6"</b>	Nos	1		
	Providing and fixing tables made out of 19 mm thick BWR Plywood Board hard wood frame work finished with 1.0mm thick laminate of approved shade. Top having steam beech wood edging of size 2" x 1 ¼" finished with 19mm thk BWR Plywood Board of approved make cladded with 1mm thk. laminate (color with vertical grain) as per design in all visible areas. All the exposed edges to be covered with wooden steam beech lippings and mouldings duly malamine polish. The drawers to be made out of 19mm thk BWR Plywood Board with 1.0 mm laminate finish in the front , and bottom to be made out of 6mm BWR Plywood Board and it should play in drawer sliding telescopic channels. The inside of the drawer to be duly paint & Table back side will be 1mm laminate. A leg rest to be provided duly polished made out of 3"x2" Wooden Section. A shutter to be made by 19mm BWR Plywood Board cladded with 1.0mm laminate . <b>12mm thk plain glass on table top as per shape with hole /cutting for wire manager should be provided. The glass should cover the length of the table &amp; width of side unit as shown in the drawing.</b> The edges are to be neatly finished as per the shape indicated by Engineer in charge. Wire manager shall be provided at the corner of the counter top. The necessary locks handles to be provided in each drawers and shutters. 3" x 1/2" wooden skirting to be provided in all visible areas duly polished. The necessary wire managers(SS) to be provided on the tables and provision for lights to be kept if required in the front of the table. The table should be All the exposed areas to be duly malamine polished. The work to be completed as per design and approval of the Bank. The table should have key board tray and CPU Trolley to be Modular. All as per the design and instructions of Bank .				
5.2	<b>ROLLING BLINDS</b>	Sq.Ft.	75		
	Providing and fixing Roller blinds of approved design and shade by the Architect,incl all std fittings as per manufacturer's specification. The work to be completed as per specification and approval of the architect. (approved brand Vista, Hunter Dogulus or approved equivalent)				
6	<b>STORAGE &amp; SIDE UNIT</b>				
6.1	<b>Side and Back Unit</b>	Sq.Ft.	20		
	Providing and fixing Side Unit/ Back unit 450 mm depth made out of 19mm thick BWR Plywood Board finished with 1.0mm laminate in all exposed areas . The drawers to be made out of 19mm BWR Plywood Board and cladded with 1.0mm laminate and bottom made out of 6mm comm BWR Plywood Board duly painted in matching tone and it should play on drawer sliding channels. The shutters to be made out of 19mm BWR Plywood Board and should play on drawer sliding castors on powder coated channels. The necessary locks , handles, etc to be provided. 3" x1/2 wooden skirting to be provided duly polished as per matching tone all along the visible areas. Inside of the unit to be enamel painted in matching tone. All the exposed edges of the boards/ Plywood Board woods to be covered with wooden lippings/mouldings duly polished all complete. The work to be completed as per approval and specification of the Architect.				
6.2	<b>LOW HT / FULL HT STORAGE UNIT</b>	Sq.Ft.	250		
	Providing and fixing Full /Low height Cabinet 450mm deep made out of 19mm thk BWR Plywood Board finished with 1.0mm laminate in all exposed areas. The Shutter to be made out of 19mm BWR Plywood Board in the front cladded with 1.0mm laminate (color, vertical grain) and bottom made out of 6mm BWR Plywood Board duly painted in matching tone and shelves 19mm thk comm BWR Plywood Board to fixed inside storage. The shutters to be made out of 19mm BWR Plywood Board . The necessary locks, tower bolts, handles, etc to be provided. 3" x1/2 wooden skirting to be provided duly polished as per matching tone all along the visible areas. Inside of the unit to be enamel paint finish. All the exposed edeges of the boards to be covered with wooden lippings/mouldings duly polished all complete. All as per the design and instructions Bank.				
6.3	<b>Main Electrical Panel Cabinet</b>	Sq.Ft.	48		
	Providing and fixing of DB Shuttering formed of 12mm thk BWR Plywood Board wood on 12mm thick Gypsum board (fire Proof) with finish as per Item no 1 for inside and out side shutters finished with laminate on outer surface with SS Handle (4Nos) louvre perforation and necessary hardware, hinges etc complete as per details. All as per the design and instructions Bank.				
	Note - For the purpose of contractor's payment in case of Electrical panel cabinet, only front elevation area shall be measured. BUT the partition shall be erected till soffit of the actual ceiling along with the board concealing the entire area and not just till the false ceiling.				

CANARA BANK								
CIRCLE OFFICE TIRUPATI								
BOQ INTERIOR WORKS FOR CANARA BANK AT ALTERNATE PREMISES OF VELGODU BRANCH & ATM								
A	SCHEDULE - 'A' (FURNISHING WORK)				UNIT	QTY.	RATE	AMOUNT
S.NO.	DESCRIPTION				UNIT	QTY.	RATE	AMOUNT
7	OTHER MISCELLANEOUS ITEMS							
7.1	PIN UP / NOTICE BOARD				Sq.Ft.	32		
	Providing and fixing soft board with necessary framework with 12mm BWR Commercial Plywood Board on top 12 jolly board to be fixed finished with fabric @Rs80 , with necessary mouldings duly polished along the periferi. All as per the design and instructions Bank.							
7.2	PLASTIC EMULSION PAINT				Sq.Ft.	0		
	Applying 2 coat of Plastic emulsion paint (asian) of approved make and shade on walls including scrapping off, preparing the base etc color and shade to give an even and smooth surface on new work including necessary scaffolding, coat of cement primer etc. all complete as per direction of Bank. ( Other than banking hall).							
7.3	ENAMEL PAINT				Sq.Ft.	0		
	Applying 2 or more coats of enamel paint after neatly scraping the existing paint and finishing smoothly (NEROLAC/ ASIAN) on wooden/ steel doors & windows to give even & uniform surface.							
7.4	WRITING LEDGER				NO	1		
	Providing and fixing writing ledger as per design minium 5 ft length made out 19mm BWR Ply board with necessary grove patterns with 1.0mm laminate. 10mm thk machine polished glass to be provided on top of the writing ledger.							
7.5	CHEQUE & SUGGESTION BOX				NO	2		
	Small boxes to be made out of 12mm BWR Plywood Board along with writing ledge finished with 1.0 mm thick laminate, inside enamel painted and rate should be included providing fixing of sugestion box & Cheque deposit box as per approval of bank. It should necessarily have a provision for dropping off the cheques or suggestion letters from the top and a small door with lock provision for the staff to access the contents.The work to be completed as per design and approval of the architect.							
7.6	OUTER SHUTTER BOXING				Sq.Ft.	120		
	Providing & Fixing ,framing consisting of 2 1/2" x 1 1/2" Al. framing @ 600 mm c/c both ways horizontally and vertically on the rolling shutter ,providing over 6mm thick A.C.P. sheet, complete with necessary hardware , scaffolding etc.or as directed by the bank.							
7.7	PILLAR & FRONT FACIA ABOVE MAIN ENTRANCE : WOODEN PANELLING				Sq.Ft.	1400		
	Fabricating and fixing wall/column panelling, the framing shall made out of aluminium hollow section of 65mm x 37mm size 1.0mm thick of JINDAL / INDAL at spacing not exceeding 600mm bothways (horizontal and vertical). Panelling framework to be secured to wall surface/column surface.Panelling framework to be clad on one side with 9 mm thick BWR Plywood finished with 1.0mm thk laminate including skirting of 100mm high & 12mm x 12mm groove at skirting level. All as per the design and instructions Bank.							
	COLUMNS, CASH CABIN , MGR CABIN, BANKING HALL							
7.10	GLASS SHELVES				Sq.Ft.	28		
	Providing and fixing glass panes / shelves of required sizes with all edges neatly grinded, polished and fixed to the wall surfaces using SS D-brackets. The glass shall be 10mm thk plain glass of approved make. Item shall include all required arrangement / hardwares/ accessories to complete the job upto the satisfaction of bank / Architect.							
7.11	DRESSING TABLE FOR STRONG ROOM				Sq.Ft.	1		
	Dressing table of size 600mmx450mmx600mm made up of 12 mm thck BWR ply on top and vertical support finished with 1 mm laminate of approved shade and brand with 5 mm thick frame less mirror of size 1200mmx4500mm fixed to wall with SS Studs as per Design and direction of Architect/bank. The table shall have openagle shutter with horizontal shelves in bottom.							
<b>GRAND TOTAL FOR FURNISHING (A)</b>								
* GST EXTRA AS APPLICABLE								