

BOQ - AC WORKS AT AMU II

S.No.	DESCRIPTION	QUANTITY	UNIT	RATE (Rs.)	AMOUNT (Rs.)
1	Supply, Fixing, Testing & commissioning of following star rated AC units, with evaporator copper coil & imported refrigerant joints, with wireless remote controller (Make:- LG/Bluestar / Voltas / Carrier Only)				
(i)	Cassette 2 TON - 3 Star	6.00	No.		
(ii)	Split 1.0 TON - 3 Star	2.00	No.		
2	SITC of interconnecting refrigerant pipe of required dia work with closed cell elastomeric nitrile rubber tubular insulation between each set of indoor & outdoor units as per specification, all piping inside the room shall be properly supported with MS hanger & clamps including required cabling from indoor to outdoor unit. (Make :- Mandev, Rejoice)				
(i)	Split 1.0 TON - 3 Star	90.00	Rmt		
(ii)	Cassette 2.0 TON - 3 Star	30.00	Rmt		
3	Providing & fixing, testing and commissioning of wall mounted copper wound voltage stabilizer suitable for split all accessories. Input Voltage range : 140-280 V, Output : 230 V (Make:- Blue- Bird/V guard & other reputed Firm)				
(i)	CAPACITY: 5 KVA	6.00	Nos		
(ii)	CAPACITY: 4 KVA	2.00	Nos		
4	SITC of rigid CPVC piping complete with fittings supports as per specification tions & duly insulated with 6mm thick closed cell nitrile rubber insulation.				
(i)	Drain Pipe for 2.0 Ton AC (Cassette)	110.00	Rmt		
(ii)	Drain Pipe for Split 1.0 TR (Split)	40.00	Rmt		
5	M.S. stand with monkey cage with lock - [In door & out door units]	8.00	No		
6	Installation Charges .	8.00	No		
7	Digital Dual AC Switching Timer for ATM (BIS / ISI Marked)	1.00	No		
TOTAL (Rs.)					
GST Extra					

NOTE :- All work should be done as per Bank's Specification