

**BOQ : Schedule of Quantities for Furnishing works of SARURPUR-KALAN Branch and ATM**

**Note I : Anti-termite with Chloropyrphos of approved brand and make to be done on all wooden surfaces.**

**Note II : Wherever painting items are mentioned, these always include base coats of primer required with a minimum 02 coats of final paint.**

S.No.	Description	Qty	Unit	Rate	Amount
<b>1</b>	<b>BANK COUNTERS</b>				
	a. Providing and fixing front bank counters of 3'-0" wide and 2'-6" height mad, out of 19 mm thick BWP plywood ofl Kitply/Natioanal/Greenply with a unit of 3 drawers, one Sliding/ channel with CPU rack and one sliding key board tray in every 4'-6" length with TW foot rest. All the front, and drawer front to be finished with 1mm thick laminate of approved colour. All internal portion to be finished with enamel painting of approved colour with necessary hardware like brass hinges, - drawer slides, locks and handles for all drawers etc as per instructions.	23.50	Rft		
	b. Providing and fixing barrier partitions (maximum 4' in height at centre) between bank counters in kailwood framework of size 50mm x 50mm at maximum spacing of 600 mm clc both ways with 6 mm thick BWP plywood to both sides finished with 1.5 mm thk laminate, 12 mm thk clear glass with etching of 10mm wide leaving 100 mm along all 4 borders of the glass, fixed with beach wood moulded beading as per design above 1.0 mt from floor level, fully finished with a bottom skirting. all exposed edges to be provided with TW lipping finished with melamine polish complete as per the drawing and as directed	108.00	Sft		
	c. Providing and fixing 12mm thick glass upright on the front end counter having height of 1 foot supported on steel decorative pipes leaving a gap of 3" between the counter too and bottom of the glass. (23.50 ft for counters and 5 ft in two rows for Cash Counter).	33.50	Rft		
<b>2</b>	<b>BULK CASH COUNTER</b>				
	Providing and fixing bulk cash counter of 3'-0" width with 2'-6" height on staff side and 3'-10" height on customer side made of 19mm thick BWP grade plywood of Kitply/National/Greenply make with a unit of 3 drawers, one sliding channel with CPU rack and one sliding key board tray in every 4'-6" length with TW foot rest. All exposed surfaces to be finished with 1 mm thk laminate of approved shade & all inernal portions to be finished with enamel painting of approved colour with necessary hardware like brass hinges, drawer, slides, locks and handles for drawers etc as per instructions.	5.00	Rft		
<b>3</b>	<b>CASH ENCLOSURE</b>				
	Cash enclosures of 1.8 M high made of kailwood sections 50mm x 50mm and frame work at maximum 600 mm clc both ways with 6mm thk BWP plywood panelling for both sides and finished with 12mrn thk clear glass with 19mm bevelled edges above 1.2m level etched as per design fixed with beachwood beading and finished with melamine polish. With one door of size 0.75mx 1.8m provided with brass hinges, Godrej night latch. brass spring handles, door stopper, door closure etc., as required and as directed.	90.00	Sft		

	<b>Aluminium mesh on Top of cash cage:</b> Providing and fixing aluminium mesh cage on top of cash cage are, all complete with polished wooden frame duly supported to prevent sagging.	35.00	Sft		
<b>4</b>	<b>PARTITIONS</b>				
	a. Providing and fixing (maximum 9' 6" in height) partitions in TW framework of size 50mm x 50mm at maximum spacing of 600 mm c/c both ways with 6 mm thk BWP plywood to both sides finished with 1.0 mm thk laminate, fixed with TW moulded beading as per design above 1.0mt from floor level, fully finished with a bottom skirting and wooden cornice of 40mm x 40mm for the top i.e. below the ceiling level and top portion of the cabin, all exposed edges to be provided with TW lipping finished with melamine polish complete as directed. The required wicket gates to be provided in the partition as per the drawing with brass hinges, handles, Godrej locks, door closures etc. (BM CABIN & UPS ROOM )	350.00	Sft		
<b>5</b>	<b>WORKSTATION</b>				
a.	<b>T1- Manager Table</b>	1.00	No.		
	(including side unit & 12 mm thick glass on top of table)				
	Size- 6'-0" X 3'-0" X 2'-6"				
	Side Storage- 3'-0" X 2'-6" X 1'-6"				
	Ply Wood-19.0mm thick BWR Grade board IS303 for frame work				
	Drawer- 1'-6" wide two drawers and one shutter below the drawers at left/right side of the table				
	Laminate-1.0mm thick approved colour				
	Key Board Tray- 19.0mm thick BWR Grade commercial board IS303 for frame work with 1mm laminate the unit shall have guides, sliding units etc.				
	Foot Rest-12.0mm thick BWR Grade Ply tapered box finish with polish				
	Handle-Brush finish stainless steel, Brass Ball Catches 12.0 thick plain glass with edge polish at top of the table (Other Exposed Edge of Ply with half round beading with approved colour polish)				
	All exposed surfaces to be finished with 1mm thick laminate of approved make & shade and all exposed edges of table top & verticals to have T.W. lipping of appropriate/approved size & shape. All visible wood should be polished with melamine polish. All inner surfaces painted with enamel paint with two and more coat after applying the primer coat. The board of 19mm thick to be used should be termite resistant.				
b.	<b>T2- Officer Table</b>	2.00	No.		
	Size- 5'-0" X 2'-6" X 2'-6"				
	Other specifications as per Table T1				
<b>6</b>	Providing and fixing <b>WRITING DESK</b> of size 8'x4' feet made up of 19 mm thick commercial board with 6" border. Stand should have 4'x3' pin up board, 10" wide shelf with glass at the top. Bottom portion should be provided with cheque drop box and suggestion box will all necessary fittings and finished with melamine polish etc. complete as per drawing and as directed.	1.0	no		
<b>7</b>	Providing and fixing flap door of size 4' x 3' with plywood on wooden framework and finished with matching colour laminate.	12.00	Sft		

8	Providing and fixing 2' x 2' <b>Amstrong tile</b> (12.5 mm thick) false ceiling in aluminium powder coated sections supported with GI framework to the ceiling including proper levelling and finished of the joints and top surface as per manufacturers specifications. All edges shall be perfectly straight G.I. angle shall be embedded within, at the edge, and the surface finished flush with surrounding surfaces complete as directed.	750.00	Sft		
9	Providing and fixing of <b>Gypsum Board</b> false ceiling in aluminium powder coated sections supported with GI framework to the ceiling including proper levelling and finished of the joints and top surface as per manufacturers specifications, All edges shall be perfectly straight G.I. angle shall be embedded within, at the edge, and the surface finished flush with surrounding surfaces complete as directed.	350.00	Sft		
10	Providing centre table measuring 4' x 2" made up of teak wood with 8 mm glass at top.	1.00	Nos		
11	Wall Paneling made out of 2"X1" TW Frame @2ft C/c on both ways with 4"X1" TW member at bottom fixed with nails screw fixed to walls ,columns with wooden plugs wherever required & 4mm Ply with 1mm Sunmica as per approved color etc.(FOR COLUMNS & WALLS)	400.00	sft		
12	<b>Low height Storage:</b> Cup-Board made out of 19 mm thick comm.Board ,1mm thick sunmica /lamination to be fixed all exposed surfaces (side, top & front). The rate includes necessary hardware such as hinges/tower bolts + shutter + Godrej locks +knobs & Brass Handles . Beading to be polished (melamine) ,all inner surfaces shall be finished with enamel paint two or more coats over a coat of primer.	90.00	sft		
13	<b>Wall hanging Cup-Board:</b> with height upto false ceiling level having 1.5ft depth made out of 19 mm thick Board, 1 mm thick sunmica / lamination to be fixed all exposed surfaces (side, top & front). The rate includes necessary hardware such as hinges/tower bolts + shutter + Godrej locks +knobs & Brass Handles . Beading to be polished (melamine), all inner surfaces shall be finished with enamel paint two or more coats over a coat of primer.	32.00	Sft		
14	Providing and fixing Aluminium Door with minimum section thickness of 2.5mm all complete with swing door, fixed portion all 12mm glass, coloured ionized/powder coated as per standard approved sections, all complete with necessary hardware and fittings including floor springs door locks etc.(ATM - Entrance Door)	144.0	sft		
15	Providing and fixing vertical blinds	49.00	Sft		
16	Providing and fixing ACP for shutter boxing	120.00	Sft		
					<b>Total in Rs.</b>
					<b>GST 18%</b>
					<b>Total (including GST) Rs.</b>