

**BOQ - FURNISHING WORKS AT RAH CANARA BANK MUZAFFANAGAR**

S.NO.	DESCRIPTION OF ITEM	QTY.	UNIT	RATE (Rs)	AMOUNT (Rs)
<b>1.0</b>	<b>Partitions</b>				
<b>a.</b>	<b>P1-(Ht. 8'-6") (Chief Manager Partition)</b>	210.00	Sq.Ft.		
	<b>Frame Work- Heavy duty Aluminium Box Sections 50mm x 50mm @ 600mm c/c Horizontally and Vertically.</b>				
	<b>Plywood- 6.0mm thick BWR Grade IS303:1998</b>				
	<b>Laminate-1.0 mm thick over Plywood (Approved Colour Scheme)</b>				
	(The necessary additional frame/opening in frame work for Electrical Conduits, Electric Modular Box, AC Grills, AC Duct etc. provide as per site requirements & aluminium member of partition shall be fixed rigidly to the floor, columns and beams). All exposed edges of Plywood shall be fixed with 1/8" C.P. Teak Lipping with natural/white colour polish. The door is also inclusive, made with 32mm board (flush door) along with necessary fittings like SS finish 100mm hinges, fittings.				
	<b>Door Size/ Design/ Type</b> - As per drawing/instruction of Bank/Architect including Door Closure / Door Lock / Mortise Lock / Night Latch of Godrej or equivalent make.				
<b>b.</b>	<b>P2-(Low Ht. 4'-6") (Solid Partition)</b>	249.00	Sq.Ft.		
	<b>(Side partition for SWO, Flap Door &amp; Other counters)</b>				
	As per other Specification partition P1				
<b>c.</b>	<b>P3-(Low Ht. 4'-6") (Solid Wicket Gate) with inner side locking arrangements</b>	27.00	Sq.Ft.		
	<b>Ply Wood-19.0mm thick BWR Grade commercial board IS303:1998 for frame work.</b>				
	<b>Laminate- Specification as per partition P1</b>				
<b>d.</b>	Providing and fixing <b>glazed door</b> and fixed glazing (full/ low height glass partition) with <b>12 mm thick toughened glass</b> of approved make with all SS patch fittings (Hettich/ Haffele/ Dorma) and frosting as per drawing. Item to include floor springs, lock, 450 mm long handles and other necessary hardware of Stainless Steel of make Hettich/ Haffele/ Dorma/ Ozone/ Geze all complete as per the directions of Architect/ Engineer-in-charge (Designer lazer cut frosting if any shall be measured and paid for separately).				
<b>(i)</b>	Fixed Glazing	151.00	Sq.Ft.		
<b>(ii)</b>	Openable door	35.00	Sq.Ft.		
<b>e.</b>	<b>MORTICE LOCK ::</b> P/F of 7" mortice lock with handle set of godrej make. It shall have 6brass lever, suitable for reight or left handed door shutter, inside or outside opening. The keyless latch shall be opened from either side of the door by turning th handle, itshall work as a latch from inside at the turn of a button and as a lock operable with a key from outside. The item should be complete in all respect including fixing in place to the satisfaction of the Bank.( Fusion rosette-2-c of godrege make code 7729) including lock body ( code 8448) and 2 c -70mm cyleinder ( code 8452)	2.00	Nos		

f.	<b>HYDRAULIC DOOR CLOSERS</b> :: P/F of hydraulic door closer godrej make, it shall incorporate, body manufactured from aluminium extruded alloy machined to extreme accuracy, rack and pinion made of machined alloy steel duly heat - treated, adjustable closing speed, suitable for right hand and left hand opening door, suitable for door / frame mounting, suitable for door weight up to 60 kgs, suitable for 180/100 degree door opening. All complete in all respect to the satisfaction of the Bank, item is inclusive of fixing of the door closures.	2.00	Nos		
g.	S/F door stopper	6.00	Nos		
<b>2.0</b>	<b>Wooden Tables/Counters</b>				
a.	<b>T1- Manager Table</b>	2.00	No.		
	<b>(including side unit &amp; 12 mm thick glass on top of table)</b>				
	<b>Size- 6'-0" X 3'-0" X 2'-6"</b>				
	<b>Side Storage- 3'-0" X 2'-6" X 1'-6"</b>				
	<b>Ply Wood-19.0mm thick BWR Grade board IS303 for frame work</b>				
	<b>Supports-2" X 2" &amp; 2" X 1.5" CP Teak Wood and beading Patti</b>				
	<b>Drawer- 1'-6" wide two drawers and one shutter below the drawers at left side of the table</b>				
	<b>Laminate-1.0mm thick approved colour</b>				
	<b>Key Board Tray- 19.0mm thick BWR Grade commercial board IS303 for frame work with 1mm laminate the unit shall have guides, sliding units etc.</b>				
	CPU Metal Stand, Twin Telescopic Drawer Fittings, Brass Powder Coated Wire Manager				
	<b>Foot Rest-12.0mm thick BWR Grade Ply tapered box finish with polish</b>				
	Handle-Brush finish stainless steel, Brass Ball Catches				
	All exposed surfaces to be finished with 1mm thick laminate of approved make & shade and all exposed edges of table top & verticals to have T.W. lipping of appropriate/approved size & shape. All visible wood should be polished with melamine polish. All inner surfaces painted with enamel paint with two and more coat after applying the primer coat. The board of 19mm thick to be used should be termite resistant.				
b.	<b>T2- Officer Table</b>	6.00	No.		
	<b>Size- 5'-0" X 2'-6" X 2'-6"</b>				
	Other specifications as per Table T1				
c.	<b>T3- MeetingTable</b>	1.00	No.		
	<b>Size- 4'-0" dia (Round Table)</b>				
	Other specifications as per Table T1				
<b>3.0</b>	<b>Storage Unit</b>				
a.	<b>S1-Storage (Low Height - 2'6")</b>	127.00	Sq.Ft.		
	<b>Ply Wood- 19.0mm thick BWR Grade IS303 for sides, top, shelf &amp; door and 6.0mm IS 303 for Backside</b>				
	<b>Shelf-19.0mm thick BWR Grade IS303 ply</b>				
	<b>Depth- 1'6"</b>				
	<b>Handle-Brush finish stainless steel</b>				
	<b>Lock- As approved</b>				
	All visible teak/ cedar wood should be polished with spirit polish. All inner surfaces painted with enamel paint with two and more coats after applying the primer coat. The board of 19mm thick to be used should be termite resistant.				
b.	<b>S2-Storage (Meter/ Electrical panel box) with air louvers</b>	42.50	Sq.Ft.		
	<b>Size- Length &amp; Width as per site and Depth- 1'10" to 2'0"</b>				
	Other specification as per Low Height Storage S1				

<b>4.0</b>	<b>False Ceiling Works (Gypsum)</b>	602.00	Sq.Ft.		
	Providing & fixing with necessary scaffolding frame in 22 gauge GI channel /angle, placed at appropriate grid, fixed to RCC slab, beam, wall etc. with fasteners /screws finished with 12.0mm Gypsum sheets joints covered with POP slurry/tape. Rates shall include painting (One Coat of putty, one coat of primer coat and two coats of acrylic paint). Rates shall include providing necessary cut-outs & additional support frames for electrical fixtures, A.C. grills, vertical drop up to 1'6" etc. item includes finishing with painting base work and finishing in plastic paint of white colour. ( Note - : No extra payment shall be given for design )				
<b>5.0</b>	<b>False Ceiling Works (Armstrong)</b>	596.00	Sq.Ft.		
	Providing & Fixing <b>Armstrong (Fine Fissured Micro Look with Tagular Edge using 15.0mm Grid sections)</b> false ceiling of size 24"x24" at levels as shown in the drg. Rate shall be inclusive of providing the total system with installation etc. Contractor has to maintain all tiles in good order and replace the defected tiles (at his own cost) before handing over the site for Branch Operations. Rate shall include providing necessary cut-outs & additional support frames for electrical fixtures, A.C. grills etc.( Note - : No extra payment shall be given for design )				
<b>6.0</b>	<b>Miscellaneous Works</b>				
<b>a.</b>	<b>Panelling on Wall &amp; Column With Aluminium Frames</b>	355.00	Sq.Ft.		
	Providing and fixing panelling on wall. Both ways horizontally and vertically on the wall / with <b>Aluminium Sections of 2"x1"</b> as directed by Bank / Architect. This framing would be covered by 6mm thk. Ply and overit finished with 1mm thick laminate all complete. <b>Plywood</b> -6.0mm thick BWR Grade IS303:1998 <b>Laminate</b> -1.0 mm thick (Approved Colour Scheme)				
<b>b.</b>	<b>ACP - Rolling Shutter Box with Trap Door</b>	124.00	Sq.Ft.		
	<b>Frame Work</b> -2" X 2" X 1.5 mm thick Aluminium Tubular section (Horizontal/Vertical) Jindal Make <b>Aluminium Composite Panel</b> -3.0mm thick of approved colour with bonding material				
<b>c.</b>	Providing and fixing <b>Writing Stand</b> of size 8'x4' feet made up of 19 mm thick commercial board with 6" border.Stand should have 4'x3' pin up board , 10" wide shelf with glass at the top.Bottom portion should be provided with cheque drop box and suggestion box will all necessary fittings and finished with melamine polish etc. complete as per drawing and as directed.	1.00	Nos		
<b>d.</b>	<b>Vertical blinds</b>				
	Providing and fixing of vertical blinds made out of 100mm wide (Scotch - Guarded ) fabric louvers ( as per shade approved by the Architect ) including Head rail, control unit carries, Tilter, Traverse cord, Tilt rod bottom Machanism, Installation Bracket etc. all Complete.	72.00	Sq.Ft.		
<b>TOTAL (Rs.)</b>					
*GST extra					
NOTE -: All work should be done as per Bank's Specification					