

കന്നഡ ബാങ്ക് കേന്ദ്ര ബੈങ്ക് Canara Bank 

ഒരു ഭാരത സർക്കാർ സ്ഥാപനം

भारत सरकार का उपक्रम

A Government of India Undertaking

 സിൻഡിക്കേറ്റ് സിൻഡിക്കേറ്റ് Syndicate

FINANCIAL BID

FOR

**INTERIOR FURNISHING WORK OF CANARA BANK ORKATTERY, PAYANTHONG,
BALUSSERY BRANCHES LOCATED AT KOZHIKODE, KERALA**

NOTICE TYPE : SHORT NOTICE DOMESTIC TENDER

ISSUED BY

PREMISES & ESTATE SECTION, CIRCLE OFFICE

TC NO. 26/173 (1), PB NO 159, M G ROAD

THIRUVANANTHAPURAM - 695 001

TEL: 0471-2331340

E-mail: pecotvm@canarabank.com

PRICE/FINANCIAL BID

To,

The Divisional Manager,
Premises & Estate Section,
Canara Bank, Circle Office,
M G Road, Trivandrum, Kerala -695001

Sir,

**SUB: INTERIOR FURNISHING WORK OF CANARA BANK ORKATTERY, PAYANTHONG,
BALUSSERY BRANCHES LOCATED AT KOZHIKODE, KERALA**

1. I/We have read the notice inviting tender, general rules, Terms & Conditions of Contract, I/We are fully qualified of the works to execute the subject work and have understood the scope of work, terms and conditions.
2. I/we are offering most competitive offer as below for the subject work based on the comprehensive site inspection and after understanding the site conditions;

**FURNISHING WORKS OF CANARA BANK, ORKATERI BRANCH
(RENOVATION TO EXISTING PREMISES)**

Sl.No	Description	Qty.	Unit	Rate	Amount (Rs.)
1	GYPSUM BOARD WORK				
1a)	FALSE CEILING: Providing and fixing Gypsum board ceiling with ISI standard Gypsum board using G.I perimeter channels along the perimeter of ceiling and sides of R.C.C column, screwing to brick walls/R.C.C. surface with the help of Nylon sleeves and screws at 600mm c/c, then suspending or fixing G.I. intermediate channels at 1200mm c/c (or nearest spacing) with the help of G.I. hanger/ steel G.I. supports/G.I ceiling angles fixed to supports with G.I. cleat and steel expansion fastening, then the ceiling section fixed to the intermediate channels for fixing Gypsum sheet with the help of connecting clip and screws in both direction perpendicular to the intermediate channels at 400mm c/c at required level including cost and conveyance of all materials and labour charges, scaffolding charges, finishing the joints of the sheets with Gypsum powder paste finishing.	190.00	M ²		
	Provisions for fixing the required electrical lights and fittings shall also be provided. The ceiling shall be painted with two coats of brilliant white plastic emulsion paint over a coat of cement primer and putty.				
1b)	SIDE WALL: Providing and fixing Gypsum board side wall for covering the space over 240cm from floor level of double skin partition wall with the same specifications as above.	7.50	M ²		
2	DOUBLE SKIN PARTITION WALL:				
2a)	Providing and fixing double skin partition with heights of 90/120cm for half cabin, 150/210cm for cash counters and about 240/310cm for other partitions (refer the drawing enclosed). Partition should have an overall thickness of 7.5cm and shall be provided with base frame in 18/19mm BWR IS 303 ply that is 5cm wide at about 40cm c/c. Bottom part of the base frame shall be fixed to existing floor with anchor bolts. The partition shall be finished on both sides with 1mm thick laminate (specified colour) over 6mm BWR IS 303 ply. Partitions in Cash counters and other specified areas shall be provided with 12mm thick plain glass with openings.	122.00	M ²		
	The cost should include removing & refixing of usable Glass from existing partition and the same are will not be taken for measurement.				

2b)	Providing and fixing full height double skin partition for UPS room (refer the drawing enclosed). Partition should have an overall thickness of 7.5cm and shall be provided with 12mm thick bison panel (cement sheet) board over frame work made of 1.6mm thick 50mm x 50mm zinc coated G.I. box sections at 60cm c/c spacing both ways and consisting of floor and ceiling flanges of suitable size which are to be fixed to ceiling/ floor with suitable anchor bolts.	27.00	M ²		
	The boards shall be fixed to both sides of frame work with suitable screws on G.I. sections a spacing of 30cm c/c. The joints of boards shall be such that it staggers, so as to avoid cracking. The boards shall be finished with recommended jointing compound and two coats of cement primer.				
3	DOORS:				
3a)	Removing & Re-fixing existing main entry door to the bank.	1.00	NOS.		
3b)	Removing & Re-fixing existing door of Manager Cabin to a new position as shown in the drawing	1.00	NOS.		
3c)	Removing & Re-fixing existing flush doors to proposed new positions as marked in the layout.	4.00	NOS.		
3d)	Providing and fixing flush door to UPS room (12mm Bison panel board on both sides over 25 x 25mm MS frame welded at about 220 cm c/c vertically and 300 mm c/c horizontally). The door shall be provided with 50mm equal angle (3mm thick) as frame, door closure, heavy duty hinges (4 nos.), lock with handles (refer drawing). The door shall be painted two coats over putty and primer.	1.00	NOS.		
3e)	Removing & Re-fixing existing flush doors of cash cabin to proposed new positions as marked in the layout.	3.00	NOS.		
	*DORMA TS 68 Std Arm Door Closer shall be used.				
3f)	Providing and fixing flap flush doors (6mm BWR IS 303 ply on both sides over suitable frame) with laminated front and back with same finish as the counter. The door shall be provided with heavy duty brass hinges (2 nos.) and bolt.	1.00	NOS.		

4	STAFF LOW COUNTER: Fabricating & fixing in position 75cm wide staff low counter as per lay out plan. The counter shall be finished with 12mm thick plain glass (edges to be bevelled) fixed with special silicon buttons over specified colour lamination provided on 18/19mm BWR IS 303 ply. Draw and shutter front shall be laminated over 15mm thick BWR IS 303 ply. All the draws shall be fixed using telescopic sliders and shutters shall be fixed with auto closing hinges. SS handles and godrej locks should be provided for shutters and draws. Keyboard draw (in telescopic sliders) and CPU stand shall be provided. The front portion of the table shall be finished with lamination as per sketch. All the inside portion shall be painted with two coat enamel over a coat of putty and wood primer.	10.50	RMT		
5	CASH COUNTER: Fabricating & fixing cash counter 150cm length, 75cm wide and 120cm height for staff side. Drawers as per sketch shall be provided. Clerical top & Customer top should be finished with 12mm bevelled glass over 1mm greenlam laminates as per details. Front side is to be fixed with 1mm greenlam laminates as per details Inner side of counter should be applied with two coat enamel paint over a coat of wood primer. Key Board Drawer, using telescopic sliders (EBCO) to be provided in the counter.	3.00	RMT		
6	TABLES:				
6a)	MANAGER'S TABLE: Supply & fixing in position Manager's table (170cm x 90cm) with side table (115cm x 45cm) as per enclosed sketch. The table shall be finished with 12mm thick plain glass (edges to be polished) fixed with special silicon buttons over specified colour lamination provided on 18/19mm ply. Draw & shutter front shall be laminated over 15mm ply. The draws shall be fixed using telescopic sliders & shutters shall be fixed with auto closing hinges. SS handles and godrej locks should be provided for shutters, draws & keyboard draw (in telescopic sliders). The table shall be provided with CPU stand, three draws. The front portion of the table shall be finished with lamination as per sketch. The inside portion shall be painted with two coat enamel over a coat of putty & wood primer.	1.00	EACH		
6b)	OFFICER'S TABLES: Supply & fixing in position Officer's tables (150cm x 75cm) as per enclosed sketch. The total unit shall be finished as detailed for manager table.	2.00	EACH		

6c)	OFFICER'S TABLES: Re-fixing in position existing Officer table with side table to a new position as per enclosed sketch. Note that the table shall be made good and re-painted inside.	2	EACH		
6c)	SIDE TABLES FOR CASH COUNTING: Supplying & fixing side tables to the cash counting (165cm x 60cm) as per the enclosed sketch. The side table shall be provided with a rack with shutter. The table top shall be laminate over 18/19mm ply. The bottom and inside portion shall be painted with 2 coats of enamel paint over a coat of wood primer.	1.00	EACH		
6d)	SIDE TABLES FOR OFFICER TABLE: Supplying & fixing side tables to the officer table (90cm x 40cm) as per the enclosed sketch. The side table shall be provided with a rack with shutter. The table top shall be laminate over 18/19mm ply. The bottom and inside portion shall be painted with 2 coats of enamel paint over a coat of wood primer.	1.00	EACH		
6e)	COUNTER IN DINING SPACE: Fabrication & fixing 12mm thick BWR grade plywood counter 60cm wide (at a height of 75cm from finished floor level) in position as shown in the enclosed lay out plan with suitable supports (vertical frames as done for other tables placed in the middle of span (at about 1.5m distance) and at edges). All exposed sides to be painted with 2 coats Asian paint enamel over a coat of wood primer. Top of the counter should be finished with laminations	6.00	RMT		
6f)	SIDE TABLES FOR OFFICER TABLES: Supplying & fixing side tables for officer tables (90cm x 45cm) as per the enclosed sketch. The side table shall be provided with a rack with shutter. The table top shall be laminate over 18/19mm ply. The bottom and inside portion shall be painted with 2 coats of enamel paint over a coat of wood primer.	1.00	EACH		
6g)	BANK-MAN TABLE: Supply & fixing in position bank-man table as per enclosed sketch. The total unit shall be finished on top with laminate over 15mm BWR IS 303 ply. Shutter front shall be laminated over 15mm thick BWR IS 303 ply. The shutters shall be fixed with auto closing hinges, SS handles & godrej locks. Inside portion shall be painted with two coat enamel over a coat of putty & wood primer.	1.00	EACH		

7	FABRICATING & FIXING STORAGE RACKS:				
7a)	Fabricating and fixing 90cm high racks with 2 compartments using 19 mm thick BWR grade plywood finished on outer sides with 1mm thick laminates; with shutters. Shutters (15mm BWR ply) to be fixed with self closing special hinges (2nos. on each shutter). 100mm wide, 19 mm thick BWR grade plywood finished with laminates shall be provided as skirting. Top of unit shall be laminated. Each rack should have two cabinets which are divided equally (about 45cm each) & width of each rack is to be divided equally as in sketch. Depth of the rack has to be 45cm. All the shutters should be provided with good quality stainless steel handles. (Note that the back side of the rack also should be fixed with 6 mm thick BWR grade plywood without lamination. All non-laminated area should be painted with two coats matching coloured enamel paint over a coat of wood primer)	1.50	RMT		
7b)	Fabricating and fixing 240cm high and 45cm deep racks with same specifications as above. (Each compartment shall equally divided have two shutters.)	8.70	RMT		
8	PANELLING THE COLUMNS: Fixing wall panelling for columns in specified area from floor level upto false ceiling level using 1.00mm laminate finish over 6mm ply fixed using plywood framing.	16.00	M ²		
10	NOTICE BOARD :- Providing and fixing pinup boards. It consist ½” soft boards of good density to be mounted over 19 mm thick BWR grade plywood. The soft board will be covered with a plain fabric (approx. Rs.150 /Rmts.) from front and edges. Suitable moulding (as directed by architect) will be fixed on all four sides and will be finished in polish.	1.00	M ²		
11	ROLLER BLINDS :- Supplying and providing roller blinds with smooth operations using manual and clutch roller controlled by a continuous cord loop . The blind is to be fixed within the window opening .The fabric shall be of sun screening quality and of approved shade .Top Roller and bottom roller of powder coated Aluminium (Make Marvel/ Vista)	6.00	M ²		
12	DISMANTLING/ SHIFTING/ REFIXING/ WORKS:				
	Dismantling / Shifting existing counters/ tables/ partitions to a space for functioning of the branch during the proposed renovation work, as directed by the bank. The work shall include all labour charges and materials required for shifting/ dismantling.	Ls	Ls		

13	Cupboard for Electrical panel :Providing and fixing electrical panel board area shutter (openable and partly louvered) made out of 19mm thick BWR grade ply boxing, shutters.1.0mm thick laminate finish on front, with app. colour polish to external edges brass hinges, handles etc. as per the details. The shutters should have 12" ht. All. Powder coated louvers on top and bottom for ventilation.	3.00	M ²		
14	Change of Laminate- Removal of Old laminate and Providing and fixing 1.00 m thck new laminate over existng surface by using proper adhesive for partition, tables, drawers, storage	16.00	M ²		
<u>TOTAL FOR ORKATTERY BRANCH WORK (EXCLUDING GST</u>					

FURNISHING WORKS OF CANARA BANK, PAYANTHONG BRANCH , (RENOVATION TO EXISTING PREMISES)					
SI.No	Description	Qty.	Unit	Rate	Amount (Rs.)
1	GYPSUM BOARD WORK				
1a)	FALSE CEILING: Providing and fixing Gypsum board ceiling with ISI standard Gypsum board using G.I perimeter channels along the perimeter of ceiling and sides of R.C.C column, screwing to brick walls/R.C.C. surface with the help of Nylon sleeves and screws at 600mm c/c, then suspending or fixing G.I. intermediate channels at 1200mm c/c (or nearest spacing) with the help of G.I. hanger/ steel G.I. supports/G.I ceiling angles fixed to supports with G.I. cleat and steel expansion fastening, then the ceiling section fixed to the intermediate channels for fixing Gypsum sheet with the help of connecting clip and screws in both direction perpendicular to the intermediate channels at 400mm c/c at required level including cost and conveyance of all materials and labour charges, scaffolding charges, finishing the joints of the sheets with Gypsum powder paste finishing.	205.00	M ²		
	Provisions for fixing the required electrical lights and fittings shall also be provided. The ceiling shall be painted with two coats of brilliant white plastic emulsion paint over a coat of cement primer and putty.				
1b)	SIDE WALL: Providing and fixing Gypsum board side wall for covering the space over 240cm from floor level of double skin partition wall with the same specifications as above.	18.00	M ²		

2	DOUBLE SKIN PARTITION WALL:				
2a)	Providing and fixing double skin partition with heights of 90/120cm for half cabin, 150/210cm for cash counters and about 240/310cm for other partitions (refer the drawing enclosed). Partition should have an overall thickness of 7.5cm and shall be provided with base frame in 18/19mm BWR IS 303 ply that is 5cm wide at about 40cm c/c. Bottom part of the base frame shall be fixed to existing floor with anchor bolts. The partition shall be finished on both sides with 1mm thick laminate (specified colour) over 6mm BWR IS 303 ply. Partitions in Cash counters and other specified areas shall be provided with 12mm thick plain glass with openings.	80.00	M ²		
	The cost should include removing & refixing of usable Glass from existng partition and the same are will not be taken for measurement.				
2b)	Providing and fixing full height double skin partition for UPS room (refer the drawing enclosed). Partition should have an overall thickness of 7.5cm and shall be provided with 12mm thick bison panel (cement sheet) board over frame work made of 1.6mm thick 50mm x 50mm zinc coated G.I. box sections at 60cm c/c spacing both ways and consisting of floor and ceiling flanges of suitable size which are to be fixed to ceiling/ floor with suitable anchor bolts.	15.00	M ²		
	The boards shall be fixed to both sides of frame work with suitable screws on G.I. sections a spacing of 30cm c/c. The joints of boards shall be such that it staggers, so as to avoid cracking. The boards shall be finished with recommended jointing compound and two coats of cement primer.				
3	DOORS:				
3a)	Removing and re-fixing existing door of Manager Cabin to a new position as shown in the drawing	1.00	NOS.		
3b)	Removing and Re-fixing existing flush doors to proposed new positions as marked in the layout.	3.00	NOS.		
3c)	Providing and fixing flush door to UPS room (12mm Bison panel board on both sides over 25 x 25mm MS frame welded at about 220 cm c/c vertically and 300 mm c/c horizontally). The door shall be provided with 50mm equal angle (3mm thick) as frame, door closure, heavy duty hinges (4 nos.), lock with handles (refer drawing). The door shall be painted two coats over putty and primer.	1.00	NOS.		
3d)	Providing and fixing flush doors (6mm BWR IS 303 ply on both sides over suitable frame) with laminated front and back (refer drawing) for cash cabin. All the doors shall be provided with a vision panel, door closure, heavy duty brass hinges (3 nos.), godrej night latch (to be self locked from inside) and SS handles.	1.00	NOS.		
	*DORMA TS 68 Std Arm Door Closer shall be used.				

4	<p>STAFF LOW COUNTER: Fabricating & fixing in position 75cm wide staff low counter as per lay out plan. The counter shall be finished with 12mm thick plain glass (edges to be bevelled) fixed with special silicon buttons over specified colour lamination provided on 18/19mm BWR IS 303 ply. Draw and shutter front shall be laminated over 15mm thick BWR IS 303 ply. All the draws shall be fixed using telescopic sliders and shutters shall be fixed with auto closing hinges. SS handles and godrej locks should be provided for shutters and draws. Keyboard draw (in telescopic sliders) and CPU stand shall be provided. The front portion of the table shall be finished with lamination as per sketch. All the inside portion shall be painted with two coat enamel over a coat of putty and wood primer.</p>	3.00	RMT		
5	<p>CASH COUNTER: Fabricating & fixing cash counter 150cm length, 75cm wide and 120cm height for staff side. Drawers as per sketch shall be provided. Clerical top & Customer top should be finished with 12mm bevelled glass over 1mm greenlam laminates as per details. Front side is to be fixed with 1mm greenlam laminates as per details Inner side of counter should be applied with two coat enamel paint over a coat of wood primer. Key Board Drawer, using telescopic sliders (EBCO) to be provided in the counter.</p>	1.50	RMT		
6	TABLES:				
6a)	<p>MANAGER'S TABLE: Removing and Re-fixing in position existing Manager's table with side table to a new position as per enclosed sketch. Note that the table shall be made good and re-painted inside.</p>	1	EACH		
6b)	<p>COUNTER IN DINING SPACE: Fabrication & fixing 12mm thick BWR grade plywood counter 60cm wide (at a height of 75cm from finished floor level) in position as shown in the enclosed lay out plan with suitable supports (vertical frames as done for other tables placed in the middle of span (at about 1.5m distance) and at edges). All exposed sides to be painted with 2 coats Asian paint enamel over a coat of wood primer. Top of the counter should be finished with laminations</p>	4.50	RMT		

7	FABRICATING & FIXING STORAGE RACKS:				
7a)	Fabricating and fixing 90cm high racks with 2 compartments using 19 mm thick BWR grade plywood finished on outer sides with 1mm thick laminates; with shutters. Shutters (15mm BWR ply) to be fixed with self closing special hinges (2nos. on each shutter). 100mm wide, 19 mm thick BWR grade plywood finished with laminates shall be provided as skirting. Top of unit shall be laminated. Each rack should have two cabinets which are divided equally (about 45cm each) & width of each rack is to be divided equally as in sketch. Depth of the rack has to be 45cm. All the shutters should be provided with good quality stainless steel handles. (Note that the back side of the rack also should be fixed with 6 mm thick BWR grade plywood without lamination. All non-laminated area should be painted with two coats matching coloured enamel paint over a coat of wood primer)	2.50	RMT		
7b)	Fabricating and fixing 240cm high and 45cm deep racks with same specifications as above. (Each compartment shall equally divided have two shutters.)	5.50	RMT		
8	PANELLING THE COLUMNS: Fixing wall panelling for columns in specified area from floor level upto false ceiling level using 1.00mm laminate finish over 6mm ply fixed using plywood framing.	8.00	M ²		
9	ROLLER BLINDS:- Supplying and providing roller blinds with smooth operations using manual and clutch roller controlled by a continuous cord loop . The blind is to be fixed within the window opening .The fabric shall be of sun screening quality and of approved shade .Top Roller and bottom roller of powder coated Aluminium (Make Marvel/ Vista)	20.00	M ²		
10	DISMANTLING/ SHIFTING/ REFIXING/ WORKS:				
	Dismantling existing False ceiling,partitions,counters/ tables after stage wise progress of work and stocking of serviceable material and disposal of unserviceable material from the site as directed by the bank official.	Ls	Ls		
	Making necessary arrangement for the branch to function smoothly during the progress of renovation work that includes rearrangement of existing set up as required by branch from time to time.				

11	Cupboard for Electrical panel :Providing and fixing electrical panel board area shutter (openable and partly louvered) made out of 19mm thick BWR grade ply boxing, shutters.1.0mm thick laminate finish on front, with app. colour polish to external edges brass hinges, handles etc. as per the details. The shutters should have 12" ht. All. Powder coated louvers on top and bottom for ventilation.	4.00	M ²		
12	Change of Laminate- Removal of Old laminate and Providing and fixing 1.00 m thck new laminate over existng surface by using proper adhesive for partition, tables, drawers, storage	10.00	M ²		
<u>TOTAL FOR PAYANTHONG BRANCH WORK (EXCLUDING GST</u>					

FURNISHING WORKS OF CANARA BANK, BALUSSERY BRANCH , (RENOVATION TO EXISTING PREMISES)					
SLNo:	Description Of Work	Quantity	Unit	Rate	Amount
	FURNITURE				
	FALSE CEILING				
1	Supplying and fixing Gypsum board ceiling using ISI standard gypsum board and GI perimetres and Channels at 60cm C/C spacing fastened to raw concrete ceiling with strings and clips at not less than 45 cm spacing, board positioned in line, level and plumb, including all cost of transporatation, materials, labour etc. complete. Gypsum joints to be made seamless with tape and finished with putty.false ceiling to be painted to two coat of white plastic emulsion over a coat of putty	1000.00	sft		
2	DOUBLE SKIN SOLID/SEMI GLAZED PARTITION (7.5cm Thick)				

	Providing and fixing double skin partition with heights of 90/120cm for half cabin and about 240Cm for other partitions (refer the drawing enclosed). Partition should have an overall thickness of 7.5cm and shall be provided with base frame in 19mm BWR 303 ply that is 5cm wide at about 40cm c/c. Bottom part of the base frame shall be fixed to existing floor with anchor bolts. The partition shall be finished on both sides with 1mm thick laminate (specified colour) over 6mm BWR 303 ply. Partitions certain cabins and other specified areas shall be provided with 12mm thick plain glass.	600.00	sft		
	Partition should have an overall thickness of 7.5cm and shall be provided with base frame in 19mm BWR 303 ply that is 5cm wide at about 40cm c/c. Bottom part of the base frame shall be fixed to existing floor with anchor bolts. The partition shall be finished on both sides with 1mm thick laminate (specified colour) over 6mm BWR 303 ply.				
	The cost should include removing & refixing of usable Glass from existng partition and the same are will not be taken for measurement.				
3	Providing and fixing flush doors (3'x7') with vision glass (6mm BWR 303 ply on both sides over suitable frame) with laminated front and back (refer drawing) for records room, . All the doors shall be provided with heavy duty brass hinges (2 nos.), godrej lock and SS handles.	3.00	nos		
4	Cabin Door- Removing and Fixing existng door and door closers in all respect	2.00	nos		
5	Entrance Door- Removing and Fixing existng entrance door and door closers in all respect	1.00	nos		
6	Providing and fixing new floor spring of Dorma xlc, Godrej/Hemco/Enox (If required only)	2.00	nos		
7	Providing and fixing 12 mm thick glass with polished edges shall be fixed with necessary SS brush finish brackets/wooden partition support on tables front and side .	22.50	sft		
8	FIRE PRRF PARTITION WITH DOOR FOR UPS				
	Providing and fixing full height double skin partition for UPS room (refer the drawing enclosed). Partition should have an overall thickness of 7.5cm and shall be provided with 12mm thick bison panel (cement sheet) board over frame work made of 1.6mm thick 50mm x 50mm zinc coated G.I. box sections at 60cm c/c spacing both ways and consisting of floor and ceiling flanges of suitable size which are to be fixed to ceiling/ floor with suitable anchor bolts.	150.00	sft		

	The boards shall be fixed to both sides of frame work with suitable screws on G.I. sections a spacing of 30cm c/c. The joints of boards shall be such that it staggers, so as to avoid cracking. The boards shall be finished with recommended jointing compound and two coats of cement primer.				
	TABLES				
9	Fabricating and positioning 145 cm X 75cm(w) x 75cm (H) counter table using 18/19 mm IS 303 BWR GRADE plywood, laminated to approved color, Outer surface of drawers and shutters to be laminated and painted inside to white and to have SS handles and godrej locks. Key board drawer to be with telescopic sliders and a CPU stand also to be provided. 12MM THICK GLASS ALSO TO BE PROVIDED ON TABLE TOP Plywood to be used- Anchor/ Green ply/ Century; Laminate to be used - Green lam/ Marino/ Euro	2.00	nos		
10	Fabricating and positioning 150 cm X 75cm(w) x 75cm (H) counter table using 18/19 mm IS 303 BWR GRADE plywood, laminated to approved color, Outer surfaces of drawers and shutters to be laminated and painted inside to white and to have SS handles and godrej locks. Key board drawer to be with telescopic sliders and a CPU stand also to be provided. 12MM THICK GLASS ALSO TO BE PROVIDED ON TABLE TOP Plywood to be used- Anchor/ Green ply/ Century; Laminate to be used - Green lam/ Marino/ Euro	1.00	nos		
11	Running counter Tables (2 nos) - Fabricating and positioning 75cm(w) x 75cm (H) counter table using 18/19 mm IS 303 BWR GRADE plywood, laminated to approved color, Outer surfaces of drawers and shutters to be laminated and painted inside to white and to have SS handles and godrej locks. Key board drawer to be with telescopic sliders and a CPU stand also to be provided. 12MM THICK GLASS ALSO TO BE PROVIDED ON TABLE TOP Plywood to be used- Anchor/ Green ply/ Century; Laminate to be used - Green lam/ Marino/ Euro	4.20	Rmtr		
12	Carefully Removing and Refixing of existing Second Manager Table, Side table, at new location.	1.00	Ls		
13	Carefully Removing and Refixing of existing Manager Cabin Table, Side table, behind storage units at new location.	1.00	Ls		
14	Carefully Removing and Refixing of existing 9nos staff tables at new location.	1.00	Ls		
15	FULL HEIGHT/LOW STORAGE	220.00	sft		

	The width and height of the cupboard is shown in the drawing All horizontal and vertical partitions, rear side and cupboard doors are made of 19 mm thick BWR 303 plywood finished with 1 mm thick laminate of approved colour.(IS 303). The front portion of the cupboard is to be provided with openable shutters using 19 mm thick BWR 303 plywood finished and all the exposed faces are finished with 1 mm laminate (shade and colour as per the drawing) and the inner portion is painted with 2 coats of enamel paint over a coat of wood primer and putty as shown in the drawing.				
	Necessary fittings such as auto closing hinges, magnetic lock, ball catches, 200 mm long SS finish handle etc should be provided in each shutter. Necessary PVC edge banding shall be given in all visible/exposed edges. Skirting for a height of 10 cm should be provided as per the drawing.				
16	Cupboard for Electrical panel : Providing and fixing electrical panel board area shutter (openable and partly louvered) made out of 19mm thick BWR grade ply boxing, shutters.1.0mm thick laminate finish on front, with app. colour polish to external edges brass hinges, handles etc. as per the details. The shutters should have 12" ht. All. Powder coated louvers on top and bottom for ventilation.	28.00	sft		
17	Dismantling / Shifting existing counters/ tables/ cutting of partitions/ partitions/exsistng false ceiling to a space for functioning of the branch during the proposed renovation work, as directed by the bank. The work shall include all labour charges and materials required for shifting/ dismantling.	1.00	Ls		
18	PANELLING THE COLUMNS/Manager Cabin : Fixing wall panelling for columns in specified area from floor level up to false ceiling level using laminate finish over 6mm ply.	350.00	sft		
19	Change of Laminate- Removal of Old laminate and Providing and fixing 1.00 m thck new laminate over existing surface by using proper adhesive for partition, tables, drawers, storage	100.00	sft		
	TOTAL FOR BALUSSERY BRANCH WORK (EXCLUDING GST)				

SR NO	NAME OF WORK	AMOUNT (Rs.)
1	FURNISHING WORKS OF CANARA BANK, ORKATTERY BRANCH	
2	FURNISHING WORKS OF CANARA BANK, PAYANTHONG BRANCH	
3	FURNISHING WORKS OF CANARA BANK, BALUSSERY BRANCH	
	TOTAL TENDER COST (EXCLUDING GST)	

(All cost is excluding GST)

(Please note that the tender is a combined tender for 3 sites and the vendor has to quote for all three site)

I have read and understood the all the terms and conditions and quote my rates as above.

Date:

Name:

Place:

Signature of the Vendor: